

Rebates for your home

Thank you for your commitment to energy efficiency



Confirm you're qualified

You have the option to:

- 1) Contact an Energy Advisor at 1-800-562-1482 Monday through Friday 8 a.m. to 5 p.m.
- 2) Review rebates qualifications by category at pse.com/rebates
- 3) Review individual incentive qualifications on the second page of this document

Fill out your account, name, address and home information

Account # (where equipment is installed)				Name (check payable to)			
Address (where equipment is installed)				City		State	Zip
Mailing Address				City		State	Zip
Email Address				Phone #			
Type of Home		<input type="checkbox"/> Site-built <input type="checkbox"/> Manufactured		Year Home was Built		Home is a Rental <input type="checkbox"/>	
Heating Type Prior to Rebate		<input type="checkbox"/> Natural Gas <input type="checkbox"/> Electric <input type="checkbox"/> Oil <input type="checkbox"/> Propane					
Heating Equipment Prior to Rebate		<input type="checkbox"/> Heat Pump <input type="checkbox"/> Baseboard/Ductless HP <input type="checkbox"/> Forced-Air Furnace <input type="checkbox"/> Boiler					

Select the rebate product(s) you are applying for and enter product information

Electric Home Heating		Gas Home Heating		Water Heating	
<input type="checkbox"/> Electric Forced-Air Furnace to Heat Pump Conversion (\$1,500) <input type="checkbox"/> Air-Source Heat Pump Tier 2 [9.0 HSPF/14 SEER] (\$350) <input type="checkbox"/> Air-Source Heat Pump Tier 3 [10.0 HSPF/16 SEER] (\$800) <input type="checkbox"/> HSPF Heat Pump Sizing & Lockout (\$300) <input type="checkbox"/> Ductless Heat Pump (\$1,200) <input type="checkbox"/> Geothermal Heat Pump (\$1,500)		<input type="checkbox"/> Furnace (\$350) <input type="checkbox"/> Fireplace (\$200) <input type="checkbox"/> Boiler (\$350) <input type="checkbox"/> Integrated Space & Water Heat (\$800)		<input type="checkbox"/> Heat Pump Water Heater Tier 1 (\$500) <input type="checkbox"/> Heat Pump Water Heater Tier 2 (\$800) Heat Pump Water Heater Install Location <input type="checkbox"/> Attic <input type="checkbox"/> Garage <input type="checkbox"/> Crawl Space Other _____	
Fuel Conversion			Replacement and Storm Windows (\$50/window up to \$750)		
Conversion Type <input type="checkbox"/> Home & Water Heat (up to \$3,550) <input type="checkbox"/> Home Heat Only (up to \$2,600) <input type="checkbox"/> Water Heat Only (up to \$950)		Previous Type <input type="checkbox"/> Baseboard <input type="checkbox"/> Forced-air		Square feet of windows/patio doors being upgraded Single _____ Double _____ Number of windows/patio doors upgraded Single _____ Double _____ Total number of windows/patio doors installed _____	
Product Information and AHRI Certificate (AHRI for Heat Pump Products Only)					
Brand/Model(s)			AHRI Number		

Attach a copy of your final installation invoice or receipt

Your installation invoice or receipt must include an installation date, brand and model number(s) of all rebated equipment.

- For Heat Pumps: Include the heat pump, air handler and/or coil model number on the invoice
- For Heat Pump Sizing & Lockout: Include PSE sizing document with invoice
- For Windows: *See back page

Sign the terms and conditions

I acknowledge that the product(s) described above have been purchased and installed at the location indicated. I understand that PSE provides rebate incentives for measures that are designed to save energy but I acknowledge that estimated energy savings are not guaranteed and I understand that PSE has made no express warranties or representations with regard to these products or their installation. I acknowledge that I am responsible for meeting applicable code requirements, determining the adequacy of installation, and paying all amounts owed to contractors/suppliers. Further, I understand that this is a tiered service and is subject to change or termination without prior notice. PSE reserves the right to inspect any installation prior to rebate approval and/or after rebate payment and I agree to provide PSE reasonable access for such purposes. I authorize PSE to release my customer account information, including my billing and energy usage information, to an independent, third-party evaluator solely for the purposes of evaluating this rebate program, confirming energy savings and for other quality assurance purposes. The disclosure of your private information will comply with PSE's privacy policy and state regulation.

Signature (typed signature is accepted)	Date
---	------


EMAIL

PRINT

CLEAR

Rebates for your home

Thank you for your commitment to energy efficiency



Submit your complete application and invoice or receipt

By email: rebates@pse.com

By mail: Puget Sound Energy/Energy Efficiency Rebates, P.O. Box 97034 BOT-01H, Bellevue, WA 98009-9734

General Qualifications

- Must be a current PSE residential customer for all of the following rebates.
- Rebate application must be submitted within 30 days of installation.
- Qualifying electric equipment must be installed in PSE's electric service area. Qualifying gas equipment must be installed in PSE's gas service area.
- Applies to existing single family properties or individually metered attached housing with four units or less. Multi-family and commercial accounts will not qualify.
- Rebates only available on new, qualifying equipment.
- Cannot be combined with any other rebates except where noted.
- Must install to comply with all federal, state and local code requirements.
- Equipment that is replaced under warranty will not be eligible for second rebate.
- One rebate per qualified single-family residence.
- Rebate cannot exceed the pre-tax purchase price of any rebated product.

Electric Forced-Air Furnace to Heat Pump Conversion

- Must have an existing electric forced-air furnace used as your primary heating source.
- Must upgrade to an air-source heat pump system that is AHRI Certified with an 8.5 HSPF/14 SEER rating or better.
- Customers with existing gas furnace or boiler are not eligible.
- Can be combined with Heat Pump Sizing & Lockout Controls rebate.
- Customers who do not qualify for this rebate may qualify for the Air-Source Heat Pump rebate if equipment meets qualifications.

- Must be installed in main living area. Bedroom installations are not eligible.
- Can be combined with other space heating rebates.
- For a list of qualifying products, go to pse.com/replace.

Boiler

- Must install an AHRI or ENERGY STAR qualified natural gas boiler with 95% AFUE rating or better.
- Indirect water heaters installed off boiler are not eligible for additional rebate incentives. Standalone water heaters are still eligible provided it meets efficiency requirements.

Air-Source Heat Pump

- Heat pump system must be AHRI Certified® with a 9.0 HSPF/14 SEER rating or better.
- Heat pumps with a 9.0 HSPF/14 SEER rating are eligible for a rebate of \$350.
- Heat pumps with a 10.0 HSPF/16 SEER rating are eligible for a rebate of \$800.
- Auxiliary heating sources do not qualify for additional rebate incentives (e.g., natural gas furnace).
- Can be combined with Heat Pump Sizing & Lockout Controls rebate.

Integrated Space & Water Heater

- Must use a single source ENERGY STAR or AHRI .90 EF natural gas tankless water heater or 95% AFUE natural gas boiler for both home heating and water heating.
- May be completely hydronic/radiant or a combination of forced-air and hydronic/radiant systems.

Heat Pump Sizing & Lockout Control

- Propane or natural gas furnaces installed as auxiliary heat are not eligible.
- Customers with an existing air-source heat pump or installing a new air-source heat pump must provide PSE sizing documentation completed by a qualified contractor indicating system is properly sized for the home.
- Newly installed air-source heat pump must be AHRI performance certified with an 9.0 HSPF/14 SEER or better.
- Existing heat pumps do not need to meet efficiency requirements but cannot be more than 12 years old.
- Heat pump lockout control must be set to 40 degrees F and heat pump must be sized at 30 degrees F.
- Can be combined with Air-Source Heat Pump and Electric Forced-Air Furnace to Heat Pump Conversion rebates only.

Windows (Single-pane Replacement & Double-pane Low-e Storm)

- Applicant must be utilizing PSE electricity or PSE natural gas as the primary source of home heat.
- For replacement incentive, must upgrade from existing single-pane wood or metal framed windows to energy-efficient windows.
- Prime windows must have an NFRC rated U-factor of .30 or lower. Patio doors must have an NFRC rated U-factor of .35 or lower.
- For low-e storm incentive: must upgrade from existing double-pane metal framed windows to low-e storm window.
 - » Storm windows must use glazing materials with an emissivity less than or equal to 0.22 and a solar transmittance greater than 0.55.
 - » Storm windows must be of the same opening type as the existing prime window.
 - » Storm window shall be permanently installed.
 - » Storm windows shall be oriented with the low-e coating facing toward the interior of the house.
- For installations with metal framed prime windows, the storm window's frame shall not be in direct contact with the prime window frame.
- Windows incentives do not apply to new construction, additions that expand the home's square or cubic footage, or installations in unheated areas of the home.
- When submitting your application and paid installation invoice, please include:
 - » Total measurement and number of single and/or double-paned windows or patio door being upgraded.
 - » Measurements of each rebated window and/or patio door installed.
 - » Copy of packing slip (preferred) or NFRC stickers for each rebated window or patio door showing the U-Factor for single-pane window upgrades, and emissivity and solar transmittance for double-pane low-e storm window upgrades.

Ductless Heat Pump

- Must be AHRI certified as mini-split heat pump, use inverter technology and be a minimum of 1.0 ton in heating mode and have an HSPF of 9.0 or greater.
- Must use electric resistance heat as primary source which includes electric zonal (baseboard, cable, wall heater), electric hydronic or electric forced-air-furnace.
- Must install at least one unit in the main living area of the home. Bedroom-only installations do not qualify.
- Customers with existing heat pump or natural gas service, even if only used for cooking, are not eligible.
- Customers who do not qualify for this rebate may qualify for the Air-Source Heat Pump rebate if equipment meets qualifications.

Fuel Conversion

- Applicant must be a PSE electric customer currently using electricity as the primary source of home and/or water heating.
- Call a PSE Energy Advisor at 1-800-562-1482 for pre-approval (M-F, 8 a.m. - 5 p.m.).
- Rebate is subject to 12-month prior electric usage requirements, as determined by PSE.
- Applicant must install ENERGY STAR qualified natural gas heating and water heating equipment (replaces are not eligible).
- Applicant is ineligible for home heating rebate if a heat pump is installed in conjunction with natural gas equipment or if existing heat pump remains on the premises.
- May switch from PSE electric to any natural gas provider.
- Rebate amount is limited to 75 percent of total equipment and installation cost.

Heat Pump Water Heater

- Must be installed outside the conditioned living space such as a garage, attic or crawl space.
- Qualifying models must be NEEA Northern Climate Specification approved. List can be found at pse.com/heatpumpwaterheater.

Furnace

- Must install an AHRI or ENERGY STAR® certified natural gas furnace with 95% AFUE or better.
- Must be the primary source of heat. Cannot be installed with a new or existing heat pump. Any natural gas furnace installed with heat pump is not eligible and heat pump qualifications will govern.

Fireplace

- Must meet Canadian P4 FE of 70% or better, be direct vent and have electronic ignition. Both direct vent, pilot on-demand and power vent fireplaces are eligible.