

RFP Appendix A-1.4 - Solar



Solar Photovoltaic Renewable Resource Technical Specification 2021



**RFP APPENDIX A-1.4 SOLAR
WORK SPECIFICATIONS (BTA)**

TABLE OF CONTENTS

1.0	ACRONYMS AND ABBREVIATIONS.....	IV
2.0	LIST OF APPENDICES TO APPENDIX A	1
3.0	REFERENCE PACIFICORP STANDARDS.....	2
4.0	TECHNICAL SPECIFICATION.....	4
4.1.	Introduction and Seller Responsibilities.....	4
4.2.	Performance Characterization.....	5
4.3.	Permitting	5
4.4.	Construction and Installation	5
4.5.	Site and Plant Description	6
4.6.	Design and Engineering.....	6
4.7.	Engineering Design Package	6
4.8.	Site Layout, Maps, Line Drawings.....	7
4.9.	Structural Engineering	7
4.9.1.	Geotechnical Analysis	8
4.9.2.	Environmental Loads	8
4.9.3.	Racking/Tracking Foundations and Supports	9
4.9.4.	Equipment Pads.....	9
4.9.5.	Corrosion Protection	9
4.9.6.	Single Axis Tracking Structures.....	9
4.10.	Civil Engineering	10
4.10.1.	Human Access	10
4.10.2.	Erosion Control	10
4.10.3.	Grading and Drainage	11
4.10.4.	Dust Control	12
4.10.5.	Fire Prevention and Protection	12
4.10.6.	Construction Access	12
4.10.7.	Site Access Roads	12
4.10.9.	Excavation	14
4.10.10.	Construction Signage	14
4.10.11.	Fencing.....	14
4.10.12.	Site Finish Grade	14
4.11.	Electrical Engineering	14
4.11.1.	Communication System	15
4.11.2.	Communications System Testing and Warranty	15
4.11.3.	Security	15
5.0	EQUIPMENT	20
5.1.	Equipment Supply	20
5.2.	Signage and Labeling	21

- 5.3. Grounding and Bonding 22
- 5.4. Surge and Lightning Protection 22
- 5.5. Surge Protection 22
- 5.6. SPDs for PV DC Power Circuits..... 23
- 5.7. SPDs Applied on AC Power Circuits 23
- 5.8. SPDs for Measurement, Control, Instrumentation and Communications Circuits 23
- 5.9. External Lightning Protection System (LPS)..... 24
- 5.10. Photovoltaic Modules 24
- 5.11. Padmount Transformers 26
- 5.12. Inverters 27
- 5.13. Medium Voltage Cable and Equipment..... 30
- 5.14. Overcurrent Protection Devices..... 30
- 5.15. Surge Arresters 31
- 5.16. Switches 32
- 5.17. Relays..... 32
- 5.18. Instrument Transformers 33
- 5.19. Battery & Battery Chargers 33
- 5.20. Fiber Optic Cable and Data Conductors 34
- 5.21. Raceways, Conduit Bodies & Boxes 34
- 5.22. Fixed Tilt Racking Structure 35
- 5.23. Single Axis Tracking Structure 35
- 5.24. Direct Current Fused Combiner Boxes..... 36
- 5.25. Meteorological Stations 36
- 5.26. Supervisory Control and Data Acquisition..... 37
- 5.27. Revenue Meter..... 38
- 5.28. Security Cameras and Related Equipment 39
 - 5.28.1. General Requirements 39
 - 5.28.2. Security System Components 39
 - 5.28.3. Video Wiring System..... 40
 - 5.28.4. Network Video Recorder and Multiplexor 41
 - 5.28.5. Security Software..... 41
- 5.29. Wires, Cable and Connectors..... 41
- 5.30. Plant Switchgear 42
- 5.31. Emergency Direct Current Battery System 42

- 6.0 WARRANTIES..... 42
 - 6.1. General Seller Warranty 42
 - 6.2. Solar Module Warranty 42
 - 6.3. Inverter Warranty..... 43
 - 6.4. Transformer Warranty..... 43
 - 6.5. SCADA Monitoring System and Security Equipment Warranty 43
 - 6.6. Performance Warranty 43

- 7.0 APPLICABLE CODES AND STANDARDS 43

- 8.0 DISTRIBUTION OR TRANSMISSION INTERCONNECTION 43

- 9.0 OPERATIONS AND MAINTENANCE — MANUALS AND TRAINING 44
 - 9.1. Documentation..... 44

9.2.	Manuals	44
10.0	SPARE PARTS	46
11.0	TOOLS AND EQUIPMENT	46
12.0	FINAL PLANT COMPLETION	46
12.1.	Step 1 Mechanical and Electrical Completion	47
12.2.	Synchronization Procedures and Requirements	47
12.3.	Step 2 Quality Assurance/Quality Control	47
12.4.	Step 3 Commissioning and Startup	48
12.5.	Step 4 Interim Operating Period	49
12.6.	Training	49
12.7.	Operator Training	49
12.8.	Maintenance Training	49
12.9.	Step 5 Capacity Test	50
12.10.	Step 6 Substantial Completion	51
12.11.	Step 7 Final Completion	51
12.12.	Requirement for Final Completion.....	52
12.13.	Procedures for Final Completion	52

1.0 ACRONYMS AND ABBREVIATIONS

AC	alternating current
A	ampere
ASCE	American Society of Civil Engineers
ASTM	American Society for Testing and Materials
CPT	control power transformer
DC	direct current
EL	electroluminescence
IEC	International Electrotechnical Commission
IEEE	Institute of Electrical and Electronics Engineers
kW	kilowatt
kWh	kilowatt hour
LPS	lightning protection system
MW	megawatt
MW _{AC}	megawatt alternating current
NEC	National Electric Code
NEMA	National Electrical Manufacturers Association
NFPA	National Fire Protection Association
O&M	operation and maintenance
PCB	polychlorinated biphenyl
PCC	Point of Common Coupling
PV	photovoltaic
PVC	polyvinyl chloride
QA/QC	quality assurance/quality control
SCADA	supervisory control and data acquisition
SCCR	short-circuit current rating
SPD	surge protection devices
SWPPP	Storm Water Pollution Prevention Plan
TÜV	Technischer Überwachungsverein
UL	Underwriters Laboratories, Inc.
V	Volt

V _{AC}	volts alternating current
V _{DC}	volts direct current
VDE	association for electrical, electronic, and information technologies

2.0 LIST OF APPENDICES TO APPENDIX A

- A-1 Not Used
- A-2 Interconnection Agreement (Seller provided)
- A-3 Permit-Matrix (Seller provided)
- A-4 Not used
- A-5 Project One-line Drawing and Layout (Seller provided)
- A-6 Division of Responsibility (Owner provided)
- A-7 Owner Standards and Specifications (Owner provided)
- A-8 PVSYST Performance Summary Report (Seller provided)
- A-9 Product Data Input Supply Forms (Seller provided)
- A-10 Not Used

3.0 REFERENCE PACIFICORP STANDARDS

RFP Appendix A-7 contains the following Owner standards that apply to this specification:

- (01) Attachment 1A Project Document Formatting and Requirements.
- (02) Attachment 1B Project Document Deliverables.
- (03) Computer Aided Design (PacifiCorp Energy) General AutoCAD/Drafting Standards (Specification DCAP876).
- (04) Renewable Resources: Engineering Procedures/CAD Standards, Volume 8 Consultant Drafting Procedures and Standards (For Engineering Drawings)
- (05) 04.1 Substation Equipment Power Transformers, ZS-001 and b) 04.2 Two-Winding Distribution Transformer, ZS-102.
- (06) Material Specification ZS 061, Electrical Equipment-Insulating Oil.
- (07) Material Specification ZS 065, Wind, Ice, and Seismic Withstand.
- (08) Material Specification ZS 066, Contaminated-Environment Protection.
- (09) Procedure SP-TRF-INST, Transformer Receiving, Installation and Testing.
- (10) Asset Management Form 006F, Meter and Relay Equipment Memorandum.
- (11) PacifiCorp Engineering Handbook, Part 6B.5 Fence Application and Construction.
- (12) PacifiCorp Engineering Handbook, Part 6B.6 Substation Grounding.
- (13) PacifiCorp Protective Relaying Standard, Document Number: GEN-ENG-RELAY-0001.
- (14) PacifiCorp Protective Relaying Standard, Arc Flash Hazard Standard, Document: GEN-ENG-RELAY-0002.
- (15) PacifiCorp Protective Relaying Standard, "Relay Current Transformer (CT) & Potential Transformer (PT) Insulation Integrity Test," Document: GEN-ENG-RELAY-0003.
- (16) PacifiCorp Protective Relaying Standard, "Thermal Plant Protective Relay Maintenance and Testing-PRC-005," Document: GEN-ENG-RELAY-1003.
- (17) PacifiCorp Protective Relaying Standard, "Relay Testing & Commissioning Checklist."
- (18) PacifiCorp Protective Relaying Standard, "Relay Installation Procedure," Document: GPCP-EQPMNT-INST.
- (19) PacifiCorp Protective Relaying Standard, "Current Transformer Installation Procedure (Relay)," Document: GPCP-CT-INST.
- (20) PacifiCorp Protective Relaying Standard, "Current Transformer Installation Form (Relay)," Document: GPCP-CT-INST.
- (21) PacifiCorp Substation High-Voltage Warning Signs, SG-001.
- (22) Specification for Substation Equipment Installation Testing and Commissioning.
- (23) SV002 Bird and Animal Protection-General Installation Instructions
- (24) SV251 Bird and Animal Protection for Miscellaneous Equipment

(25) TD051 Danger Sign

OTHER RELEVANT DOCUMENTS

PacifiCorp “Open Access Transmission Tariff”. FERC Electric Tariff

4.0 TECHNICAL SPECIFICATION

This is Appendix A - Solar “Solar Photovoltaic Renewable Resources 2020 – Technical Specification”, which will subsequently become a contract document, as a supplement to the Build Transfer Agreement (“The Agreement”). Capitalized terms used and not defined herein have the meanings given in the Agreement unless the context requires otherwise.

4.1. Introduction and Seller Responsibilities

Seller shall provide all required services and materials for the successful completion of the Plant. Seller’s responsibilities shall include environmental permitting, design, engineering, procurement of equipment, Site preparation work, foundations, installation of all equipment, bulk material and commodities supply, and Site finishing work. Seller also shall deliver project management, construction management, commissioning and startup, and testing of work, all as described in this document including all referenced appendices and standards which will subsequently become a contract document.

Seller shall construct all roads, foundations, electrical systems, control systems, monitoring systems, communications, ancillary structures, storage facilities, security systems, and fencing, and shall erect and commission and start-up the photovoltaic (PV) System in the locations and orientations set forth in the Site plan and Site layout drawings and in accordance with this document, and all related specifications that relate thereto.

Installation of the PV System shall be performed by a recognized, experienced Contractor in accordance with federal, state, local, and utility specifications and requirements and in accordance with the relevant state energy office. The electrical installation of the PV System shall be performed in accordance with the same requirements. The Work shall be performed by an electrical contractor licensed in the state where the project will be constructed. The work shall be performed by a licensed Contractor approved by the relevant State authority. Seller shall provide comprehensive onsite construction management for the Plant and shall commission and start-up the Plant. Seller shall manage, supervise, inspect, and furnish all labor, equipment, materials, temporary structures, temporary utilities, products, and services related to the foregoing, all on a turnkey basis.

These specifications are intended for use by Sellers providing a Solar PV Plant to be owned by PacifiCorp (Owner). The PV Plant shall be designed, built, commissioned, and started-up by the Seller based on these PV Specifications, and all other Owner requirements including its interconnections for connecting to the transmission or distribution system. Upon completion of the quality assurance/quality control (QA/QC) procedures and Plant Acceptance the PV Plant shall be turned over for care and custody by Owner. Seller shall perform the Work in accordance with the following:

- (01) In a manner that is sufficient, complete, and adequate in all respects necessary for the Plant to successfully achieve Final Acceptance by the Guaranteed Final Acceptance Date.
- (02) In conformance with the professional standards, skill, expertise, and diligence of design and construction of professionals regularly involved in utility-grade, utility-scale, grid-connected solar PV power projects in the United States.
- (03) In compliance with the terms of the contract documents, the operating guidelines, the Utility’s interconnection requirements (**RFP Appendix A-2 – Interconnection Agreement**), and all applicable laws, standards, and permits including PacifiCorp’s “Access Transmission Tariff”, FERC Electric Tariff.

- (04) Approved as to form, use, and content by all government authorities and private entities authorized to administer or enforce any building, electrical, or construction code or standard whose approval of the final design of the Plant, or any portion thereof, is necessary for the construction, operation, or interconnection of the Plant.

4.2. Performance Characterization

The predicted PV system performance estimate must be provided in **RFP Appendix A-8** and is based on the performance characterization data in **RFP Appendix C-2 and C-3**. The predicted PV system performance information that is to be provided shall include the PVSyst report, the 12X24 output in an Excel format, and an hourly profile 8760 output in an Excel format.

4.3. Permitting

Seller shall apply for and obtain all permits and authorizations necessary for construction and to support operations of the Plant, as per the attached permitting matrix (**RFP Appendix A-3**). Copies of all applicable permits will be provided to Owner within 5 business days after they are obtained or completed.

4.4. Construction and Installation

Prior to beginning construction, Seller shall provide a comprehensive onsite construction management plan for the construction of the Plant in accordance with all applicable laws and policies and Health, Safety, and Environmental Plans of the Seller and if work is performed on Owner property, meet all safety program requirements of Owner including Appendix A Contractor Health Safety and Environmental Requirements, Appendix A Contractor Safety Plan Requirements, and all changes to applicable law and Owner policies. No later than 15 days prior to initial Site mobilization, Seller shall prepare and submit such Plans to Owner. Seller shall also provide Owner with an evaluation and appropriate documentation of the safety record for any licensed Subcontractor that will be performing work on the Plant.

Seller shall assemble, construct, and install with its own labor forces and/or with Subcontractors labor, tools, and equipment necessary to complete the Plant, including the following Works:

- (01) Site preparation, including but not limited to drainage required by the civil engineering plan, and remove excess debris
- (02) Coordination with Owner when trenching is performed
- (03) Direct current (DC) cabling and combiner and junction boxes
- (04) Alternating current (AC) trenching and cabling
- (05) Inverters, switchgear, and transformers and accompanying supports and/or concrete pads
- (06) All equipment from the DC solar array up to and including the point of interconnection with the electric utility system
- (07) Perimeter security fencing, access gates, and security systems (described in section A-3.9 Security)
- (08) Security lighting
- (09) Installation of the monitoring system, meteorological station(s), and revenue grade metering.

Installation of all required Customer Owner interconnection structures of equipment – e.g. Substation or disconnects, meter and GOAB poles.

Seller shall provide all utilities necessary during construction, including but not limited to electricity, water, toilets, fuel and communications. Seller shall be responsible for all costs associated with

construction power. The following sections and associated appendices describe the scope of work and technical specification for the Plant.

4.5. Site and Plant Description

Seller shall, at its own cost and expense, design, engineer, procure, construct, test, permit, and start up a utility scale PV solar system with a design output as stated in its proposal.

Except as otherwise expressly provided in the Agreement, Owner is not responsible for providing any material, labor, or services of any kind during Seller's execution of the Work. Seller is fully responsible for all development, permitting, engineering, procurement, construction, interconnection coordination, and startup and testing activities, and shall deliver a complete, operational, and reliable turnkey Plant to Owner. Seller shall provide civil, electrical and structural engineered drawings stamped by an engineer certified in the state where the project will be constructed, materials and equipment, installation of PV modules, installation of electrical systems including inverters, electrical connection to the existing electrical infrastructure, and construction of mounting structures on which the PV modules are installed. Seller shall provide comprehensive onsite construction management for the Plant and shall commission the Plant. Seller shall manage, supervise, inspect, and furnish all labor, equipment, materials, temporary structures, temporary utilities, products, and services related to the foregoing, all on a turnkey basis.

4.6. Design and Engineering

Seller shall design and engineer the Plant in accordance with prudent utility practices, with the professional standards, skill, expertise, and diligence of design and construction of professionals regularly involved in utility-grade, utility-scale, grid-connected solar PV power projects for public utilities in the United States. The design must conform to the requirements and conditions of all applicable permits, codes and standards, and laws, and it must be in compliance with the operating guidelines and meet the Owner specifications.

Seller is responsible for all engineering for the Plant. All design drawings, specifications, and calculations shall be signed by a professional engineer-of-record in the state where the project will be constructed. The Agreement provides for submission to Owner of complete design drawings, data, and documents for review and comment. These engineered design drawings, data, and documents must be submitted to Owner for review and comment before construction is to begin.

Seller is responsible for ensuring that all components are installed min 1 foot above the 100-year flood plain (e.g., inverter stations, substation, supervisory control and data acquisition [SCADA] system, Security System, control building, PV modules, tracker motors, switchgear, transformers, combiner boxes, etc.). The Seller is responsible for ensuring that all PV modules and combiner boxes are installed above the maximum snow height.

Any third-party study or independent engineering reviews including, but not limited to, the geotechnical study and the corrosion study shall be provided to Owner.

4.7. Engineering Design Package

Based on the review of the Plant Site and infrastructure, Seller shall design (or have designed by consulting engineers) a Plant (including all layout, civil, electrical, and structural components) that will produce the required electricity and that is capable of being operated in a safe, normal, reliable, and continuous manner as required by the contract documents at all operating conditions and modes specified below. The system design shall comply with all applicable laws and regulations and applicable permits. Owner may utilize a third-party or independent engineering consultant to perform technical reviews. Studies prepared by the Seller's third-party consultants shall be provided to the Owner for review.

The Engineering Design Package shall include but not be limited to all items required in **Appendix A-7.2 Attachment 1B – Project Document Deliverables:**

- (01) Studies related to the project, such as the geotechnical engineering report and the lightning protection study
- (02) Schematic and preliminary designs
- (03) Design calculations
- (04) All drawings including mechanical, electrical, structural, civil, and construction drawings (Site plans, schematic single lines, wiring diagrams and detail drawings). Drawings shall follow **Appendix A-7.03**.
- (05) Project schedule
- (06) Product description information
- (07) Bill of Materials
- (08) Equipment details, descriptions, and specifications
- (09) Commissioning and start-up plan
- (10) Full power test plan (capacity test)
- (11) Layout of equipment
- (12) GIS Shapefiles of all project equipment (transformers, junction boxes, overhead line poles, access roads, etc.)

The Engineering Design Package shall be provided prior to commencement of construction.

4.8. Site Layout, Maps, Line Drawings

Prior to beginning construction or procuring equipment, Seller shall submit to Owner Site layout design drawings, data, and documents for review. The design shall include a vehicle access road to provide maintenance, cleaning, and public safety access with a 30-year service life (assuming regular maintenance) that shall comply with state and local county surface requirements.

The Seller shall plan and execute construction of earthwork methods and culverts (or other water control devices) to control surface drainage from cuts and fills and prevent erosion and sedimentation in compliance with the Storm Water Pollution Prevention Plan (SWPPP).

4.9. Structural Engineering

Seller shall supply or design the PV arrays' mounting systems, foundations, and piers, as well as any equipment pads and buildings on the Site. The designs of these components shall be based on the requirements of applicable codes, standards, and permits, and the information/specifications provided by the module, inverter, transformer, switchgear, racking/tracking structures, and all other vendors.

Concrete designs shall conform to the requirements listed in the latest applicable editions of ACI 318 Building Code Requirements for Structural Concrete (ACI 318) and ACI 336.1-01 Specification for the Construction of Drilled Piers, if applicable. At a minimum, compressive strength of concrete shall not be less than 4000 psi (28 MPa).

Steel designs shall conform to the requirements listed in the latest applicable edition of AISC Manual of Steel Construction. Seller shall be responsible for full design of all structural components including connections. Load combinations used in design shall be defined as according to the latest edition of ASCE 7 or local applicable codes, whichever is most restrictive. The designer shall consider various wind load configurations to ensure that the most critical loading conditions are captured.

Welding shall be performed in accordance with AWS D1.1 Structural Welding – Steel (AWS) by AWS certified welders. The Seller shall ensure that installation tolerances and structural deflection are followed.

4.9.1. Geotechnical Analysis

Geotechnical analysis shall be provided by Seller and performed by a qualified geotechnical engineering firm employing a licensed Professional Engineer. The results of the analysis shall be used when designing the foundations for the structures on the Site.

At a minimum, the following should be included in the analysis:

- (01) Review publicly available geotechnical information and reports. This may include soils and geologic maps and literature, photographs, hydrogeology reports, groundwater reports, and water well data.
- (02) Coordination and mobilization of the geotechnical services team for subsurface exploration of the Site. This should include working with the local utilities to mark any existing underground utilities (such as cables, gas lines, piping, etc.) in advance of mobilization.
- (03) Study the Site to determine the presence of faults, ground fissures, slope instability on the Site or adjacent lands, and other potential geologic hazards that could affect the structural design, construction, and long-term operation of the Plant.
- (04) Drilling or digging of exploratory borings and pits. The amount and depth shall be determined by the Seller's geotechnical engineering firm.
- (05) Performance of cone penetration tests. The amount and depth shall be determined by the Seller's geotechnical engineering firm.
- (06) Laboratory testing of collected soil samples from the borings and test pits. An evaluation of the in-place moisture content and dry density, gradation, plasticity, consolidation characteristics, collapse potential, expansivity, shear strength, soil resistivity for the purposes of determining cable ampacity, chloride content, sodium sulfate content, and solubility potential (total salts) should be conducted.
- (07) Analyze the corrosivity of the soil. Include a recommendation for the type of cement to be used in any concrete foundations. Also include recommendations for corrosion protection for underground steel, including rigid metal conduit (such as the need for polyvinyl chloride [PVC] coatings).

Provide design criteria that can be used as required for performing L-Pile calculation – structural soil layers, K values, etc.

A detailed geotechnical report shall be provided outlining the tasks performed and the results of the testing. Included in the report should be any recommendations for the foundation designs, structural support designs, corrosion protection for both underground steel and concrete, pile drive frequency, minimum pile size, and any geologic conditions that may prevent the development of the project. Specifically, an opinion on the viability of driven piles as the PV racking supports should be provided.

4.9.2. Environmental Loads

All structures on the Site shall to be designed using environmental loads as specified in the American Society of Civil Engineers (ASCE) 7-16 (year 2016) code book *Minimum Design Loads for Buildings and Other Structures*. These include wind loads (Chapter 6), snow loads (Chapter 7), rain loads (Chapter 8), ice loads (Chapter 10), and earthquake loads (Chapter 11). Each structure on Site shall be

grouped in Occupancy Category II as defined in Table 1-1 of ASCE 7 - 2016. The corresponding importance factor shall be used for each load calculation.

4.9.3. Racking/Tracking Foundations and Supports

All foundations and supports must be designed using the calculated environmental loads discussed above and soil properties provided in the geotechnical report. Foundations and supports shall meet the recommendations found in the geotechnical report. Foundations and supports shall be designed for a minimum 30-year lifetime, including all environmental factors and corrosion. Foundations and supports should be designed to withstand the impacts and contact pressure from the installation method (such as a vibratory hammer). Any damage to corrosion protection coatings during installation should be repaired. Foundations and supports, including any field-applied modifications (e.g., holes drilled), shall meet the requirements in Corrosion Protection. The pile calculations shall account for the top 12 inches of soil to not have any load bearing capacity due to long term erosion and other effects over the course of the structure life. Pre-drilled or other special foundation types will be evaluated on a case by case basis.

4.9.4. Equipment Pads

All equipment pads shall be located such that adequate personnel access is provided to such equipment. A minimum of 4 feet (or 1.5 meters) horizontal clearance from obstructions that would otherwise limit access to the equipment on the pad shall be provided around all equipment pads. The pads shall be sized sufficiently to allow safety and adequate working space around the equipment. The inverter stations, switchgear, substation (if applicable), and other buildings shall be elevated minimum 1 foot above the Federal Emergency Management Agency 100-year flood plain. The slope of the earthwork around the inverter stations and other equipment shall allow safe and ergonomic access to the equipment.

4.9.5. Corrosion Protection

Corrosion protection shall be utilized on the structures of the Plant. The type and amount shall depend on the selected materials of construction and conditions at the Site. A study of these conditions along with recommendations from the geotechnical report shall be used to design the corrosion protection.

The corrosion protection study shall be performed by a qualified corrosion expert and documented with references and calculations showing that the foundations, supports, racking, fasteners, and conduit shall meet a 30-year design life in aboveground and belowground conditions. If galvanized materials are used, field-applied zinc coatings shall meet American Society for Testing and Materials (ASTM) A780, Standard Practice for Repair of Damaged and Uncoated Areas of Hot-Dip Galvanized Coatings. This standard contains minimum requirements for the material, surface preparation, and application process. For example, repairs to damage due to vibratory pile driving shall conform to ASTM A780.

It is preferred that all holes in structural members requiring galvanization shall have the holes drilled before the galvanization is applied. Should holes be drilled in the field, galvanizing shall be applied to the exposed steel as specified in ASTM A780. All field welds shall have a field-applied galvanization as specified in ASTM A780. For example, if torque tubes with a 3-mil (0.003-inch) hot-dip galvanization are to be welded in the field, a field-applied coating, such as hot stick repair, shall meet or exceed the original 3-mil coating thickness of the torque tube per ASTM A780 requirements.

Only steel bolts with pre-applied corrosion inhibitors or stainless-steel bolts and fasteners shall be allowed in the entire mounting structure.

4.9.6. Single Axis Tracking Structures

In the event a tracking system is utilized, the system shall be designed using the environmental loads and the Occupancy Category as discussed in Environmental Loads. The torque tubes, attachments, module mounting brackets, fastening hardware, foundations, and supports shall have a 30-year design life. Equipment shall have corrosion protection coatings as discussed in section Corrosion Protection.

A common feature of many trackers is the “stow” option during high winds. This feature will change the tracker’s tilt to a more favorable angle to decrease the wind loads on the racking, supports, and foundations during high wind conditions. If a “stow” is required to meet design wind loads, a backup energy source (e.g., a backup emergency battery system) shall be installed on the Site to ensure that the tracker shall be able to move into the stow position if the power from the grid is interrupted during high wind conditions in excess of the vendor’s design limit or the foundation design limit.

4.10. Civil Engineering

Seller shall design all systems in accordance with applicable codes and standards. Seller shall design necessary road improvements to meet state and local transportation codes, standards, conditional use permit stipulations and conditions, and requirements presented by construction equipment, delivery vehicles, and operation and maintenance traffic. Seller shall perform required Site preparation, to include earthworks, SWPPP, and erosion control. Seller shall attempt to minimize earthwork and vegetation disruption for the installation of the Plant to the extent it is compliant with the use permits; however, site grading and surfacing shall be designed to control vegetation to minimize fire danger and provide the ability to operate and maintain the Plant. Any land contours that may affect PV electrical generation should be included in the PV system performance estimate. If required, Seller shall import engineered fill to slope the Site and prevent accumulation of standing water. Any direct burial cabling shall be protected with adequate bedding materials to ensure long-term cable integrity. Dust control shall be maintained in accordance with state and county requirements until Final Acceptance is achieved. Seller shall provide other Site maintenance as needed during construction. Seller shall coordinate interaction between Owner and any permitting authorities regarding the Work.

4.10.1. Human Access

Seller shall make access to all equipment safe and reasonably ergonomic for maintenance staff. For example, if an inverter pad is elevated, the earthwork surrounding the concrete pad shall have a safe approach slope.

4.10.2. Erosion Control

Seller shall submit a location-specific erosion control plan for state and/or local jurisdiction approval prior to construction.

All areas of temporary soil disturbance are to be graded, if necessary, and re-vegetated in a timely manner to limit erosion as required by the local jurisdiction. A weed management plan for site reclamation shall be developed and submitted to Owner for review prior to construction.

All storm water and erosion control measure details to include installation, operation, and maintenance requirements.

The civil design shall include specifying applicable seeding notes and details for temporary and final/permanent site stabilization. Seed mix specifications shall be outlined on the civil plans. Seed mixes to be low lying, native mixes.

Protection of sensitive features during construction as established by environmental, biological, and/or historic studies.

The Seller shall provide an Erosion and Sediment Control Plan document that includes, and not limited to, at least the following sections:

- (01) Initial Land Disturbance
- (02) Construction Period Disturbance
- (03) Stabilization Plan
- (04) Post Construction Stabilization Plan
- (05) Long Term Maintenance Plan

4.10.3. Grading and Drainage

The grading and drainage plan shall be designed and installed in accordance with state and/or local code and permit requirements. All structures required for the drainage plan, if any, shall comply with state standard specifications for drainage facilities.

The Seller shall design the site in a manner which properly manages storm water and/or groundwater such that minimal pooling/ponding of water occurs in any of the array or access road areas. Efforts shall be made to minimize earthwork and balance total cut/fill on site for a zero off-haul/import condition. Efforts shall be made to balance different areas on site to limit the earthwork haul lengths as most practical.

Efforts shall be made to maintain the pre-construction drainage patterns and peak flow rates at the outlet locations, for the post-construction condition.

Grading and associated earthwork shall be considered for site optimization and racking selection. Grading shall be conducted to allow installation of racking system per any mechanical and other installation tolerances.

Earthwork quantities shall be tabulated on the civil plans.

The Base Flood Elevation shall be determined based on the higher elevation and worst effect scenario between the Official Floodplain limits published by the authorities or the site-specific study to determine the flood height. The site-specific study shall take into consideration a 100-year Design Event (statistically computed) and/or local Historical Storm data. 100-yr Design Event (statistically computed) and/or check with local Historical Storm.

The site shall be designed such that all critical electrical equipment (combiner boxes, inverters and transformers) have a minimum freeboard height of 1 foot above the Water Surface Elevation or applicable Base Flood Elevation (BFE) as determined in the site Hydrological and Drainage Study Report. All PV modules have a minimum freeboard of 1 foot above the WSE or applicable BFE. Additionally, the site design shall meet any governing agency requirements. If requirements conflict, the more stringent requirement shall govern.

Grading, Storm Drainage and Erosion Control Plan. Contracted civil engineer (contracted by Seller) will prepare a grading and erosion control plan in accordance with state and/or local municipality requirements. Plan will depict federal, state and locally regulated waters and required buffers, as appropriate. Contracted engineer will prepare permit application forms and drawings. Seller will coordinate with Owner to obtain required signatures prior to submitting and will deliver the land disturbing permit to Owner upon receipt. This plan shall include:

- (01) Project Description (Topography, Watercourses, Soils, Regulatory Floodplain, etc.)
 - a. Pre-Construction Conditions
 - b. During Construction Conditions
 - c. Post-Construction Conditions

- (02) Applicable Construction Notes
 - a. Construction Methods and Standard Details
 - b. Confirmation of applicable Codes and Standards
- (03) Results
 - a. Pre, During and Post Construction flows, water depths, velocities, etc.
 - b. Sizing details (ditches, swales, culverts, basins, etc.)

Seller shall design the solar PV array in such a manner that all arrays and above ground PV system equipment and electrical equipment are outside of any pooling/ponding of water due to 100-year storm event. If the Seller has no alternatives but to build portions of the array within areas of water pooling/ponding based on a 100-year storm event, the Contract shall specifically request an approval from the Owner to do so. In that scenario, the Seller shall prepare a hydrology study to assess peak flows and flood risk across the project site for a 100 -year storm event. The Civil, Electrical and Structural design takes into account the results of the Hydrology Study and the design specifications. Seller shall implement the findings of the Hydrology Study such that water sensitive equipment and structures will be elevated above or sited outside the areas identified in the Hydrology Study within the 100-yr flood limits. The contract shall implement a design to effectively de-water any areas water pooling/ponding after a 100-year storm event. No areas within the facility shall have water pooling/ponding for longer than 72 hours after a 100-year rain event intensity. Lesser rain intensities shall not result in water ponding/pooling anywhere within the solar PV facility.

4.10.4. Dust Control

Seller shall apply dust control materials to minimize raising dust from construction operations and traffic, including haul routes, using only dust control mixtures approved by the state and/or local jurisdictions.

4.10.5. Fire Prevention and Protection

As part of its Safety Plan, the Seller shall include a fire prevention and response plan.

The Seller shall perform all work in a fire-safe manner.

The Seller shall comply with all state, federal, and local fire prevention regulations.

4.10.6. Construction Access

Seller shall abide by all load limits established by the applicable Department of Transportation (DOT) for the relevant state where the Plant is built.

Seller shall be responsible for providing, operating, and maintaining equipment, services, and personnel with traffic control and protective devices, meeting the requirements of the *Manual of Uniform Traffic Code Devices* as required, to allow traffic flow on haul routes and onsite access roads in a safe manner. Seller shall be responsible for any costs to comply.

Seller is responsible for construction of temporary access around areas of excavation and other construction activity, if necessary and as required. Seller is responsible to obtain state and/or local jurisdiction permits for developing temporary or permanent access from public road rights-of-way.

4.10.7. Site Access Roads

The Site access road, if not currently in place, shall be designed and installed by the Seller. If the Site access road does exist, then it is to be improved by the Seller to a 20-foot gravel road. This design shall be based on sufficient soils and subsurface investigation by a qualified professional to ensure that the constructed road will meet its intended purpose. The design life of the access road shall be 30

years, assuming minimal maintenance without full re-surfacing. The Site access road shall be a gravel road sufficient to satisfy the loading requirements of the equipment vendors and to provide all-weather access for operation and maintenance of the Plant. Site access roadway design shall comply with state and/or local permit requirements.

Temporary construction roads and staging areas not connected to permanent roads (if any) shall be restored by Seller in accordance with permit requirements and post construction stabilization plan.

Seller shall provide a minimum setback of 20 feet between the perimeter fence line and any equipment or as directed by local authorities if more distance is required. This setback space may be used as a perimeter road.

For interior service roads as necessary, Seller shall allow a minimum road width of 16 feet with 20 feet min clear access. Pathways between rows of modules and circuit blocks may be narrower but designed with consideration of procedures required for accessing all modules and array equipment for maintenance and repairs. Interior roads (as needed) shall be 16 feet wide. Pathways between rows of modules and circuit blocks may be less. Road surfacing shall meet local fire and emergency vehicle access requirements

Seller shall follow the Geotechnical Engineer's recommendations for subgrade preparation, prior to construction of the access roads, as well as for any aggregate base material selection, placement, and compaction.

Drainage patterns shall not be interrupted due to the placement of the roadway or water conveyance shall be provided on the side the roads. Where needed properly sized culverts or low water crossing shall be provided. It is the Seller's responsibility to ensure that all road designs adhere to the approved storm water runoff plans. Where road wash-out is a concern, hydrological effects shall be considered in the road design – max overtopping depth at low road locations, velocity at max depth, estimated shear stress vs permissible.

Roads shall have a minimum 30-foot inside radius, unless otherwise instructed by state or local requirements. A smaller turning radius may be approved with written approval from the Owner.

Earthwork

4.10.8. General

Earthwork includes, but is not limited to, the following:

- (01) Trench excavation (including rock excavation) and backfill for underground utilities
- (02) Excavation and backfill (including rock excavation) for foundations
- (03) Installation of granular fill and surfacing around concrete structures, drainage facilities, towers, and related Site structures, and within roadways
- (04) Finish grading around all concrete pads (e.g., an inverter pad) shall have a safe approach slope leading to the top of the pad or to a small step up not to exceed 8 inches in height

Seller shall make its own estimate of the types and extent of the various materials to be encountered or required to accomplish the Work.

Seller shall utilize sustainable practices where practical, such as recycling shipping containers, pallets, etc. All materials that are not practically recyclable shall be disposed of in an approved landfill. Seller shall clean up any spill or contamination that may occur on Site in accordance with approved standard procedures.

4.10.9. Excavation

Seller shall be responsible for making all excavations in a safe manner and consistent with the requirements of the Occupational Safety and Health Administration (OSHA).

Seller shall provide adequate measures to retain excavation side slopes to ensure that structures, equipment, and persons working in or near the excavation are protected.

Seller shall protect all above grade and below grade utilities.

4.10.10. Construction Signage

Seller shall provide temporary signage for local traffic control in accordance with state DOT or local county requirements and in accordance with the Agreement.

4.10.11. Fencing

Seller shall utilize temporary fencing whenever an existing fence is removed and as necessary to maintain security and prevent the movement of livestock and other natural wildlife. Seller shall provide a minimum setback of 20 feet between the perimeter fence line and the solar panels and project substation. Additional setback may be required by other standards. Fencing shall meet PacifiCorp design standards of **Appendix A-7.10**.

4.10.12. Site Finish Grade

Seller shall leave the Site in a clean condition upon completion of the work. Efforts shall be made to restore area to a clean condition as soon as practical. Seller shall remove all trash, debris, and stockpiles. The Site access roads shall be returned to a condition that meets the original specification by repairing road damage such as ruts, gouges, and weather damage that may have occurred during construction.

The Site finish grade within the equipment footprint and in areas required for operation and maintenance of the Plant shall be fully stabilized in a manner that meets or exceeds local county requirements.

Provisions of the SWPPP for final storm water drainage shall be implemented.

Seller shall seed and mulch all areas of the Plant Site that have been disturbed beyond the permanent portion of the Site and access road, per the SWPPP. Seller shall follow the post construction stabilization plan for restoration guidance. It is preferred that the Seller use low water, low maintenance plans for re-seeding. Plant Design and State Requirements

Any technical requirements under any applicable state incentive program shall be met by the Seller. For example, any technical requirements under the state energy office incentive structure shall be met by the Seller for the state where the Plant is built.

4.11. Electrical Engineering

Seller shall provide all electrical engineering design services, meeting applicable codes and standards and the requirements of Pac Trans.

The engineering and design shall include the appropriate sizing and cabling (above and below ground) that will connect all applicable equipment to the point of interconnection. The Plant electrical system shall be designed for electrical system losses on the DC wiring system to be no more than 2 percent average within an inverter block and losses on the AC wiring system no more than 2 percent within a single distribution circuit. All DC disconnects at the inverter (s) and combiner boxes shall include a visible gap when in the open position or integral voltage and current detection such that no special PPE is required to ensure the circuit is deenergized.

The overall sequence of power flow for the photovoltaic plant shall be DC power generated by individual modules arranged in strings and the strings wired to a central point among them to be combined into larger groups of strings. These combiners are connected to the inverter DC bus input. The inverter outputs AC power at low voltage, is stepped up immediately, and is fed into the medium voltage collector system. The collector system is comprised of several AC circuit limited in size by the max ampacity of a 1250 kcmil per phase conductor between the substation and the first inverter in the circuit. The total size of the project will be optimally distributed across the required circuits and fed into the transmission system at the project substation through the point of interconnect.

All protection equipment used throughout the system shall be sized, specified, and coordinated to reduce damage to surrounding components in the event of a fault.

The above ground portion of the electrical systems shall be neatly routed to facilitate access, troubleshooting, maintenance, etc.

Trench depth for electrical wires shall be as follows:

- (01) Bottom of trench ~ 3.5 feet typical for DC trench
- (02) Bottom of trench ~ 4 feet below finish grade for AC trench (28 kV)
- (03) Bottom of trench ~ 5 feet below finish grade if both DC and AC (28 kV) in same space

The electrical design shall include the design of equipment grounding and lightning and surge protection for the entire Plant Site. Seller shall provide a comprehensive surge protection system and provide a lightning risk assessment. The results of the lightning risk assessment and consultation with Owner will be the basis for determining the extent of the lightning protection system (LPS) that is required.

An arc flash study shall be performed per **Appendix A-7.13**. Incident energy values based on the protection coordination shall be used for arc flash labeling and as the basis for the PacifiCorp arc flash safety procedures.

Seller shall design and specify all communications hardware and software required for system protection and remote monitoring and control. All monitoring and communication supplemental equipment and cabling shall be designed and specified by Seller, subject to Owner review.

The power delivered to the grid must at all times meet the interconnect requirements for power factor. A one-line drawing is required illustrating the power factor control strategy.

4.11.1. Communication System

Seller shall procure and install a SCADA system as required in the Interconnection Agreement.

Seller shall install communications systems as required by the Interconnection Agreement.

Seller shall install communications systems as required in Security.

Seller shall supply all equipment necessary to connect to Transmission Provider's fiberoptic cable for each of the communications described in this section.

4.11.2. Communications System Testing and Warranty

Seller shall test the installed communication system to demonstrate its ability to meet the requirements of its intended use. Testing shall be performed when the final system interconnections have been made.

4.11.3. Security

Seller shall provide a security system for the Plant. The security system around the perimeter shall include a 7-foot-high chain link fence with 1-foot top guard (total 8-foot high) of three strands of nine-gage barbed wire. The perimeter fence shall include three locked gates: two with a width of 20 feet for vehicles and one pedestrian entrance with a width of 4 feet. Fencing shall meet guidelines in section A-3.6.4 Fencing. Seller shall utilize temporary fencing whenever an existing fence is removed and as necessary to maintain security and prevent the movement of livestock and local wildlife.

Perimeter signage shall be provided by Owner and installed by Seller in accordance with Owner standards. Signage shall be installed every 65 feet along the perimeter fence and on all gates. Signage shall be installed five feet above ground level.

Signage that will be provided by the Owner will include the following:

Warning! Hazardous Voltage Inside Keep Out

English SI# 7999852

Spanish SI# 7999854

No Trespassing

SI# 8252306

Mounting Hardware

SI# 7999092

The Seller shall be responsible for security during construction.

Seller shall contract with AVTEC SYSTEMS INTEGRATOR, A DIVISION OF CACHE VALLEY ELECTRIC, (Security Sub-Seller), to provide and install the necessary security equipment. Contact:

Avtec – System Integrator
Michael Petric
(801) 908-4191
michael.petric@cve.com

This equipment may include, but is not limited to:

- (01) LED Spot or LED flood lights.
- (02) Security cameras located such that they are capable of adequate identification of intruders covering the perimeter of the Site. Cameras shall be placed at a height that permits line-of-sight access to the property and minimizes shading onto the PV array.
- (03) Cameras with a control and detection system that assists in the detection and identification of intruders.
- (04) Network - Digital Video Recorders used to record video that could be used for evidence in the event of theft or vandalism.

- (05) Seller shall negotiate with the Security Sub-Seller to identify the scope of work that will be performed by the Security Sub-Seller, to ensure that a complete and operational security system as described by the Security Sub-Seller is provided. The Security Sub-Seller shall provide to the Seller the security system design, which will indicate the location of cameras, DVRs, security lighting and any security communications equipment, based on the Seller's overall System design. The work that may be provided by the Security Sub-Seller may include the furnishing and installation of wiring, cabling, labor, tools, equipment, and ancillary materials required for a complete and operational security system. At minimum, it is expected the Security Sub-Seller will provide the following equipment: cameras, network DVRs, and any specialized security communications equipment.
- (06) Seller shall be responsible for the furnishing and installation of all necessary conduit, 120 Volt alternating current (V_{ac}) power extensions for all Security related equipment. Seller to allocate a minimum /of (3) three each – 1” conduits from each Inverter Pad.
- (07) Seller shall provide a free-standing weather proof enclosure with adequate space required for Security Control Equipment as specified by the Security Sub-Seller. Seller may also install the solar facility SCADA equipment, in accordance with Section A-4.12, within the same enclosure.
- (08) Installation of telephone lines, and/or cellular modem(s), and/or local area network for the interconnectivity of all related Security System Equipment.
- (09) Seller shall provide fiber optic cable for Security System Communications. Fiber optic cable shall consist of a minimum of (4) four fiber strands between each inverter pad. Security fiber strands provided can be included in the fiber optic cabling that is provided as part of the SCADA Communications System.
- (10) The system shall be complete, tested, and fully operational. Prior to construction, Seller shall provide the following:
 - (11) Descriptive statement and single-line block diagram to show how all related equipment will interface and operate as a complete system.
 - (12) Product data: manufacturer's technical data sheets on each product to be used.
 - (13) Drawings, including plans, elevations, equipment mounting heights, and dimensions required to show devices' locations and demonstrate accessibility compliance in accordance with referenced documents.
 - (14) Detailed schematic wiring diagrams for all system devices; wiring information shall include cable type, conductor routings, quantities, and connection details at devices.
 - (15) Manufacturer's user's manuals for operations, administration, installation, and maintenance.

Security System Installation

All system components and appurtenances shall be installed in accordance with the manufacturer's specifications, referenced practices, guidelines, and applicable codes. All necessary interconnections, services, and adjustments shall be furnished as required for a complete and operable system as specified. Control signal, communications, and data transmission line grounding shall be installed as necessary to preclude ground loops, noise, and surges from adversely affecting system operation.

All security system wiring shall be installed in dedicated conduit throughout. Cable shall not be pulled into conduits or placed in raceways, compartments, outlet boxes, junction boxes, or similar

fittings with other wiring. All low-voltage wiring outside the control console, cabinets, boxes, and similar enclosures shall be plenum rated where required by code.

All wiring conductors connected to terminal strips shall be individually numbered and each cable or wiring group being extended from a panel or cabinet to a building-mounted device shall be identified with the name and number of the device as identified and shown on the drawings.

4.11.4. Cybersecurity Requirements

General Security Criteria

1. Please confirm you have and maintain security controls to protect the Company's networks, systems, software, Confidential Information, and Data no less rigorous than those set forth in the latest published version of ISO/IEC 27001 – Information Security Management Systems– Requirements and ISO/IEC 27002 – Code of Practice for International Security Management.
2. If providing a web portal or web service, please confirm that web services use HTTPS/TLS version 1.2 or later for all content.
3. Please confirm you encrypt all Company data while at rest as well as when in transit over the network.
4. Please confirm that all Company-related file transfers are encrypted while at rest as well as when in transit over the network.
5. For responses above, please confirm all encryption uses NIST-approved algorithms and key lengths.
6. Please confirm you support federated single-sign-on (SSO) authentication for any Company accounts, whether via web interface or mobile application. You must have the ability to support Azure Active Directory.
7. If you do not support federated single-sign-on (SSO) authentication, please confirm that Accounts provided by you support multi-factor authentication compliant with NIST SP 800 63-3 Authentication Assurance Level 2. Provide documentation that supports compliance and describe supported authentication mechanisms.
8. Please confirm, by provision of supporting documentation, that email sent while under the Contract to the Company by you or by any service: Originates from a domain(s) with a published Domain-based Message Authentication, Reporting and Conformance (DMARC) policy of “reject” and with a published Sender Policy Framework (SPF) policy consisting of valid senders and a “fail” directive (-all). If the optional DMARC “pct” directive is used, “pct” must be set to “100”.

9. Please confirm, by provision of supporting documentation, that email sent while under the Contract to the Company by you or by any service passes a Domain-based Message Authentication, Reporting and Conformance (DMARC) authentication check.
10. Please confirm, by provision of supporting documentation, that email sent while under the Contract to the Company by you or by any service is signed by a DomainKeys Identified Mail (DKIM) 2048 bit key.
11. Please confirm, by provision of supporting documentation, that email sent while under the Contract to the Company by you or by any service supports Transport Layer Security (TLS).
12. Please describe your process to disclose known vulnerabilities to the Company related to products or services provided as they pertain to the proposed service.
13. Please describe methods supplied to the Company to verify software integrity and authenticity for any software or patches provided by you as they pertain to the proposed service.
14. Please describe your process for security event monitoring and notification/alert/response plans, including response to security incidents affecting the Company.
15. Please confirm you will notify the Company of a security incident as soon as practicable, but no later than 48 hours after discovery.
16. Please confirm you will coordinate responses to security incidents with the Company that pose a security risk to the Company.
17. Please confirm that all rights to any data provided by the Company shall remain exclusive property of the Company.
18. Please confirm you will not share data with third parties for unrelated commercial purposes, such as advertising or advertising-related purposes.
19. If remote access of any type will be required as part of the service, please fully describe your requirements for remote access.
20. If remote access of any type will be required as part of the service, confirm your ability to conform to Company requirements for intermediate host methods for remote access, such as Citrix or Virtual Desktop,

21. If remote access of any type will be required as part of the service, and if a virtual private network is required, please confirm your ability to terminate in a demilitarized zone network (DMZ). Note that direct virtual private network connectivity to Company corporate networks is always prohibited.
22. If remote access of any type will be required as part of the service, confirm that you will notify the Company when remote or on-site access is no longer needed by your representatives, where applicable.
23. Please list facilities proposed in bid located outside the continental United States.
24. Please list any support staff used during the term of this contract located outside the continental United States.
25. Please confirm you will disclose third parties upon which you depend to deliver the Company offering (such as third-party software, implementation, hosting, for example).
26. Please describe your methods to securely ship and deliver products to the Company as they pertain to the proposed service.

For Hosted or Cloud Services:

27. If your service is comprised in whole or in part of a cloud-based or hosted services solution, please confirm you currently undergo, or are willing to undergo, annual Statement on Standards for Attestation Engagements (SSAE) Service Organization Control (SOC) 2 Type 2 audits (“Audit”) for your enterprise or covering the scope of services for the term of the contract with the Company, as appropriate. Note that a datacenter audit alone will not be sufficient. You may include an audit for datacenter/colocation provider for informational purposes.
28. If your service is comprised in whole or in part of a cloud-based or hosted services solution, please confirm that your administrative access complies with NIST SP 800 63-3 Digital Identity at Authentication Assurance Level 2 or higher, where compromise of one factor does not contribute to compromise of the other factor. Provide compliance documentation and describe supported authentication mechanisms.

5.0 EQUIPMENT

5.1 Equipment Supply

As described in detail throughout this document, Seller shall purchase and furnish to the Site all material required to complete the Plant, including the following material:

- (01) Miscellaneous steel
- (02) Support steel posts
- (03) Components (nuts, bolts, clamps, etc.)
- (04) PV modules
- (05) Fixed tilt racking or single axis tracker equipment (as applicable) and components
- (06) DC cabling and combiner boxes
- (07) DC junction boxes
- (08) AC cabling
- (09) Power centers, including inverters
- (10) Electrical switchgear
- (11) Transformers
- (12) Meteorological station
- (13) Snow Monitoring System
- (14) Remotely accessible data acquisition system
- (15) All materials related to drainage required by the civil engineering plan
- (16) All electrical conduit and junction boxes
- (17) Concrete equipment pads
- (18) Fencing, gates, lighting, security cameras, and security camera recording equipment
- (19) Communications structure (if required)

Each item of equipment to be supplied by Seller shall be subject to inspection and testing during and upon completion of its fabrication and installation as per PacifiCorp Facility Connection (Interconnection) Requirements for Distribution Systems (34.5 kilovolts and below).

Seller shall provide the manufacturer's flash test data for all modules to Owner upon procurement of modules.

Prior to the arrival of equipment and materials at the Site, the Seller shall install a fenced, secured area and provide security for the storage of such equipment and materials. Seller shall notify Owner of the location and layout of intended staging areas, parking areas, storage areas, office areas, workshops, and other temporary facilities. Temporary construction roads and staging areas not converted to permanent roads (if any) shall be restored in accordance with all permit requirements.

Seller shall be responsible for receiving and storing all freight at the Site in a secure manner.

Installed equipment and materials shall be new, of good quality and suitable grade for the intended purpose, and not a lower grade or quality than specified in the design and engineering plans or in manufacturers' recommendations. Where applicable, utility-grade equipment shall be used. Commercial- or residential-grade equipment shall not be acceptable. No equipment shall utilize polychlorinated biphenyls (PCBs).

If Seller proposes to use equipment that is non-utility grade, it is the responsibility of Seller to identify the equipment and report it to Owner for approval. It is the responsibility of Seller to identify any equipment using SF₆ gas. It is the responsibility of Seller to identify any proposed batteries and provide quantities and associated data sheets. It is the responsibility of Seller to provide data sheets and quantities on any proposed chemicals used on the Plant. Seller shall provide a list of all major equipment to be purchased, constructed, and installed as part of the Plant. The list shall identify both the items and quantities.

5.2. Signage and Labeling

Permanent naming placards should be placed on all equipment, including inverters, combiner boxes, transformers, and others according to the NEC and Owner specifications. Naming on placards and/or

tags shall match drawing naming convention. Security signage shall be in accordance with A-3.9 Security. All signage must meet current industry standards. Placards and signs shall have a life span of 20 years.

All cables shall be labelled to meet applicable codes and standards. All cables shall have a label affixed to the outer jacket with a Brady or equivalent cable marker at each termination of a type accepted by Owner before installation. Labelling will match the point to point drawings. A method for ensuring labeling is complete must be included in the Seller's QC Inspection Point Program.

5.3. Grounding and Bonding

Seller shall provide detailed information (such as ground-grid drawings and calculations) for all proposed Plant grounding. Seller is responsible for designing and providing the Plant system grounding and equipment grounding. The Plant grounding design shall be done in accordance with Institute of Electrical and Electronics Engineers (IEEE) standards for generating stations. Substation grounding shall be done in accordance with IEEE standards for substation grounding. All grounding designs shall be reviewed by Owner prior to Seller commencing work.

All ground conductors shall be stranded copper and may be bare if exposed. Ground conductors in conduits shall be green-insulated. Ground lugs shall be mechanical and rated aluminum to copper. All below grade connections shall be exothermic welds. Step-up transformers and inverters and the Plant switchgear shall be bonded to the ground ring at opposing corners of the equipment. Mounting structures shall be grounded in a manner that is sized for maximum available short-circuit current and lightning current (if required).

Seller shall submit to Owner grounding and lightning calculations for assurance of safe step and touch potentials on the Site, in accordance with Owner's standards. Seller shall conduct a ground resistivity test, as prescribed by Owner prior to testing, with opportunity for witness as provided in the Agreement, to verify that the grounding system meets minimum requirements for the overall grounding scheme. Interior fencing (including without limitation internal fences around interconnection equipment and inverters) shall be installed and grounded and substation grounding shall be done in accordance with PacifiCorp Engineering Handbook Parts 6B.5 and 6B.6. Fencing around the perimeter of the overall Plant Site shall not need to meet the aforementioned Handbook standards but shall be grounded in accordance with local codes. Perimeter fences shall not be shared with the substation fence and shall be at least 30 feet from the fence around the interconnection equipment. A ground grid meeting the requirements of IEEE 80 shall be installed in the area of the interconnection equipment.

5.4. Bird and Animal Protection

Bird and animal protection at the Project Substation shall be provided following Owners Standards referenced in Appendix "A-7".

5.5. Surge and Lightning Protection

Seller shall provide a lightning risk assessment performed to industry standards by a certified lightning protection professional, as outlined in section A-4.4.2 External Lightning Protection System (LPS). The results of this assessment, in consultation with Owner, shall be the basis for determining the requirements and extent of the facility LPS and a surge protection system that provides protection of the PV panels, DC power circuit, inverters, measurement control and communications systems, and other major electrical equipment.

5.6. Surge Protection

A staged, comprehensive surge protection system, inclusive of Type 1, 2, and 3 surge protective devices (SPDs), shall be incorporated as determined by the lightning risk assessment (A-3.7.1 Electrical Engineering) or as required by the photovoltaic and inverter manufacturers in all relevant pieces of electrical equipment. Protection shall be provided within the inverter on both the DC and AC sides as required by inverter manufacturer. Additionally, surge protection shall be provided in combiner boxes, trackers, and measurement control and communication systems as determined by the lightning risk assessment study. Type 3 surge protection installed within that equipment shall be mounted on DIN rails and must have finger safe replaceable modules that can be exchanged without the use of tools. SPDs shall be applied on all power circuits (AC and DC) and all communications and control circuits in a coordinated, staged manner. The operating status of the power SPDs shall include visual indication and shall be able to be remotely monitored by a set of integral contacts.

In addition to the performance requirements indicated above, all SPDs shall be compliant to the respective domestic or international standards, including, but not limited to, the following standards and guidelines:

Underwriters Laboratories, Inc. (UL) Standard 1449 3rd edition.

IEEE Guideline C62.41.1-2002

IEEE Guideline C62.41.2-2002

IEEE Standard C62.42.0 -2016

IEEE Standard C62.45-2002

IEEE Standard 1100-2005

5.7. SPDs for PV DC Power Circuits

SPDs applied on PV DC power circuits shall meet all the requirements listed above in this general section and shall be specifically designed for and labeled to UL 1449 3rd edition and UL's Certification Requirement Decision for PV DC application. DC PV SPDs shall be rated for a short-circuit withstand capacity (I_{SCWPV}) of not less than 1,000 amperes (A). The SPDs must be specifically designed to be able to disconnect themselves from an energized DC circuit by means of an internal integral fused circuit and do so without damage caused by faulting arcs. SPDs must be selected for the voltage system that they are to be applied (such as 600; 1,000; 1,200; or 1,500 V_{DC}). SPDs shall be from an equipment manufacturer regarded as a Tier 1 Supplier. Surge Suppression, Inc. of Destin, Florida is the preferred manufacturer of any required SPDs.

5.8. SPDs Applied on AC Power Circuits

SPDs applied on AC systems must meet all the requirements listed above in this general section and must be specifically designed for and compliant to UL 1449 3rd edition. SPDs must be selected for the system voltage where they are to be applied. SPDs are to have a short-circuit current rating (SCCR) higher than the short circuit availability where they are installed, therefore not requiring external fusing. SCCR of 200,000 A is ideal. SPDs shall be from an equipment manufacturer regarded as a Tier 1 Supplier. Surge Suppression, Inc. of Destin, Florida is the preferred manufacturer of any required SPDs.

5.9. SPDs for Measurement, Control, Instrumentation and Communications Circuits

All critical non-power circuits are to be protected with appropriate DIN rail-mounted pluggable surge protection for the system they are applied. Surge protection bases are to permit signal continuity even if the SPD module is removed from the base. SPDs shall be from an equipment manufacturer regarded as a Tier 1 Supplier. Surge Suppression, Inc. of Destin, Florida is the preferred manufacturer of any required SPDs.

5.10. External Lightning Protection System (LPS)

Based on the findings of the lightning risk assessment and/or the discretion of the Owner, an external LPS may be required to be installed. If so, Seller shall provide an LPS to protect the overall plant from direct lightning strikes to any portion of it, including, but not limited to, solar panels, inverters, outside cabinets, and buildings housing electrical equipment. The LPS shall consist of air terminals of proper height and spacing (using the rolling sphere method), properly rated and properly designed and placed down-conductors to assure safety of personnel during discharges, and a properly designed and installed ground system.

The systems shall be designed in accordance with the latest globally recognized standards for such designs, which are either International Electrotechnical Commission (IEC) 62305-1 and IEC 62305-3, or NFPA 780.

Grounding systems shall be in compliance with IEEE Standard 142-1982, IEEE Recommended Practice for Grounding of Industrial and Commercial Power Systems.

Designs are to be provided by a recognized expert LPS design firm, supplier, or professional engineering firm, and are to be submitted to the Owner.

All components of the LPS shall be in compliance with the selected system design standard chosen.

Careful consideration must be given to the design and placement of all air terminals to have no shadowing effect on PV panels.

5.11. Photovoltaic Modules

The PV modules shall:

- (01) Meet IEC 61215 (crystalline silicon PV modules) or IEC 61646 (thin film PV modules).
- (02) Meet IEC 61730: Photovoltaic Module Safety Qualification.
- (03) Meet IEC 61701: Salt Mist Corrosion Testing of Photovoltaic Modules; Severity 6.
- (04) Be listed to UL standard 1703 for the voltage specified.
- (05) Include all known and future duties, tariffs, export tariffs, customs, demurrage, and shipping costs.
- (06) Be from an equipment manufacturer regarded as a Tier 1 Supplier.
- (07) Module supplier should provide a bankability report from an independent engineer.
- (08) Manufacturer should provide an established track record of installed systems throughout the United States.
- (09) Demonstrate workmanship quality through a third-party factory audit or testing score such as VDE Quality Tested certificate, or Solar buyer's Independent Quality Assessment overall rating of "Good" or better with zero critical findings.
- (10) Demonstrate a 25-year rated lifetime via long-term outdoor testing and/or accelerated lifetime laboratory testing. Testing such as Thresher testing, DNV-GL's "PV Module Reliability Scorecard," Atlas 25+ PV Module Durability Testing (Desert Climate Classification preferred), or Technischer Überwachungsverein (TÜV) long-term sequential testing of the specific model of the PV module selected is an acceptable demonstration of a 25-year module expected life.

- (11) Demonstrate that damp heat testing is performed at proposed design voltage (e.g., 1,500 V_{DC}).
- (12) Demonstrate proposed module is Potential Induced Degradation (PID) free.
- (13) Be only factory “firsts” meeting all QA/QC requirements. No “seconds,” or modules not meeting all quality control requirements shall be allowed.
- (14) Demonstrate manufacturing quality by electroluminescence (EL) testing of every module for defects.
- (15) Preferred PV module vendors¹ are:
- ~~a) Canadian Solar~~
 - ~~b) First Solar~~
 - ~~c) Hanwha Q CELLS~~
 - ~~d) JA Solar~~
 - ~~e) Jinko Solar~~
 - ~~f) Kyocera~~
 - ~~g) LG~~
 - ~~h) LONGi Solar~~
 - ~~i) Mission Solar~~
 - ~~j) Panasonic~~
 - ~~k) Phono Solar~~
 - ~~l) REC Solar~~
 - ~~m) Renesola~~
 - ~~n) Sanyo~~
 - ~~o) Solar Frontier~~
 - ~~p) SolarOne~~
 - ~~q) SolarWorld~~
 - ~~r) SunPower~~
 - ~~s) Trina~~

¹ BTA and Benchmark supply contracts shall be subject to prohibited vendor and supplier audit provisions. For more information, see Section 3.2.18 (Prohibited Vendors), and Section 3.2.19 (Supply Chain Audit) of the pro forma contracts in Appendix E-2.1:
https://www.pacificorp.com/content/dam/pcorp/documents/en/pacificorp/suppliers/rfps/pacificorps-2022-all-source-request-for-proposals/appendix-e-g/PacifiCorp_2022AS_RFP_App_E-2.1_PPA_Document%E2%80%93Generating_Resource_Only.pdf

Demonstrate batch consistency by documenting that the batch of modules proposed for this project meets performance requirements. A minimum of five modules shall be tested to ensure performance and reliability under accelerated lifetime tests. Documentation shall include flash test results and EL images before and after the tests shown in Figure 1. Costs of the modules, shipping, testing, and




Figure 1: Module Manufacturing and Batch Quality Assurance

summary report are the responsibility of the Seller. The documentation of the batch, module sampling, EL imaging, flash testing, and summary report shall be provided to the Owner.

Note that the Owner, at its sole discretion, may randomly select up to 20 PV modules shipped to the Plant for delivery to a third party for quality verification testing. The costs of such verification testing will be the responsibility of Owner. Owner reserves the right to refuse the Bidder's proposed module if the independent tests indicate performance, workmanship, batch quality, or reliability issues.

PV module manufacturer shall:

- (01) Be ISO 9001 certified (alternatively, ISO 62941)
- (02) Be ISO 14001 certified
- (03) Have a minimum of 5 years' experience manufacturing PV modules

5.12. Padmount Transformers

Transformers shall meet transformer efficiency standards set forth in the most recent version of the U.S. Department of Energy "Energy Conservation Program for Commercial Equipment: Distribution Transformers Energy Conservation Standards; Final Rule." Transformers shall be rated for inverter source operation and the environment in which they will operate. The transformer shall be supplied with a no-load tap changer with 5 high-voltage taps capable of operating at +5, +2.5, -2.5, and -5 percent above and below nominal collector system voltage at full rating. The transformer shall be supplied with a fused disconnect switch on the transformer high-voltage side to isolate the transformer in case of an internal fault. The switch/transformer configuration shall be designed for loop feed. Transformers shall be either dry-type, biodegradable fluid, or less-flammable oil insulating

fluid. Enclosure finish shall be a top powder coat that is designed for a 25-year service life. Seller shall provide and install pad mount transformers as provided in the Agreement. Owner shall reserve the right to attend factory witness testing of padmount transformers.

Seller that interconnects to the PacifiCorp system shall provide equipment and perform the work in compliance with the requirements of the **RFP Appendix A-2 - Interconnection Agreement, RFP Appendix A-7.04**, and other applicable standards and specifications listed in **Appendix A-7 – Owner Standards and Specifications**.

5.13. Inverters

The inverter units shall be utilized for inverting the DC input from the Plant to AC output. Seller may use large-scale, central inverter or string inverter design strategies. However, either design shall be capable of operating under all required federal, state, and local standards and codes, and be capable of providing all the required grid support.

Inverters shall be calibrated and set so that the AC output, after inverter clipping and losses between the inverter to the meter, shall not exceed the Plant AC capacity at the meter. Seller shall supply and install inverters, transformer pads, and wiring/cabling to this equipment in accordance with National Electrical Code (NEC) and any other applicable standards. Seller will tie into the existing medium-voltage distribution system, connecting the system to the new generation facilities via medium-voltage transformers.

Inverters selected for this project shall:

- (01) Be UL listed to 1741 (Standard for Inverters, Converters, Controllers and Interconnection System Equipment for Use with Distributed Energy Resources).
- (02) Comply with IEEE 1547-2018, including testing to IEEE 1547.1 and IEEE C62.45. Regulatory standards compliance shall also include IEEE C62.41.2 and CSA107.1-01.1. Inverters shall have voltage and frequency ride-through functionalities, as well as be capable of actively regulating voltage levels by providing adjustable active and reactive power. The inverters/plant controllers shall have the capability of reducing their active power during certain pre-determined conditions, as specified in the Interconnection Agreement. The inverter shall have the capability to meet the following:

Ride-through region for voltage and voltage trip settings

Voltage at Point of Common Coupling (% Nominal Voltage)	Ride-Through Until (s)	Operating Mode	Maximum Trip Time (s)
>120			0.16
110- 120	12	Momentary Cessation	13
88 - 110	Continuous Operation	Continuous Operation	Continuous Operation
70 - 88	20	Mandatory Operation	21
50 - 70	10	Mandatory Operation	11

0 -50	1	Momentary Cessation	1.5
-------	---	---------------------	-----

Default Interconnection System Response to Abnormal Frequencies

System Frequency Default Settings	Range of Adjustability (Hz)	Default Clearing Time (s)	Range of Adjustability (s)	Ride Through until (s)	Ride Through Operational Mode
f > 62	62 - 64	0.16	0 - 300	No Ride through	Not Applicable
60.5 - 62	60 - 62	300	0 - 300	299	Mandatory Operation
58.5 - 60.5	indefinite				
57.0 - 58.5	57 - 60	300	0 - 600	299	Mandatory Operation
< 57.0	53 - 57	0.16	0 - 5	No Ride through	Not Applicable

Notwithstanding the above, the inverter and associated system shall meet all requirements specified in the Interconnection Agreement. Seller shall notify Owner at least two weeks prior to factory acceptance tests that will be performed to demonstrate these capabilities. Owner, or its representative, shall have the opportunity to witness factory acceptance tests.

The inverter and associated equipment shall meet all standards for operating on the transmission or distribution systems including all aspects of dynamic grid support noted in A-4.7 b. above and the additional requirement for providing Primary Frequency Response as dictated by FERC and included in the PacifiCorp interconnection standards for Small and Large Generators.

Inverter shall be capable of providing voltage droop control.

- (01) Carry a minimum 5-year standard warranty with options for at least a 20-year extended warranty.
- (02) Be designed for a 30-year lifetime, assuming regular maintenance (including replacement of inverter components).
- (03) Have a maximum harmonic distortion less than 3 percent of total harmonic distortion at rated power output.
- (04) Have an efficiency greater than 98 percent not including medium-voltage padmount transformer according to the California Energy Commission (CEC) test procedures for peak efficiency.
- (05) Be capable of rated output at 50° C or higher.
- (06) Incorporate a no-load, two-pole, lockable disconnect switch or fusible disconnect for main DC power disconnect for maintenance personnel safety with visible gap between contactors when in the open condition. DC load break switches should be installed at the combiner boxes and at the inverters (located as close to the array as possible). Be equipped with lightning protection.

Skid-mounted package units containing all equipment including DC switches, master fuse boxes, inverters, step-up transformers, and other power conditioning system equipment are preferred. Skid-mounted package units with integrated steps, side rails, and other safety features are preferred. The inverter manufacturer must approve all structures that contain inverters, especially as it relates to ventilation and temperature.

Inverters located outdoors shall be enclosed in lockable enclosures with a minimum rating of National Electrical Manufacturers Association (NEMA) 3R and with coatings in accordance with section A-3.3.5 Corrosion Protection. Any sensitive electronic equipment associated with, or part of, the inverter shall be installed in a NEMA 4 rated enclosure.

To the extent practicable, inverters should be mounted/oriented in such a way to avoid the effects of the sun (for example, facing the LCD display north to reduce sun exposure). If an LCD screen will be exposed to direct sunlight, a shade canopy shall be installed to provide shading for the screen.

Enclosure must have a door interlock system to prohibit the door(s) from being opened while energized.

Inverter output shall be protected by a circuit breaker with short- and long-time adjustable over-current protection. This circuit breaker shall be externally operated, or the vendor shall furnish an external on/off (start/stop) switch.

Inverters shall employ a maximum power point tracking scheme to optimize inverter efficiency over the entire range of PV panel output for the given Site design conditions.

Inverters shall be equipped with all hardware for data collection and communication to the central SCADA server.

Inverter shall be equipped for direct external communication and control to Owner. If communications to Transmission Provider's SCADA system is required by the Interconnection Agreement, then inverter communications and all available inverter controls shall be provided to the Transmission Provider over Transmission Provider's telecommunication network (see **RFP Appendix A-2**).

Inverter shall include a fused, and disconnectable control power transformer (CPT).

Plant design for inverters rated to 1,500 or 1,000 V_{DC} shall comply with NEC Articles 690 and 490, and all other requirements applicable to installations rated over 600 volts (V).

Buildings, storage facilities, and enclosures shall be provided to the extent that protection is needed; the environment needs to be maintained for the long-term reliability, availability, and operation of the equipment; or that it is required by law or the Interconnection Agreement.

Inverter manufacturer shall:

- (01) Be certified to ISO 9001 and ISO 14001 standards.
- (02) Be regarded as a Tier 1 Supplier.
- (03) Shall have supplied a minimum of 100 MW capacity in utility-scale projects located in North America.

Preferred inverter vendors² include the following firms:

² [BTA and Benchmark supplier contracts shall be subject to prohibited vendor and supplier audit provisions. For more information, see Section 3.2.18 \(Prohibited Vendors\), and Section 3.2.19 \(Supply Chain Audit\) of the pro forma contracts in Appendix E-2.1](#)

- a) Huawei
- b) Sungrow

- e)a) SMA
- e)b) TMEIC
- e)c) ABB
- e)d) Power Electronics
- e)e) SolarEdge
- e)f) Yaskawa-Solectria Solar
- e)g) Ingeteam
- e)h) Kaco New Energy
- e)i) Enphase

5.14. Medium Voltage Cable and Equipment

MEDIUM VOLTAGE AC WIRING

- (01) Governing Standards
 - a) NEC
 - b) UL 1072
 - c) ANSI/ICEA S-94-649
 - d) AEIC CS-8
 - e) RUS-1
 - f) One or more of the following ASTM specifications: B3, B8, B230, B231, B609
- (02) Wiring Material
 - a) Medium voltage AC conductors shall be, single-phase, EPR or TRXLPE insulated cables, 100% or 133% insulation voltage rating as per design requirements, MV -90 rated, and shall have a concentric neutral.
 - b) Conductors may be made of either aluminum or copper.
 - c) Insulation rating shall meet or exceed the highest expected continuous circuit voltage. The outer jacket may be PVC or XLPE, however shall bare the UL marking and list of conductor size and ratings.
 - d) iv. In general, bare copper concentric neutral under jacket shall be 100% (full) for cable smaller than 500 KCMIL, 1/3 for 500 KCMIL, and 1/6 for 750 KCMIL and larger, unless short circuit calculations indicate larger neutral is required. Engineer shall coordinate with Owner on protection tripping maximum clearing time to use in the calculation. For any neutral size less than 1/6 the Owner must approve. v. Note: 133% insulation shall be required for delta connected circuits, if the circuit is not effectively grounded at the point of interconnection or substation breaker. vi. MV cables shall be of the UL type specified and have been designed, manufactured, and/or tested according to the following standards: UL 1072, ICEA S-94-649 (NEMA WC 74).

5.15. Overcurrent Protection Devices

DC AND LOW VOLTAGE AC OVERCURRENT PROTECTION DEVICES

- (01) Governing Standards
 - a) NEC Article 240

- b) UL 248-1
 - c) UL 1066
 - d) UL 489
 - e) IEEE Std C37, all applicable sections
- (02) Application
- a) Seller shall provide overcurrent protection devices for all conductors, busses and electrical equipment that may be damaged due excessive current on the circuit.
 - b) Seller shall provide overcurrent protection devices for all other equipment that may be damaged due to a fault or overcurrent event within the facility's circuits.
 - c) All overcurrent devices shall be selectively coordinated such that the branch level circuits are deenergized first, leaving as many feeder and main level circuits in operation as possible during a faulting event.

MEDIUM AND HIGH VOLTAGE OVERCURRENT PROTECTION DEVICES

- (01) Governing Standards
- a) NEC Article 240
 - b) IEEE Std C37
- (02) Application
- a) Seller shall provide overcurrent protection devices for all conductors, busses and electrical equipment that may be damaged due excessive current on the circuit.
 - b) Seller shall provide overcurrent protection devices for all other equipment that may be damaged due to a fault or overcurrent event within the facility's circuits
 - c) All overcurrent devices shall be selectively coordinated such that the branch level circuits are deenergized first, leaving as many feeder and main level circuits in operation as possible during a faulting event.
 - d) HV protection shall be coordinated and agreed with the utility, as required.

5.16. Surge Arresters

- (01) Governing Standards
- a) IEEE C62
 - b) IEEE SA – 1672
 - c) IEEE 1299
 - d) NESC
- (02) Application
- a) All AC circuits and equipment shall be protected from transient over voltage events with the use of surge arresters.
 - b) Medium Voltage surge arresters shall be metal oxide varistor type, and shall be rated for the anticipated maximum continuous over voltage (MCOV) level for the circuit.

5.17. Switches**(01) Governing Standards**

- a) IEEE C37
- b) IEEE 1247
- c) UL 98
- d) UL 363
- e) UL 489
- f) NEC

(02) Application

- a) Switches shall be installed in the electrical circuits where indicated on the engineering plans.
- b) Switch voltage and current ratings shall be suitable for the application.
- c) All switches intended to be used for load break applications shall be marked as such, otherwise Seller shall label the device as non-load break rated.

(03) Types of switches

- a) Pad Mount
 - a. SF-6
 - b. Vacuum
- a) Gang Operated Air Break (GOAB)
- b) Knife Blade Disconnect
- c) Rotary
- d) AC or DC Contactor

5.18. Relays**(01) Governing Standards**

- a) IEEE C37
- b) NESC

(02) Application

- a) Protective relays shall be used for the automatic protection of circuits that cannot be protected by the sole use of fuses or stand-alone circuit breakers. This includes but is not limited to all medium voltage feeder and main circuits, substation transformers, and medium and high voltage buses.
- b) Relays must be microprocessor controlled.
- c) Relays may be single or multi-function devices, as long as the appropriate protective functions and setting levels can be achieved.

- d) Schweitzer Engineering Laboratory (SEL) is the preferred manufacturer, however the Seller may select alternative vendors upon approval from the owner.

5.19. Instrument Transformers

(01) Governing Standards

- a) IEEE C57.13
- b) UL 506

(02) Application

- a) Instrument transformers shall be used for converting primary line voltage or current to a level that may be read by an instrument such as a relay or meter.

(03) Ratings

- a) Instrument transformer current and voltage ratings shall be determined by the EPC Seller, based on their application. ii. All instrument transformers used for metering shall be of metering class, relay class transformers are not acceptable. For operational metering, 0.5 class accuracy is acceptable, with 0.2 class required for revenue metering.
- b) Relay or metering accuracy class instrument transformers may be used for protective relay applications, as long as the accuracy meets the requirements of that application.
- c) All Instrument current transformers shall be of accuracy class 0.15B0.5 with full output at two (2) times base rating.
- d) All Instrument potential transformers shall be of accuracy class 0.3%.

5.20. Battery & Battery Chargers

(01) Governing Standards

- a) IEEE 450-2010
- b) IEEE 36-1928
- c) IEEE 485
- d) IEEE 937
- e) UL 1236
- f) UL 1642
- g) UL 1989

(02) Application

- a) Batteries shall be used to provide uninterrupted power supply to electronics throughout the project.

(03) Types of Batteries

- a) Lead Acid
- b) Nickle-Cadmium
- c) Lithium Ion

5.21. Fiber Optic Cable and Data Conductors**FIBER OPTIC CABLE**

- (01) Governing Standards
 - a) ANSI/ICEA S-87-640
 - b) ANSI/EIA/TIA 455
 - c) ANSI/EIA/TIA 568
 - d) NEC Article 770
- (02) Cable Specification and Construction
 - a) All fiber optic cables shall be single mode, 24-strand, all-dielectric, indoor and outdoor rated, as applicable for the intended use, rated for installation in direct burial, in conduit, or aerial applications.
 - b) Fiber optic cables shall be rated temperature conditions between -40°C and 70°C.
- (03) CAT5 AND CAT6/ETHERNET CABLES
 - a) ANSI/EIA/TIA 568
 - b) NEC Article 800 and 840
- (04) Cable Specifications and Construction
 - a) All CAT5, CAT5e, CAT6 and other non-optical cables shall be constructed with shielded twisted pairs, cabled within a polyolefin insulated sheath, with an abrasion-resistant PVC or polyethylene outer jacket.

5.22. Raceways, Conduit Bodies & Boxes

- (01) Governing Standards
 - a) NEC
 - b) NESC
- (02) Materials Specification
 - a) All conduits and raceways inside buildings/interior locations shall be EMT.
 - b) All EMT fittings shall be compression type, not set screw type.
 - c) All raceway fittings in outdoor locations shall be rain-tight compression type, unless otherwise noted.
 - d) Schedule 40 PVC shall be used for buried conduits (not under roads) or for conduits encased in concrete unless otherwise noted on the drawings.
 - e) Raceways in exposed exterior locations or under roads shall be schedule 80 PVC.
 - f) PVC installed in exposed exterior locations shall be marked as UV resistant.
 - g) "L" and "T" conduit bodies shall not be used. Mogul-type conduit bodies shall be considered by Owner upon request.

- h) HDPE couplings with other types of conduit shall be listed for those conduit types, or approved by Owner
- i) Use Meyers (or approved equal) hub listed to provide moisture protection for conduit entrances in all applicable locations unless conduit enters from the bottom side of enclosure.
- j) All vertical mv conduit sweeps shall have minimum 36-inch radius. Horizontal mv conduit sweeps shall have minimum 60-inch radius.

5.23. Fixed Tilt Racking Structure

The fixed tilt racking system (if applicable) shall include the racking structure and all module mounting hardware. The racking vendor may supply the supports if desired, or the supports may be provided by a third party. The rack's azimuth and tilt angle shall be specified on the engineering drawings.

The racking system shall be designed using the environmental loads and the Occupancy Category as discussed above in section A-3.3.2 Environmental Loads. The racking structures, support attachments, module mounting brackets, fastening hardware, and supports (if applicable) shall have a 30-year design lifetime. Equipment shall have corrosion protection coatings as discussed in Corrosion Protection.

If the racking structure is a component of the solar array grounding and bonding strategy, the racking system shall meet UL 2703. Manufacturers' directions pertaining to grounding and bonding shall be followed.

Fixed tilt racking vendors under consideration shall have installed a minimum of 500 megawatts (MW) capacity in utility-scale projects.

5.24. Single Axis Tracking Structure

The single axis tracking system (if applicable) shall include the racking structure, mounting hardware, drive motor(s), and controller system. Additionally, any equipment required for the safe operation and wind stow (if applicable) should be included in the bid. The vendor may supply the supports if desired, or the supports may be provided by a third party. The trackers shall be oriented on a north-south axis and shall automatically track the path of the sun each day. All control equipment enclosures shall be rated NEMA 4.

Flexible cords or cables, where connected to moving parts of PV tracking arrays shall follow National Electrical Code 690.31 (E) pertaining to the number of strands required in flexible cabling, keeping in mind that this is a minimum standard and the number of strands may be significantly higher than Table 690.31 (E).

If the tracking structure is a component of the solar array grounding and bonding strategy, the tracking system shall meet UL 2703. Manufacturers' directions pertaining to grounding and bonding shall be followed.

Self-powered tracking systems shall be UL 3703 listed.

The tracking system shall be designed using the environmental loads and the Occupancy Category as discussed in section A-3.3.2 Environmental Loads of this specification. The torque tubes, support attachments, module mounting brackets, all fastening hardware, and supports (if applicable) shall have a 30-year design lifetime. Equipment shall have corrosion protection coatings as discussed in section A-3.3.5 Corrosion Protection. PV modules may be either 60-cell or 72-cell modules. Modules shall be oriented as modeled in Seller PVsyst or other modeling tool used by the Seller for System design.

As discussed in section A-3.3.6 Single Axis Tracking Structures, many trackers feature a “stow” option. If this feature is required for the racking, supports, and foundations to satisfy the design wind loads, a backup energy source shall be installed on the Site to ensure the tracker will be able to move into stow position during winds in excess of the supplier’s design wind speed if the power from the grid is interrupted. Owner does not require the backup energy source if the stow feature is not needed. Seller shall design the PV arrays’ mounting systems, foundations, and piers as provided in the Agreement. The design shall be based upon standard industry practice, including the requirements of applicable codes, standards, and permits, as well as the information and specifications provided by the module, inverter, transformer, switchgear, racking, and all other vendors.

Single axis tracking vendors under consideration shall have installed a minimum of 500 MW of capacity in utility-scale projects.

5.25. Direct Current Fused Combiner Boxes

Combiner boxes shall be rated for maximum system voltage and maximum system continuous and short-circuit currents.

Design should follow combiner box manufacturer instructions pertaining to temperature rating of output conductor in order to use 90° F conductor rating, combiner box manufacturer must certify box assembly as 90° F rated.

Enclosures shall be rated NEMA 4 and shall have integral key lock or provisions for padlocking.

DC inputs shall be fused with finger safe fuse holders for all hot conductors

Fuses shall have blown fuse indication.

Combiner box output shall have a means to be externally disconnected.

If the combiner box has a lightning protection device, the device should include a visual trip indicator.

5.26. Meteorological Stations

Seller shall provide complete solar meteorological weather stations for the Plant per the requirements of IEC 61724 -1 “Photovoltaic System Performance – Part 1: Monitoring” for Class A monitoring. The quality and quantity of stations will be as per Class A.

The required minimum measurements shall be as follows to meet Class A:

- (01) Global horizontal irradiance (measured by two instruments)
- (02) Plane of array irradiance (in the plane of the tracker if used)
- (03) Ambient air temperature and relative humidity
- (04) Cell temperature on a single solar module in the array
- (05) Wind speed and direction (measured at 2 and 10 meters)
- (06) Precipitation (rainfall)
- (07) PV module soiling and back of module temperature sensor

Below is a list of the general features the monitoring station shall include and other provisions the design shall accommodate:

- (01) Equipment calibration certificates
- (02) Summary of common calibration recertification timelines
- (03) Functional specifications for the measurement devices

- (04) Electrical schematic and mechanical installation drawings, proposed commissioning plan (flow chart) and site troubleshooting and problem resolution protocol (flow chart) for the monitoring systems
- (05) O&M manual that includes an overall description of the monitoring system, the routine O&M plan and schedule of maintenance events and procedures
- (06) Equipment and installation warranties

5.27. Supervisory Control and Data Acquisition

Seller shall supply and install an Owner-approved monitoring hardware and software package, including interconnection communications. The monitoring system must be selected to provide its 5-year Commercial Solar Monitoring Equipment and Service Package for the Plant. SCADA pricing shall include hardware and software (including all software subscriptions) for a minimum of 5 years. The monitoring system shall provide energy generation data, historical data, solar insolation attributes, and meteorological data. The system shall be configured to sample data at a rate of once per second, with 1-to-10-minute average intervals and shall be configured to update the server at least once every 15 minutes. The system shall be configured to sample and store the 1-to-10-minute averaged interval data for a period of 24 months.

The Seller shall supply a meteorological station that will provide current weather data as noted in section A-4.11 Meteorological Stations.

The monitoring system shall be capable of issuing alarms and notices to instantly alert the system manager and operation and maintenance (O&M) Seller to potential system problems and outages. The metering and monitoring system shall comply with the accuracy requirements and general standards set forth in IEC 61724.

The metering scheme shall be capable of reading the net electrical energy to the grid during daylight hours and the nighttime auxiliary loads when the Plant is in standby mode. The metering and monitoring system shall be compliant with Western Renewable Energy Generation Information System certification requirements for Renewable Energy Credit sales or trading per section A-4.13 Revenue Meter.

Data from the monitoring system can be accessed through the system's dashboard, which allows for public and administrator panel views. All electronics shall be enclosed in a NEMA 4 enclosure. This system may be housed in the same enclosure as the security equipment (see Section A-3.9). The data shall be collected at hardwired locations and transmitted wirelessly via a cellular modem to be provided and installed by Seller. Seller shall test the installed communications system to demonstrate its ability to meet the requirements of its intended use. Testing shall be done when the final system interconnections have been made.

Seller shall furnish and install all materials and equipment necessary to complete the SCADA installation. The monitoring system shall be configured for automatic reporting of generation statistics required by Owner. The data shall be collected at the hardware locations and transmitted wirelessly via a wireless SCADA system to be provided and installed by Seller. Points to be monitored by the SCADA system shall include, at a minimum:

- (01) Meteorological station
 - a) Monitor and record all items in section A-4.11 Meteorological Stations
- (02) Inverters
 - a) AC voltage
 - b) DC voltage
 - c) AC current

- d) DC current
- e) Kilowatts (kW)
- f) Kilowatt hours (kWh)
- (03) Metering
 - a) Monitor and store data from the Plant meter on an interval between 5 and 20 seconds
- (04) Transformers
- (05) Tracker control system integration, remote monitoring, and control
- (06) Any buildings or shelters
- (07) Plant switchgear

The following shall make up the SCADA calculated values list:

- (01) Model versus actual performance in kW and kWh
- (02) Day's energy in kWh
- (03) Month's energy in kWh
- (04) Year to date energy in kWh
- (05) Total lifetime energy in kWh
- (06) Plant performance ratio, current value
- (07) Plant performance ratio, day's average
- (08) Plant performance ratio, month's average
- (09) Plant performance ratio, year to date average
- (10) Plant performance ratio, since commissioning

All monitored plant electrical generation equipment (e.g., inverters, transformers, switchgear) shall be monitored to capture real time AC and DC electrical characteristics, including:

- (01) Voltage
- (02) Current
- (03) Power
- (04) Frequency
- (05) Power factor

All monitored plant electrical generation equipment (e.g., inverters, transformers, switchgear) shall be monitored to capture all diagnostic information, including:

- (01) Temperatures
- (02) Alarms
- (03) Status indicators
- (04) Fault states

5.28. Revenue Meter

A bi-directional revenue grade meter shall be installed to measure the total Plant output at the switchgear for accurately metering energy (kWh) generated by the Plant. The revenue grade meter shall be American National Standards Institute C12.20 0.2% Class UL listed, ISO9001 certified, which is accepted by all authorities requiring revenue grade. The meter must have a display for easy reading of current power generation and lifetime generation and shall be compliant with Western Renewable Energy Generation Information System certification requirements for Renewable Energy Credit sales or trading.

This revenue meter will be supplied by the Transmission Provider. Seller shall coordinate with the Transmission Provider for the installation of same.

5.29. Security Cameras and Related Equipment

The material furnished shall be in accordance with, but not limited to, the following codes and standards:

- (01) NFPA 70 - National Electrical Code
- (02) NFPA 101 - Life Safety Code
- (03) UL 294 - Access Control Systems (if applicable)
- (04) UL 1076 - Proprietary Burglar Alarm Units and Systems
- (05) American with Disabilities Act - Public Law 101.336
- (06) State Building Code

5.29.1. General Requirements

All security system components shall be UL labeled.

5.29.2. Security System Components

Security system components may consist of LED spot or LED flood lights, cameras, alarms, network video recorders, communication lines, and all wiring required for all the components. The security system shall be sufficient to monitor and deter any theft or vandalism onsite. The security component supplier shall provide detailed specifications of each component.

The Security Sub-Seller and Seller shall coordinate with the SCADA design/instrumentation and control engineer to ensure sufficient bandwidth is available on the network to accommodate the proposed security system. Owner may elect to reduce the equipment needs based on the location of the Site and subsequent security requirements.

Surveillance cameras and pan/tilt/zoom (P/T/Z) drives shall meet the following minimum requirements. Surveillance cameras and P/T/Z drives shall be provided by the Security Sub-Seller. Alternative solutions providing higher upgradeability and compatibility with future products are acceptable at no additional cost, subject to Owner's approval.

- (01) The P/T/Z unit shall meet the following design and performance specifications:
 - a) The unit shall be microprocessor controlled with network / IP based programming via standard WEB based interface.
 - b) Each pan/tilt drive unit shall operate as an independent unit with exclusive programming and setup data contained on each unit's nonvolatile memory.
 - c) The unit shall be capable of 360-degree continuous pan rotation with a vertical unobstructed tilt of +36 to -85 degrees.
 - a. Manual Control Speeds of: 0.1 degree to 40 degree per second (Pan), and 0.1 degree to 30 degree per second (Tilt)
 - b. Preset Speeds of: 100 degree per second (Pan) and 30 degree per second (Tilt)
 - d) The unit shall pan and tilt under manual control.
 - e) The unit shall be capable of 16 learned tours and 256 configurable preset locations for Alarm Call-up configuration.
- (02) The camera shall meet the following specifications:

- a) The sensor type shall be 1/2-.8-inch Type Exmor CMOS Sensor.
 - b) The camera shall provide a minimum of 1080p (1920x1080) resolution, at 30 Images per second (ips).
 - c) Camera shall provide a minimum of 2 simultaneous video streams: Dual H.264 or H.264 and Scalable MJPEG.
 - d) Camera shall allow for control and monitoring of video via IPv4 and IPv6 Networks.
- (03) The motorized lens shall meet the following design and performance specifications:
- a) The camera shall provide 16:9 Aspect Ratio and shall provide a 30X optical zoom and 12X Digital Zoom.
 - b) The lens shall provide horizontal angle of view of 59.5 degrees (wide) to 2.1 degrees (telephoto).
 - c) The lens shall feature an automatic focus with manual override.
 - d) A step-down power transformer shall be provided for each camera. Transformers shall be rated 120/24 V_{AC} and shall have an adequate Volt-ampere rating for the load at 40 degrees C ambient air temperature. Individual Fuse Distribution shall be provided.
- (04) The camera and lens housings shall be weatherproof and part of an Integrated Optics Cartridge (IOC). The IOC shall accommodate specified camera and lens combinations. IOC shall be dry nitrogen filled to 10 psig, to protect Camera Sensor / Lens optics from condensation and corrosion.
- (05) Camera assembly shall be provided with integrated IR Illumination. IR Illumination Transmitters shall be integrated to the Pan / Tilt Assembly Housing to provide IR Illumination for areas being viewed by the camera.
- a) IR Illumination shall be provided for distances up to and including 330 feet from each camera location.

5.29.3. Video Wiring System

- (01) Description: 100-ohm, four-pair UTP, covered with a black PVC jacket.
- a) Comply with ICEA S-90-661 for mechanical properties.
 - b) Comply with TIA/EIA-568-B.1 for performance specifications.
 - c) Comply with TIA/EIA-568-B.2, Category 6.
 - d) Listed and labeled by an NRTL acceptable to authorities having jurisdiction as complying with UL 444 and NFPA 70 for the following types:
 - a. Communications, Direct Burial Rated: Type F/UTP, complying with NFPA 262.
 - b. General Requirements for Cable Connecting Hardware: Comply with TIA/EIA-568-B.2, IDC type, with modules designed for punch-down caps or tools. Cables shall be terminated with connecting hardware of same category or higher. All terminations shall use TIA/EIA 568B wire termination color coding.
- (02) Power and/or Auxiliary Input/Output cable shall be multi-conductor twisted shielded cables selected for use with the specific equipment to be controlled for installation in concealed conduit system. Cables shall have outer jacket of PVC and shall be suitable for direct burial installation.
- (03) All cables and conductors that serve as control, sensor, low voltage power, or data conductors shall have surge protection circuits installed at each end that meet the IEEE C37.90.1 surge withstand capability test. Fuses shall not be used for surge protection.

5.29.4. Network Video Recorder and Multiplexor

- (01) The network video recorder (NVR) and multiplexer shall be provided as one integrated unit. The NVR shall be provided by the Security Sub-Seller.
- (02) The NVR shall provide for live and playback viewing while the system continues to record new images. It shall be capable of time division, multiplexing multiple cameras and storing their digitized and compressed images on integral hard disk drives, and search and retrieval either locally at the unit or from a remote work station using a graphical user interface. It shall have Ethernet connectivity.
- (03) The NVR shall record video on an internal hard disk drive(s). It shall support multiple internal and external hard disk drives of minimum 500 gigabytes, or large enough to store up to 1 month of the camera recordings.
- (04) The NVR shall support archiving of images on an external archiving device. It shall support recording on portable / removable storage media.
- (05) The NVR viewing software shall provide the following displays as a minimum in live and playback mode: full-screen, sequencing, quad, 9-way, or 12-way. It shall allow the user to rearrange cameras in any multi-screen display, in both live and playback modes. The display options shall include but not limited to:
 - a) Camera tilting
 - b) Title display, per monitor
 - c) Time and date, per monitor

5.29.5. Security Software

The Security Sub-Seller shall provide a minimum of two software and database management licenses. Seller shall provide two copies of the software on CDs for backup and a complete user manual. Software shall be Windows compatible. Seller shall provide free software upgrades during the warranty period of the system as a minimum.

5.30. Wires, Cable and Connectors

Seller shall provide information about proposed wire, cable, and connectors, including all underground facilities. Cable shall be designed and installed for a service life of 30 years. Cable for DC feeders and PV panel interconnect shall be 2-kilovolt 90°C (wet or dry) power cable type USE-2 or RHH/RHW-2 with XLPE jacket and UL 1581, VW-1 rating or approved equal for intended use capable of meeting DC collection system design current requirements. Externally installed cables shall be sunlight and ultraviolet resistant, suitable for direct burial, and conform to NEC 300.5 Underground Installation, Table 300.5 Minimum Cover Requirements, rated to the maximum DC voltage of the Plant.

PV panel interconnect connectors shall be: (i) latching, polarized, and non-interchangeable with receptacles in other systems, and (ii) tap branch connectors with multi-contact termination connectors. Grounding member shall be first to make and last to break contact with mating connector and shall be rated for interrupting current without hazard to operator.

Cables shall be listed and identified as PV wire as stated in NEC Article 690. If a cable tray is utilized, there shall be no self-tapping screws, only a clamping mechanism to secure the top. All underground cable shall be mapped and identified along its entire run with hazard tape and tracing, 18 inches above the cable elevation and 18 inches below finish-grade elevation.

Galvanized, rigid metal conduit where underground cable is exposed above ground or stubbed up to junctions or poles shall be used. Rigid metal conduit shall be included in the corrosion mitigation plan and shall be designed for a 30-year life in the Site soils and conditions. All 90-degree bends shall be in long sweeps installed in accordance with standard utility practices. Underground cable shall be direct-buried a minimum of 3 feet below finish-grade elevation. **No underground cable splicing shall be acceptable under any circumstance.** All cable splices shall be brought above ground and housed in a suitable enclosure or, if below grade, placed in a suitable vault that is clearly marked.

Cables shall be labeled in accordance with Section A-4.2 Signage and Labeling.

5.31. Plant Switchgear

Switchgear shall be located outdoors in a NEMA 4 lockable enclosure. Switchgear shall include an auxiliary compartment containing all instrument transformers associated with the protective relays and the 120/240-V CPT shown in the one-line diagram(s). The protective relay system shall be specified, designed, and installed in accordance with interconnecting utility's requirements. Switchgear monitoring and communication hardware shall be included to meet the requirements of sections A-4.12 Supervisory Control and Data Acquisition and A-4.13 Revenue Meter, and the metering requirements of Owner. Relay current transformers shall be C400 accuracy class.

The CPT shall be fused and disconnectable. The CPT shall be sized, and single-phase breakers shall be included to supply power to a 120-V convenience receptacle and an energy efficient light within the switchgear enclosure, switchgear heaters, and the 240/120-V_{AC} panelboard within the communications shelter (if applicable). The switchgear main breaker shall have vacuum fault interrupters and shall have provisions for bifurcation. Medium-voltage protective device selection and relaying should be based on the use of Schweitzer Electric Laboratories relays or approved other, as required and specified in the Interconnection Agreement.

In general, the interconnection design and components should meet the requirements of the interconnecting utility and the interconnection agreement (including the necessity of a grounding transformer if required).

5.32. Emergency Direct Current Battery System

The batteries and charger's location shall be specified in accordance with temperature and shading requirements, and the battery system shall meet the requirements set forth in the Interconnection Agreement. The battery system shall be sized: to provide DC power to trip, close, and recharge the switchyard 8 hours after a loss of power; recharge within 12 hours; and supply sufficient power to the SCADA and communications systems for 12 hours minimum. The battery sizing calculation shall be provided by Seller to Owner.

6.0 WARRANTIES

6.1. General Seller Warranty

Seller shall follow all material requirements of the warranties of the principal equipment suppliers using the procedures detailed in the manuals delivered upon completion of the Plant. All warranties shall be passed to Owner and shall be enforceable throughout the warranty period.

6.2. Solar Module Warranty

Provide the proposed module warranty duration, terms and conditions. At a minimum, solar module manufacturer shall provide a 25-year linear warranty on the solar modules with at least 80 percent of power output guaranteed at 25 years as more particularly described and provided in the module warranty to be provided by the Seller. The solar module manufacturer shall confirm that the warranty applies on an "as installed basis," i.e., it will confirm the panels were installed according to its requirements and specifications for installation.

Racking and Tracking System Warranty

Provide the proposed tracker warranty duration, terms and conditions. The tracking manufacturer, if applicable, shall supply a 5-year warranty for the installed structure and a 5-year warranty on the motor, and the racking design shall be certified by both the tracking manufacturer and the solar module manufacturer such that all warranties apply on an “as installed” basis. An extended warranty for parts only (motorized drives) shall be provided for a period of 10 years by Seller.

The racking manufacturer, if applicable, shall supply a 10-year warranty for the installed structure, and the racking design shall be certified by both the racking manufacturer and the solar module manufacturer such that all warranties apply on an “as installed” basis.

The racking and tracking manufacturer shall supply a minimum five (5) years full parts and labor replacement warranty, as more particularly described and provided by the Seller.

6.3. Inverter Warranty

Provide the proposed inverter warranty duration, terms and conditions. The inverter manufacturer shall provide a 5-year full parts and labor replacement warranty, as more particularly described and provided by the Seller. A six to 10-year warranty also may be offered by the inverter manufacturer. The inverter manufacturer shall confirm its warranty on an “as installed basis.”

6.4. Transformer Warranty

The transformer manufacturer shall provide a 5-year warranty for the transformers, as more particularly described and provided by the Seller.

6.5. SCADA Monitoring System and Security Equipment Warranty

Provide the proposed SCADA Monitoring System warranty duration, terms and conditions. Provide the proposed security system warranty duration, terms and conditions. The SCADA and security equipment system manufacturers shall provide a 5-year full parts and labor replacement and software upgrade warranty, as more particularly described and provided by the Seller.

6.6. Performance Warranty

This section not used.

7.0 APPLICABLE CODES AND STANDARDS

The Plant’s design, engineering, construction, interconnection, startup, and testing shall follow the applicable codes, standards, and publications that are in effect at the time of Plant initiation, and which are consistent with current utility industry standards. The codes and standards utilized shall be the latest editions in effect at the notice to proceed date.

Materials manufactured within the scope of Underwriters Laboratories shall conform to UL standards and have an applied UL listing mark. If no UL compliance is available, material and equipment shall be labeled or listed by a nationally recognized testing laboratory.

Where codes do not govern specific features of the equipment or system, Prudent Utility Practice, equipment manufacturer specifications, and standard industry standards shall apply. Where local codes or ordinances will have an impact on the design, Owner and Seller shall jointly address these with the local authorities having jurisdiction as provided in the Agreement.

8.0 DISTRIBUTION OR TRANSMISSION INTERCONNECTION

Seller is responsible for the cost of designing, procuring equipment for, and installing all interconnection and metering facilities required to deliver the Plant’s electrical output to the Point of Interconnection, in accordance with this Agreement and the Interconnection Agreement. Seller shall be aware of the relevant interconnection requirements for Small Generators, (less than 20 MW), and Larger Generators, (Greater than 20 MW) and design, install and operate the PV Plant accordingly.

Seller shall be fully responsible for working with and coordinating with the transmission provider to assure that the Plant is properly designed, constructed, and prepared to interconnect with the distribution system. Seller shall provide the interconnection equipment and structures to the Point of Interconnection as shown on the detailed design drawings and specified in the Interconnection Agreement. Seller shall coordinate its work on interconnection with the Owner and perform in accordance with any applicable requirements in the Interconnection Agreement. Seller shall provide Owner and the transmission provider with at least 15 days advance written notice of the first test that involves either backfeed or delivering energy to PacifiCorp and must be in compliance with the Interconnection Agreement.

9.0 OPERATIONS AND MAINTENANCE — MANUALS AND TRAINING

9.1. Documentation

Seller shall supply Owner with all manuals and/or handbooks (in printable electronic format) that provide, either in a single manual or handbook or collectively, complete operating and maintenance instructions (including inventories of spare parts and tools and parts lists with ordering instructions) for each major piece of equipment and system of the Plant. Each such manual and handbook shall comply with the requirements as set forth below and in **RFP Appendix A-7.2**.

9.2. Manuals

Seller shall provide Owner with six (6) paper copies and one editable electronic copy of all manuals.

Hard copy manuals shall be on standard 8-1/2" x 11" paper. Drawings and schedules which are to be bound into the manual shall also be 8-1/2" x 11" or 11" x 17" folded. Each manual shall be assembled and bound in heavy-duty post binders designed for rough usage. Light duty and ring binders are not acceptable. Binder capacity shall not exceed four inches, nor shall material included exceed the designed binder capacity. If the material to be furnished exceeds this capacity rating, multiple volumes shall be furnished. Binders shall be sized to the material to be contained, and capacity should not be more than approximately one-half inch greater than the thickness of material within the binder. All documents, illustrations, specifications, equipment data sheets, drawings, operating and maintenance instructions shall be in the English language. Use of the English system of units on documents is preferred; if the metric system of units is used, the drawing, data sheet, specification or illustration shall clearly indicate that the metric system of units is used. Each manual shall include a Table of Contents, front cover, side label and laminated index tabs and shall be of a consistent format.

The electronic copy of the manuals shall be organized in folders consistent with tabs in the paper manuals. Electronic copies of installation, operation and maintenance manuals shall be organized from the most general information in the top directory to the most specific information in the lowest level folder. The top-level folders shall include a document containing a directory of the subfolders describing the contents of each subfolder. Electronic copies of Installation, Operation and Maintenance manuals shall be organized by project, system, subsystem, equipment and components. Manufacturers' or vendors' electronic manuals shall be delivered as individual files. Seller shall not merge or combine manufacturer and vendor provided files containing manuals.

The manuals to be provided shall include:

Design Manuals

- (01) Design manuals shall contain the following items:
- (02) Drawing List, Drawing and Specification Identification System, Units of Measurement and Formats

- (03) System List and Equipment Numbering System
- (04) List of applicable drawings
- (05) System design requirements
- (06) System and equipment descriptions
- (07) Equipment lists itemizing type, performance and technical requirements.
- (08) Overall performance data

Start Up, Operation and Shutdown Manual for the Plant, including comprehensive and complete procedures for checkout, startup and testing of the Project and will include as a minimum the following items:

- (01) Plant start-up and shutdown procedures
- (02) Startup schedule
- (03) Startup organization chart
- (04) Administrative procedures
- (05) Data sheets
- (06) Test procedures for all tests required for Mechanical and Electrical Completion and Final Acceptance.
- (07) Turnover sequences and procedures
- (08) Safety clearance procedure
- (09) Work responsibility matrix
- (10) Installation, Operation, and Maintenance Manuals for the Equipment, including information typically supplied for equipment and/or systems such as the following items:
 - (11) System or equipment startup and shutdown procedures
 - (12) Description / design criteria of each item of equipment
 - (13) Nameplate information and shop order numbers for each item of equipment and components thereof
 - (14) Operating procedures and instructions for commissioning, startup, normal operation, shut down, standby and emergency conditions and special safety precautions for individual items of equipment or systems
 - (15) List of any start-up prerequisites
 - (16) Normal range of system variables
 - (17) Operating limits and hazards for all equipment and systems including alarm and trip set points for all devices
 - (18) Testing and checking requirements
 - (19) Effect of loss of normal power
 - (20) Tolerance of electrical supply frequency variation
 - (21) Final performance and design data sheets, specifications and performance curves for all equipment including test data and test curves
 - (22) Preventive maintenance schedule and maintenance instructions for equipment including standard and special safety precautions
 - (23) Lubrication schedule showing requirements and specifications for lubricants for equipment
 - (24) Dismantling and assembly procedures for equipment with associated tests and checks prior to returning equipment to service.

- (25) Detailed assembly drawings to complement assembly procedures mentioned above including parts lists and numbers for replacement ordering.
- (26) Setting and running clearances and tolerances
 - a) Cleaning procedures
 - b) Specifications for any gases, chemicals, solvents or lubricants
 - c) Drawing showing space provided for equipment maintenance for equipment and any fixed facilities for maintenance such as trolley beams, etc.
 - d) Methods for trouble-shooting
 - e) List of maintenance tools furnished with equipment
 - f) Installation instructions, drawings and details
 - g) Vendor drawings as appropriate
 - h) Installation, storage and handling requirements.

The above requirements are a minimum; however, requirements which are clearly not applicable to specific items or components may be deleted, however, any additional information which is necessary for proper operation and care of the equipment shall be included.

10.0 SPARE PARTS

No later than 90 days after the Effective Date the Seller shall provide to the Owner a recommended spare parts list, including quantities and prices if purchase with the contract, for the equipment and systems provided by the Seller. The recommended spare parts list shall include all expendable items that may be required during the operation of the Project. Each of the spare parts shall be fully identified by reference to the spares list, part number, cost, and manufacturer drawing number. Seller shall also identify spare parts that the Seller recommends should be stocked locally to ensure prompt repair due to any failure that can be reasonably expected, considering the length of time required to obtain replacement parts.

The Seller shall provide, receive, store locally, distribute and restock spare parts, materials, test equipment, instruments, tools, and consumables required for start-up and operation of the systems and equipment within its scope until **[Substantial Completion]**.

If the Seller, his suppliers, or sub suppliers cease manufacture of any of the spare parts, or if for any reason any spare part will become unavailable at any time during the life of the facility, the Seller shall notify the Owner in writing at least 180 days prior to the unavailability of such spare parts. The Seller shall provide the Owner the opportunity to purchase sufficient stock of spare parts to support the system for its expected life.

11.0 TOOLS AND EQUIPMENT

Seller shall provide all special tools, test instruments and computer programs, as applicable for maintenance and operation which are not normally or readily available. The Seller shall submit a complete list of tools and equipment needed for erection/installation and maintenance and a list of special tools and equipment that will be provided, including prices. Special tools and equipment shall become the property of the Owner at the completion of the PV installation. The Owner reserves the right to purchase additional quantities of tools if desired.

12.0 FINAL PLANT COMPLETION

Following is the step-by-step procedure for orderly completion of the Plant:

- (01) Mechanical and Electrical Completion
- (02) Q/A Q/C testing
- (03) Commissioning and Start-up procedures and tests
- (04) Interim operating time
- (05) Capacity Test
 - a) If Plant passes Capacity Test (Go to Final Acceptance and hand-over)
 - b) If failed Capacity Test – allowable period for corrective measures for re-testing of Capacity Test
- (06) Substantial Completion
- (07) Final Completion and hand-over to Owner

12.1. Step 1 Mechanical and Electrical Completion

Seller shall achieve Mechanical and Electrical Completion and assure that the Plant has been synchronized with the PacifiCorp Interconnection Facility (in accordance with PacifiCorp's requirements) before conducting the Capacity Test. Mechanical and Electrical Completion shall mean:

- (01) Equipment for the Plant has been installed, including with the required connections and controls to produce electrical power.
- (02) All equipment related to the solar tracking system (if applicable) has been installed and checked for alignment, lubrication, and rotation.
- (03) All remaining electrical systems have been checked out and are ready for operation.
- (04) All electrical continuity and ground fault tests and all mechanical tests and calibrations have been completed.
- (05) All instrumentation is operational and has been calibrated in accordance with manufacturers' standards and guidelines and, where possible, loop checked.

12.2. Synchronization Procedures and Requirements

All testing shall be done in accordance with the Interconnection Agreement and all the requirements to achieve electrical and mechanical completion of the plant.

12.3. Step 2 Quality Assurance/Quality Control

Seller shall submit to Owner a copy of its QA/QC plan for review not later than 45 days after contract execution for Owner review and comment. The Plant shall be managed in accordance with the program.

The QA/QC program shall include, but is not limited to, such procedures and systems as the following:

- (01) Road construction
- (02) Rebar and conduit placement
- (03) Concrete placement and testing
- (04) All wire insulation testing—Megger testing or very low frequency testing

- (05) Mechanical system—trackers, mounting structures, tracker controls
- (06) Factory testing of inverters and transformers by the manufacturer
- (07) PV source open-circuit measurements— V_{OC} at combiner boxes
- (08) Fuse tests
- (09) Termination pull testing
- (10) All visual inspections
- (11) Grounding continuity testing
- (12) Earth-ground resistivity testing
- (13) PV module inspection and manufacturer documentation of factory test per the manufacturer's existing program
- (14) Metering and instrumentation calibration testing
- (15) Step-up transformer testing
- (16) Inverter phase rotation and matching with utility
- (17) Relay settings at the point of interconnection to Owner
- (18) Verification of security camera system operations, including device points, sequences, and communications
- (19) Other Seller-prescribed procedures

All QA/QC testing procedures onsite shall be witnessed and documented by a qualified representative of Seller. Owner shall observe and witness QA/QC as necessary and at its discretion. A qualified engineer of Seller shall date and sign documentation indicating completion and acceptance of each onsite QA/QC test procedure.

12.4. Step 3 Commissioning and Startup

Seller shall provide the proposed commissioning and startup plan for the Plant at least 45 days prior to the proposed commissioning and startup dates. The plan shall follow procedures as dictated in IEC 62446-1.

Seller shall coordinate with Owner to develop an acceptable commissioning plan that includes a checkout and startup procedure. This work will assure: that systems are activated in a manner that is safe for personnel as well as for the equipment, that Seller work is complete and according to the contract documents, and that the systems perform as required by the contract documents and are ready to be turned over to Owner. As the construction and installation of the systems nears completion, Seller shall prepare punch lists and conduct system walk-downs, sub-system and system checkouts, startups, testing, and turnovers.

The final approved Acceptance Test and Commissioning Procedures shall follow IEC 62446-1, and at minimum, include the following:

- (01) Safety plan during startup and commissioning
- (02) Review of all QA/QC testing on the DC and AC sides of inverters
- (03) Detailed procedure for Plant startup, including switching sequencing
- (04) Confirm testing and energizing inverters in conformance with manufacturer's recommended procedures; note operating voltages; and confirm inverter is performing as expected

- (05) Under full sun conditions, and after at least 15 minutes of operation, taking and recording Plant operating data—such as but not limited to megawatts direct current, megawatts alternating current (MW_{AC}), V_{DC} , V_{AC} , I_{DC} , I_{AC} , Solar Radiation, etc.
- (06) Testing the system control and monitoring system to verify that it is performing correctly
- (07) Testing the communication system for offsite monitoring
- (08) Testing the Plant metering and protective relaying to verify they meet utility requirements
- (09) Detailed procedure for interface and initialization with the grid
- (10) Documentation of successful startup and commissioning procedure
- (11) Written notification submitted by Seller to Owner that the completion of Acceptance Testing and Commissioning has occurred

Upon successful completion of energizing and startup, the Plant will be considered operable. The Plant will then move to the Interim Operating Period where Seller shall make the Plant ready for Capacity Testing.

12.5. Step 4 Interim Operating Period

Following successful completion of the startup and commissioning of the Plant, the Seller shall have a maximum of 45 days to resolve any operating issues. The Owner-designated operating and maintenance team shall receive training regarding the Plant during this period. After the successful execution of the Interim Operating Period, the Seller shall perform a Capacity Test Procedure to verify the rated output for the Plant. Seller is not required to use the maximum 45 days, rather it is an allowance of time.

12.6. Training

The Seller shall provide training for the PV system as specified below. The Seller shall determine the content and duration for each training session. The suggested class durations in this specification are meant to illustrate the level of training expected. Performance evaluation testing of all trainees (i.e. a written test) is required for all classes except the Orientation Training

12.7. Operator Training

The Seller shall provide the necessary training in proper operation of the PV system and related equipment. It is anticipated that this session will last 3-5 days. This session will be limited to a maximum of 20 people. Emphasis shall be placed on hands-on operating experience interspersed with the critical background as necessary, including switching procedures and emergency response training.

12.8. Maintenance Training

The Seller shall provide necessary training in maintenance of the PV system and related equipment, providing maintenance by the Owner option is chosen. The maintenance training shall be scheduled after successful completion of the availability guarantee period. It is anticipated that maintenance training will last 3-5 days. This session will be limited to a maximum of 20 people. The maintenance training shall include, but not be limited to:

- (01) normal maintenance methods
- (02) repairs and replacement
- (03) diagnostic procedures
- (04) equipment calibration
- (05) re-energization

- (06) special tests
- (07) special tools
- (08) safety and grounding procedures

12.9. Step 5 Capacity Test

Upon notification that the Plant is ready for field testing, the Seller, in the presence of Owner-designated engineers or a third-party independent engineer, shall complete the Capacity Test. The Test will be performed under field environmental conditions (in the field irradiance, temperature, and measured capacity in MW_{AC}) according to the procedures described in IEC TS 61724-2 “Photovoltaic System Performance Part 2: Capacity Evaluation Method”. The metering and monitoring procedure for the Capacity Test shall conform to the IEC Standard “Photovoltaic Systems Performance – Part 1 Monitoring”. For the basis of the Capacity Test, that the inverter stations will be producing AC power at a power factor of 1.0.

Seller shall submit its proposed plan to comply with the testing procedures 60 days prior to the date that Seller anticipates the commencement of the test. The Seller shall include in the testing procedure the proposed reference conditions for the testing which will be reviewed and approved by the Owner and its engineers. The objective of the Capacity Test is for Seller to demonstrate to Owner that the Plant has achieved the performance (in MW_{AC}) under the reference test conditions (irradiance, ambient temperature, wind, and other parameters used to define the capacity performance). Seller’s Capacity Test procedure submittal shall, at a minimum, include a listing of test instrumentation, calibration procedures, test duration, type of data collected and collection frequency, test data collection procedures, and test reporting conforming to IEC 61724 Parts 1 and 2.

The objective of the testing shall be for the Seller to compare the actual measured capacity (MW_{ACTUAL}) to the contracted capacity ($MW_{CONTRACT}$) which are defined as follows:

MW_{ACTUAL} = The Plant capacity in MW_{AC} as measured resulting from the IEC 61724 capacity test at the reference test conditions.

$MW_{CONTRACT}$ = The Plant ‘guaranteed contract capacity’ by Seller in MW_{AC} at reference test conditions. (Seller bid)

Seller shall submit preliminary results of the Capacity Test within 24 hours of the conclusion of the test. Upon Independent certifier’s acceptance of the preliminary test results, Seller shall submit to Owner a detailed test report within 10 business days of the completion of the Capacity Test. The test report shall consist of the following:

- (01) Any agreed upon deviations to the test procedures
- (02) Instrument calibration sheets/certificates
- (03) Test data (manual and from the data acquisition system)
- (04) Corrected test data
- (05) Field notes
- (06) Calculations
- (07) Power factor at which test was taken
- (08) Post-test uncertainty analysis
- (09) Conclusion

If the rating falls below the guaranteed output, Seller shall take measures to bring the Plant up to the required rating.

If Seller chooses to take corrective measures to bring the power rating up to an acceptable level, then retesting may occur following notification to Owner in writing.

12.10. Step 6 Substantial Completion

After the startup and commissioning is successfully demonstrated to Owner's satisfaction in accordance with **RFP Asset Purchase and Sale Agreement**, the Plant will be considered Substantially Complete. To demonstrate substantial completion, the Seller shall:

- (01) Commission the completed system in accordance with the tests to verify that:
 - a) The system is capable of being operated at all levels and operating modes in accordance with the operating guidelines, applicable laws, applicable standards, applicable permits, prudent utility practices, and requirements of the contract documents.
 - b) The Plant is functioning as expected within acceptable parameters and as designed at a nameplate capacity as per the final results of the Capacity Test.
- (02) Facilitate completion or execution of any incentive- or rebate-related documents or other documents required for any warranty to become effective or to be assigned to Owner.
- (03) Coordinate with PacifiCorp confirming that the facility has been installed per the Interconnection Agreement.
- (04) Cause the Plant and all items of equipment and improvements at the Plant to be designed, manufactured, installed, calibrated, and tested where applicable in accordance with the published standards (as of the dates specified) listed in this Technical Specification; Seller shall notify Owner of any standards of such organizations that are inconsistent with each other and advise Owner of the manner in which it intends to resolve such inconsistency in accordance with the published standard.
- (05) Acceptance testing of security system shall include verifying that each device point and sequence is operating correctly.
- (06) Provide Owner a startup manual in conformance with section A-8.1.1 as part of the plant startup procedures.
- (07) Provide Owner with all training and documentation as required to satisfy the requirements for Substantial Completion as listed in **Appendix A-7.2**.
- (08) Within 45 days prior to Substantial Completion Seller shall complete training of Owner in the operation and recommended maintenance of the Plant.

12.11. Step 7 Final Completion

After Substantial Completion, Seller shall complete all punch-list items; demobilize; clean and clear the Site; submit all as-built drawings; O&M manuals, and spare parts lists; complete all training; deliver all spare parts onsite; and transfer all permits to Owner. Prior to submitting its request for a Final Acceptance Certificate, Seller shall perform the following tasks without limitation:

- (01) Identify punch-list items and provide timeline for completion. Following the Final Acceptance Date, Seller shall complete the items on the punch-list in accordance with the standards described herein, and as quickly as reasonably practical. Seller shall coordinate with Owner regarding continued Site access.
- (02) Conduct a final clean-up of the Site.
- (03) Remove all its equipment from the Site (other than equipment, supplies, and materials necessary or useful to the operation or maintenance of the Plant, and equipment, supplies, and materials directed by Owner to remain at the Site until completion of the Plant).

- (04) Tear down and remove all temporary structures on the Site built by Seller or its Subcontractors and restore such areas to a condition consistent with that of a newly constructed solar PV power plant, except as required by any provision of this Agreement.
- (05) Remove all waste, rubbish, and hazardous material from and around the Site and disposed in accordance with all state, federal, and local regulations.
- (06) Provide Owner with copies of all O&M manuals and warranties for the Plant.
- (07) Provide final as-built documents upon completion.
- (08) Complete all performance testing in accordance with the Capacity Test.
- (09) Meet all requirements listed below.

12.12. Requirement for Final Completion

Final Completion of the Work shall be deemed to have occurred only if all the following have occurred:

- (01) Seller has achieved Substantial Completion in accordance with Article 14;
- (02) Owner has received final “as-built” drawings in accordance with the terms of this Contract;
- (03) the Punchlist Items have been completed to the reasonable satisfaction of Owner;
- (04) Seller has delivered the Final Release and Waiver of Liens and Claims in accordance with Section 7.6 and has delivered such other documents and certificates as Owner has reasonably requested to ensure compliance with all Applicable Laws;
- (05) Seller has paid Owner all amounts due hereunder and not in dispute; and
- (06) Seller has delivered to Owner a Notice of Final Completion stating that all the preceding conditions in this Section 15.4 have been satisfied.

12.13. Procedures for Final Completion

When Seller believes that it has achieved Final Completion, it shall deliver to Owner a Notice of Final Completion. Such Notice shall contain a report in a form reasonably acceptable to Owner, and with sufficient detail to enable Owner to determine that Seller has achieved Final Completion. Owner shall, within twenty (20) Days following receipt of such Notice, either: (a) approve Seller’s Notice of Final Completion, indicating Owner’s acceptance of the achievement of Final Completion; or (b) if reasonable cause exists for doing so, notify Seller in writing that Final Completion has not been achieved, stating in detail the reasons therefor. If Owner delivers the Notice under the preceding clause (b), Seller promptly shall take such actions, including the performance of additional Work, to achieve Final Completion, and upon completion of such actions, shall issue to Owner a revised Notice of Final Completion pursuant to this Section 15.5. Such procedure shall be repeated as necessary until Final Completion has been achieved. If Owner fails to respond to Seller’s submitted Notice of Final Completion within the time set forth above, Owner shall be deemed to have approved Seller’s Notice of Final Completion. For all purposes of this Agreement, the Final Completion Date shall be the date on which Seller delivers to Owner the Notice of Final Completion that Owner ultimately accepts or is deemed to have accepted (or pursuant to a later determination under the dispute resolution procedures, should have accepted). Any disputes regarding the existence or correction of any such alleged

deficiencies shall be resolved pursuant to Article 35. Contract shall cause Final Completion to occur no later than sixty days following the Substantial Completion Date.