

BEFORE THE WASHINGTON UTILITIES AND TRANSPORTATION COMMISSION

DOCKET NO. UE-17_____

DOCKET NO. UG-17_____

DIRECT TESTIMONY OF

HEATHER L. ROSENTRATER

REPRESENTING AVISTA CORPORATION

I. INTRODUCTION

Q. Please state your name, employer and business address.

A. My name is Heather Rosentrater and I am employed as the Vice President of Energy Delivery for Avista Utilities, at 1411 East Mission Avenue, Spokane, Washington.

Q. Would you briefly describe your educational background and professional experience?

A. Yes. I received a Bachelor of Science degree in electrical engineering from Gonzaga University, and hold a Professional Engineer (PE) credential. I joined Avista in 1996, and worked initially as an electrical engineer at Avista's former subsidiary Avista Labs, where I developed electrical systems for fuel cells. I joined Avista Utilities in 2003, and have broad experience on both the electric and natural gas side of the business, having managed departments and projects in transmission, distribution, SCADA, asset management and supply chain, as well as business process improvement using LEAN and Six Sigma techniques. I was named to my current position in December 2015. In this role, I am responsible for electric and natural gas engineering, operations, and shared services – fleet, facilities and business process improvement.

I currently serve on the board of directors for the Vanessa Behan Crisis Nursery and the West Valley Education Foundation in Spokane. In addition, I am a member of the Washington State University School of Engineering and Computer Science Executive Council.

1 **Q. What is the scope of your testimony?**

2 A. I will provide an overview of the Company’s electric and natural gas energy
3 delivery facilities, discuss our electric reliability objectives, types of investments, and system
4 performance, and explain the factors driving our investment in electric distribution
5 infrastructure. My testimony will explain why our planned investments in electric distribution
6 are necessary to maintain the current levels of asset health and performance of our system and
7 will discuss the need for each distribution capital project and program by the “Investment
8 Driver” classification used to categorize our infrastructure investment needs. I will describe
9 how our planned compliance with mandatory federal standards for transmission planning is
10 driving a greater demand for new investment, and why our planned investments in natural gas
11 distribution are necessary in the time frames they are being completed. Finally, I will explain
12 why each capital investment planned for our fleet and facilities areas are necessary to support
13 the efficient delivery of service to our customers, today and into the future. Overall, my
14 testimony will demonstrate that:

- 15 1. Avista’s recent past, current, and planned investments in electric distribution
16 infrastructure are necessary, and why the failure to make these investments at this time
17 would impair the performance of our system and harm our ability to deliver safe and
18 reliable service to our customers. As such, the Company’s investments are necessary
19 in the time frames they are being completed.
20
- 21 2. The investments we make to uphold the current reliability of our electric distribution
22 system and to comply with required federal standards for transmission reliability are
23 conservative, thoroughly evaluated, and cost-effective for our customers.
24
- 25 3. The approaches used by our business units to identify, evaluate, prioritize and
26 recommend capital projects and programs ensure that we are properly identifying and
27 funding the highest priority needs in this planning cycle in a prudent and business-like
28 manner.

1 4. Even with our current level of infrastructure investment, the Company has identified
 2 needs for investment that are not fully funded in this planning cycle, in an effort to
 3 balance investment demand with the planning principles we consider in setting our
 4 overall investment limit.

5
 6 A table of the contents for my testimony is as follows:

<u>Description</u>	<u>Page</u>
I. INTRODUCTION	1
II. OVERVIEW OF AVISTA’S ENERGY DELIVERY SERVICE	4
III. ELECTRIC DISTRIBUTION INVESTMENTS	8
IV. ELECTRIC TRANSMISSION INVESTMENTS	25
V. NATURAL GAS SYSTEM INVESTMENTS	40
VI. FLEET AND FACILITIES INVESTMENTS	50

15
 16 **Q. Are you sponsoring any exhibits in this proceeding?**

17 A. Yes. I am sponsoring Exh. HLR-2 which shows the number of customers and
 18 customer energy usage for each customer class. Exh. HLR-3 is the Company’s Electric
 19 Distribution System 2016 Asset Management Plan, Exh. HLR-4 is the Company’s Electric
 20 Substations 2016 System Review performed by Asset Management, Exh. HLR-5 is the
 21 Company’s Electric Transmission System 2016 Asset Management Plan, and finally Exh.
 22 HLR-6 contains the capital business case summary documents for each of the infrastructure
 23 investments described in my testimony.

1 **II. OVERVIEW OF AVISTA’S ENERGY DELIVERY SERVICE**

2 **Q. Please describe Avista Utilities’ electric and natural gas utility operations.**

3 A. Avista Utilities operates a vertically-integrated electric system in Washington
4 and Idaho. In addition to the hydroelectric and thermal generating resources described by
5 Company witness Mr. Kinney, the Company has approximately 18,300 miles of primary and
6 secondary electric distribution lines. Avista has an electric transmission system of 685 miles
7 of 230 kV lines and 1,534 miles of 115 kV lines.

8 Avista owns and maintains a total of 7,650 miles of natural gas distribution lines, and
9 is served off of the Williams Northwest and Gas Transmission Northwest (GTN) pipelines.
10 A map showing the Company’s electric and natural gas service area in Washington, Idaho and
11 Oregon is provided by Company witness Mr. Morris in Exh. SLM-3.

12 As detailed in the Company’s 2015 Electric Integrated Resource Plan¹, Avista expects
13 retail electric sales growth to average 0.6% annually and customer growth is projected to
14 increase approximately 1% for the next twenty years in Avista’s service territory, primarily
15 due to increased population and business growth.

16 Also, based on Avista’s 2016 Natural Gas Integrated Resource Plan², in
17 Washington/Idaho the number of natural gas customers is projected to increase at an average
18 annual rate of 1.10%, with demand growing at a compounded average annual rate of 0.36%
19 over the next twenty years.

20 **Q. How many customers are served by Avista Utilities in Washington?**

¹ A copy of the Company’s 2015 Electric IRP has been provided by Mr. Kinney as Exh. SJK-2.

² A copy of the Company’s 2016 Natural Gas IRP has been provided by Company witness Ms. Morehouse at Exh. JM-2.

1 A. Of the Company's 377,285 electric and 240,294 natural gas customers (as of
2 December 31, 2016), 245,916 and 156,777, respectively, were Washington customers.

3 **Q. Please describe the Company's operation centers that support electric and**
4 **natural gas customers in Washington.**

5 A. The Company has construction offices in Spokane, Colville, Othello, Pullman,
6 Clarkston, Deer Park, and Davenport.

7 **Q. Please describe the Company's approach to managing the reliability of its**
8 **electric distribution system?**


9 A. Avista is focused on maintaining a high degree of electric reliability as an
10 important aspect of the quality of our service, particularly as our society becomes ever more
11 reliant upon electronic technologies. The Company's objective has been primarily to maintain
12 our current level of reliability.

13 **Q. How does the Company track its reliability performance?**

14 A. For many years Avista has measured, tracked and reported the number of
15 outages and the duration of outages that our customers experience on average each year.³ Our
16 annual results for the number of electric outages and outage duration on average are provided
17 for the period 2004-2016 in Illustration No. 1 on a system basis.

³ The number of outages on average is reported as the System Average Interruption Frequency Index (or SAIFI), and the duration of outages on average as the System Average Interruption Duration Index (or SAIDI).

Illustration No. 1 – Duration and Frequency of Outages



Q. What does Illustration No. 1 show?

A. Although it is the norm for the number of outages and the average length to vary each year due to factors beyond Avista’s control, such as major weather or wind events, our long-term reliability has been stable. In addition to these primary statistics, we report on several other utility-wide measures of reliability, the geographic areas of greatest reliability concern on our electric system, and our plans to improve service performance in those areas of greatest concern. These plans include investments targeted to: 1) replacing certain sections of overhead feeders with underground lines when cost effective; 2) relocating lines to reduce outages caused by trees and to give our crews better access to speed up outage repairs; 3) implementing special tree trimming and wood pole inspection; 4) improve fuse coordination⁴

⁴ Fuse coordination refers to the engineering scheme of ensuring we have the properly-sized fuses for system protection at each juncture of a feeder. Good fuse coordination helps ensure that an outage fault is restricted to that portion of the feeder network where the damage has occurred.

1 on the feeder and laterals to reduce the size of an outage; and 5) dividing individual feeders
2 into separate segments, as well as installing operating devices to sectionalize individual
3 feeders, and other means necessary and cost effective to ensure our customers receive a
4 reasonable level of service quality and reliability.

5 **Q. Please describe the overall investments the Company makes to maintain**
6 **and improve upon its current level of reliability?**

7 A. Avista has in the past referred broadly to individual investments we make as
8 having the purpose of “improving reliability.” This reflects the fact that many investments,
9 especially distribution investments made to replace deteriorated assets, are very likely to
10 improve the reliability of the specific infrastructure that is being rebuilt or replaced. This is
11 the case because the likelihood of failure of an asset generally increases with age and
12 deterioration over its service life. Avista’s many infrastructure investments often include at
13 least a mention of these reliability benefits. In the great majority of cases, however, the
14 *predominant* need for these investments is to replace assets that have reached the end of their
15 useful life, or to a lesser degree to solve capacity and performance issues. This timely
16 replacement of deteriorated assets is crucial to our ability to uphold and maintain our current
17 levels of reliability performance.


III. ELECTRIC DISTRIBUTION INVESTMENTS

A. Avista’s Distribution Investments from 2005 - 2016

Q. How do the electric distribution investments made by Avista over the past several years compare with those made by other similar utilities?

A. Avista, like utilities across the country have responded to similar needs for increased investment in electric transmission and distribution infrastructure on a system basis as shown in Illustration No. 2.⁵

Illustration No. 2



⁵ Results are from the data set gathered and reported by the Energy Institute of the University of Texas, Austin. Fares, L., Robert, King, Carey W., “Trends in Transmission, Distribution, and Administration Costs for U.S. Investor Owned Electric Utilities,” 2016. UTEI/2016-06-1, 2016, available at <http://energy.utexas.edu/the-full-cost-of-electricity-fce/.38> electric utilities

1 Organizations such as the Edison Electric Institute reported total utility investments in
2 electric transmission and distribution facilities doubling between 2009 and 2014, noting that
3 investments in distribution infrastructure alone reached \$22.5 billion in 2014, an increase of
4 8% over 2013.⁶ The American Society of Civil Engineers in 2011 conducted an extensive
5 review of then-current trends in electric utility investments, and identified a \$37 billion
6 “investment gap” between those current plans and the infrastructure investments needed by
7 year 2020.⁷ Their report on electric infrastructure was updated in 2016, noting the *significant*
8 *increased investment that had been made by the industry* compared with the 2011 forecast of
9 planned investments, but it still identified an \$18 billion investment gap between current
10 spending plans and the investments that will be needed by year 2025.⁸ The report noted that
11 54% of the \$18 billion gap was attributed to the needs of electric distribution systems alone.

12 In addition to the similarity in the overall pattern of investment, the Company’s annual
13 distribution investments have been similar to those of other electric utilities measured on a
14 cost per customer basis. Illustration No. 3, below, shows the annual electric distribution capital
15 cost per customer for 38 electric utilities similar in size to Avista,⁹ and the Company’s annual
16 capital cost per customer. The illustration shows the maximum, and the average annual capital
17 cost per customer for this group. As noted above, the Company’s investments in electric
18 distribution infrastructure on a system basis were depressed for several years early in this

⁶ 2015 Financial Review: Annual Report of the U.S. Investor-Owned Electric Utility Industry. Edison Electric Institute.


⁷ Failure to Act. The Economic Impact of Current Investment Trends in Electricity Infrastructure. American Society of Civil Engineers. 2011.

⁸ <http://www.infrastructurereportcard.org/wp-content/uploads/2016/10/ASCE-Failure-to-Act-2016-FINAL.pdf> pages 16 and 17.

⁹ Ibid. Report of the Energy Institute of the University of Texas, Austin. For this figure Avista selected a subset of those utilities similar in the number of electric customers and peak loads from the more than 200 utilities in the data set. A total of 38 utilities were selected based on the parameters of the number of customer between 200,000 and 400,000, and peak loads between 1,000 MW and 3,000 MW.

1 period, as reflected in our below average cost per customer. Our increasing investments
 2 pushed our per customer cost above the national average in 2005, however, our costs have
 3 generally converged with the group average since 2012.

4 **Illustration No. 3**



14 **Q. What conclusion do you draw from the comparison of Avista's**
 15 **investments in electric distribution infrastructure with those of the broader utility**
 16 **industry since 2000?**

17 A. The pattern of investments made by the Company during this period bear a
 18 striking resemblance to that of the industry, which should not be a surprise, since we are all
 19 responding to the same investment needs: first, the need to replace an increasing amount of
 20 infrastructure that has reached the end of its useful life, and second, responding to the need
 21 for reliability and technology investments required to build the integrated energy services grid
 22 of the future.


1 **B. Currently Planned Investments in Distribution Infrastructure**

2 **Q. Would you please summarize the distribution investments on a system**
3 **basis that are planned for years 2017 – 2021?**

4 A. Yes. Planned investments for this period, grouped by investment driver, are shown in
5 Table No. 1 below on a system basis, and the expected transfers-to-plant by “driver” is
6 provided in the following Illustration No. 4. Please see Company witness Mr. Morris Exh.
7 SLM-3, consisting of an Infrastructure Investment Plan identifying six “drivers” of
8 infrastructure development. These are:

- 9 1. Respond to customer requests for new service or service enhancements;
10 2. Meet our customers’ expectations for quality and reliability of service;
11 3. Meet regulatory and other mandatory obligations;
12 4. Address system performance and capacity issues;
13 5. Replace infrastructure at the end of its useful life based on asset condition, and;
14 6. Replace equipment that is damaged or fails, and support field operations.

1 **Illustration No. 4**



10

11 As the illustration shows, the great majority of our planned investment is required to

12 connect new customers who request electric service to replace assets that have reached the

13 end of their useful life, and to replace failed assets and support operations. In the following

14 sections, I will further explain the need for these investments, by project and program, and by

15 investment driver.¹⁰

¹⁰ The figures contained within each of the Tables in my testimony reflect “transfers-to-plant” during the respective calendar years; as such, the amounts may differ from the amounts shown for any particular line item in the Infrastructure Investment Plan (Exh. SLM – 3) or in the associated Business Cases (Exh. HLR – 6), which reflect budgeted capital spend numbers. The costs shown in Illustration No. 4 for Customer Service Quality and Reliability are derived from the feeder automation portion of the Grid Modernization Program, which costs are included as part of the overall Grid Modernization investments shown in Table No. 1 on next page.”

Table No. 1

Distribution Capital Projects (System) In \$(000's)					
Business Case Name	2017	2018	2019	2020	2021
<u>Traditional Pro Forma Study Projects:</u>					
Asset Condition					
Distribution Grid Modernization	15,051				
Distribution Wood Pole Management	9,000				
	<u>24,051</u>				
<u>End of Period Rate Base Study and Rate Year Projects:</u>					
Asset Condition					
Dist Grid Modernization		13,929	14,333	12,942	12,942
Distribution Transformer Change-Out Program	3,000	1,200	1,200	1,200	
Distribution Wood Pole Management		9,500	9,500	9,000	12,000
Primary URD Cable Replacement	503	1,000	1,000	1,000	1,000
Customer Requested					
New Revenue - Growth	23,775	23,249	22,668	23,055	23,123
Failed Plant and Operations					
Distribution Minor Rebuild	9,105	8,900	8,900	8,900	8,900
Meter Minor Blanket	505	300	300	300	300
Spokane Electric Network	2,605	2,300	2,300	2,300	2,300
Mandatory and Compliance					
Elec Replacement/Relocation	2,600	2,700	2,800	3,000	3,100
Environmental Compliance	350	350	350	350	350
Franchising for WSDOT	1,594	200	200	200	200
Performance and Capacity					
LED Change Out Program	2,900	2,000	2,320	2,000	
Segment Reconductor and FDR Tie Program	6,587	4,900	5,001	5,000	5,000
	<u>53,524</u>	<u>70,528</u>	<u>70,871</u>	<u>69,247</u>	<u>69,215</u>
	<u>\$ 77,575</u>	<u>\$ 70,528</u>	<u>\$ 70,871</u>	<u>\$ 69,247</u>	<u>\$ 69,215</u>

Traditional Pro Forma Study Projects:**Asset Condition:**

Q. Please describe and list the Asset Condition Investment Drivers included in the Traditional Pro Forma Study and explain why these investments are such a large portion of our overall capital needs?

1 A. Certainly. Assets of every type degrade with age, usage and other factors, and
2 must be replaced or substantially rebuilt at some point in order to ensure we continue to deliver
3 reliable and cost effective service. Projects or programs in this driver are defined as:
4 *“investments to replace assets based on established asset management principles and*
5 *systematic programs adopted by the Company, which are designed to optimize the overall*
6 *lifecycle value of the investment for our customers.”*¹¹

7 The replacement of assets based on condition is essentially the practice of removing
8 them from service and replacing them at the end of their useful life. Across the utility industry,
9 and likewise for Avista, the replacement of assets based on condition often constitutes the
10 largest type of the infrastructure investments required each year.¹² In a survey of 433 U.S.
11 electric utility executives, 47% listed “old infrastructure” as the most challenging issue they
12 face, with the next-closest infrastructure issues reported as “Grid Reliability” (17%) and Smart
13 Grid Deployment (16%).¹³ As an industry we face this investment demand today because the
14 sizeable infrastructure built during the period of economic growth and expansion following
15 World War II, and extending generally into the 1970s, has either reached, or is nearing the
16 end of, its useful life and must be replaced.¹⁴ As demonstrated earlier in my testimony, our
17 Company like utilities across the nation have stepped up the level of investments needed to
18 accommodate the orderly replacement of these facilities. For our electric distribution system,
19 these investments are required to uphold and maintain the capability of our various feeder
20 equipment, overhead conductor and poles, transformers, and underground cables.

¹¹ Exh. SLM – 3, page 30.

¹² Exh. SLM – 3, page 31.

¹³ Why Utilities are Rushing to Replace and Modernize the Aging Grid: State of the Electric Utility 2015.

¹⁴ Exh. SLM – 3, page 31.

1 **Q. What are these projects?**

2 A. The following projects fall within the category of “Asset Condition” under the
3 Traditional Pro Forma Study:

4 **Distribution Grid Modernization –2017: \$15,051,000**

5 In order to properly select¹⁵ the most appropriate feeders for rebuilding, Grid Modernization
6 uses inventory information from the Wood Pole Management Program and our Avista
7 Facilities Management System, to assess the potential energy efficiency savings, avoided
8 customer outages, and avoided expenses for failure of equipment. This feeder criteria
9 information is used to rank the potential benefits for each compared with all of the other
10 feeders on our system. The top ranked feeders are then balanced among Company operating
11 districts, jurisdictions and urban vs rural service. In the process of evaluating feeders for
12 potential rebuilding, our engineers evaluate reliability results for each feeder, study the actual
13 loadings on each phase of the feeder under a range of seasonal conditions and model the
14 average and peak loadings expected after the phase loads are balanced. They also model the
15 capacity of the overhead conductors, by segments on the trunk and laterals, to identify any
16 limitations as well as potential for energy savings. By integrating all of this information, along
17 with the full range of asset age and condition data, our engineers recommend a comprehensive
18 set of treatments that could be applied and identify the cumulative potential benefits.

19

20 This program represents a comprehensive approach to infrastructure management, based on
21 extensive data and engineering-driven analysis and evaluation. It serves as a platform to better
22 integrate a portion of the capital investments we make each year in our electric distribution
23 system. Through grid modernization, we know we are targeting work on the right
24 infrastructure at the right time, and in a priority that allows us to maximize the customer value
25 of every investment made under the program. The failure to fund this program at the planned
26 level for this period will push even more work into wood pole management program and
27 reduce the value of both programs.

28

29 **Distribution Wood Pole Management – 2017: \$9,000,000**

30 Avista has approximately 340 electric feeders with a total circuit length of approximately
31 7,700 miles. This system is composed mainly of overhead electric conductors and associated
32 equipment that is supported by approximately 240,000 wood poles and attached equipment
33 that includes crossarms, transformers, cutouts,¹⁶ insulators and pins,¹⁷ wildlife guards,

¹⁵ The objective in selecting candidate feeders for rebuild is to achieve the greatest overall value for customers based on improved reliability (on that feeder), energy efficiency savings, and avoided expenses for equipment failures.

¹⁶ Cutouts are fuse devices that protect the feeder and equipment in the event of a fault on the line.

¹⁷ The overhead wire or conductor that carries the electric current is attached to insulators that prevent the conductor from faulting, and each insulator is attached to the pole or crossarm with a wooden pin (though new materials are frequently in use today).

1 lightning arresters, guy lines,¹⁸ and pole grounding.¹⁹ Poles, equipment and conductors
 2 comprise over 70% of the Company's electric distribution infrastructure. In managing these
 3 assets, it is the Company's goal to repair or replace aging poles and equipment before they
 4 actually fail, but late enough in their expected life span to capture the full value of the initial
 5 investment and any follow-up investments. The practical way to accomplish this is to
 6 systematically inspect each pole in the system on a regular cycle and to make the investments
 7 needed to replace failed poles or to extend the life of weakened poles so they don't fail before
 8 the next inspection. The central question is what time interval to use for the inspection cycle.²⁰
 9 Generally, more frequent inspections (shorter cycle time) reduce the likelihood that poles and
 10 associated components will fail sometime during the interval between inspections, but they
 11 also cost more because the annual number of poles inspected is greater than with a longer
 12 cycle interval. The optimum interval time can be mathematically determined based on the
 13 characteristics of the wood pole population, the associated operating expenses, and the
 14 likelihood and cost of customer service outages resulting from poles that fail between
 15 inspections. The Company's evaluation of the cycle interval in 2009 pointed to a 20-year cycle
 16 as preferable to both a shorter 10-year interval and a much longer interval.

17
 18 In each 20-year cycle all of the wood poles in our system will have been visually inspected
 19 and repaired, reinforced (stubbed), or replaced as needed. The program has been modified to
 20 more fully utilize the crews performing inspections, by replacing pre-1960's transformers,
 21 identifying inefficiently sized transformers, installing grounds or guy wires where needed, and
 22 ensuring equipment meets current safety standards. In 2012 Avista initiated the Grid
 23 modernization Program which is dovetailed with the Wood Pole Management Program to
 24 make further-optimized use of crews and materials supporting wood pole management. The
 25 failure to fund this program at the planned levels for this period will result in more risk of
 26 customer outages, and higher expenses and capital costs due to unplanned maintenance and
 27 repair.
 28

29 **Q. Does the Company's five-year investment plan fully fund these programs?**

30 A. No. The Company's Distribution Grid Modernization Program is optimized on
 31 a 60 year cycle, however, it has not been funded at a level to achieve that cycle time, in order
 32 to accommodate other priority investment needs in Avista's electric distribution system. The
 33 level of funding for this project that the Company has included in the 2017 – 2021 timeframe

¹⁸ Wire support attached at the upper part of the pole and anchored into the ground diagonally to counteract tension on the line as needed to keep the pole stable, upright and plumb.

¹⁹ To ensure the pole and equipment is electrically grounded to ensure any fault goes safely to ground.

²⁰ The inspection cycle interval is the period of time within which every pole in the system will have been inspected and treated as needed.

1 provides for an 84 year cycle; still longer than the optimized cycle. The effect of the longer
2 than 60-year cycle interval is that the wood pole management program will have to complete
3 more capital work every year (work that would have been done under grid modernization).
4 Both the grid modernization and wood pole management programs will operate at a lower
5 efficiency, and a portion of the added customer value delivered by the grid modernization
6 program will be lost.

7
8 **End of Period Rate Base Study and Rate Year Projects:**

9 **Asset Condition:**

10 **Q. Please list and explain each capital project or program grouped under the**
11 **Asset Condition Investment Driver as it relates to the End of Period Rate Base Study**
12 **and Rate Year Projects.**

13 A. As already noted earlier in my testimony, assets of every type degrade with
14 age, usage and other factors, and must be replaced or substantially rebuilt at some point in
15 order to ensure we continue to deliver reliable and cost effective service. Projects or programs
16 in this driver are defined as: *“investments to replace assets based on established asset*
17 *management principles and systematic programs adopted by the Company, which are*
18 *designed to optimize the overall lifecycle value of the investment for our customers.”*²¹

19 These programs include Distribution Wood Pole Management, PCB Transformer
20 Replacement, Underground Cable Replacement, and Distribution Grid modernization.
21 Collectively, the Company relies on these primary programs for making systematic

²¹ Exh. SLM – 3, page 30.

1 investments in our distribution plant, which allows us to cost-effectively maintain a safe and
 2 highly reliable system that meets the expectations of our customers. These programs were
 3 developed with support from the Company's asset management group, which has continued
 4 to evaluate them as needed through the course of implementation. The most recently
 5 completed Electric Distribution System 2016 Asset Management Plan report has been
 6 included as Exh. HLR-3. Below are descriptions of each of these asset programs:

7 **Distribution Grid Modernization - 2018: \$13,929,000; 2019: \$14,333,000; 2020:**
 8 **\$12,942,000; 2021: \$12,942,000**

9 Please see the Distribution Grid Modernization description above under the Traditional Pro
 10 Forma Study projects.

11
 12 **Distribution Transformer Change-Out Program - 2017: \$3,000,000; 2018: \$1,200,000;**
 13 **2019: \$1,200,000; 2020: \$1,200,000**

14 Between 1929 and 1981, a family of synthetic organic compounds known as Polychlorinated
 15 Biphenyls (PCBs) were commonly used in the oil that fills electrical transformers due to their
 16 high dielectric strength²² and resistance to fire. Studies conducted in the 1960s and 70s
 17 revealed, however, that these compounds are also toxic, carcinogenic and highly resistant to
 18 biodegradation in the environment. Their production was banned in the United States in
 19 1979.²³ As a result of this elevated concern, Avista began to formally analyze alternatives to
 20 deal with its distribution transformers containing PCBs.

21
 22 Under the current plan all transformers with PCB concentrations exceeding 1 ppm should be
 23 removed from our system by year 2019. In year 2020 and beyond, the remainder of the pre-
 24 1981 transformers in our system will be targeted for removal as part of the wood pole
 25 management and grid modernization programs.

26
 27 **Distribution Wood Pole Management - 2018: \$9,500,000; 2019: \$9,500,000; 2020:**
 28 **\$9,000,000; 2021: \$12,000,000**

29 Please see the Distribution Wood Pole Management description above under the Traditional
 30 Pro Forma Study projects.

31
 32 **Primary URD Cable Replacement - 2017: \$503,000; 2018: \$1,000,000; 2019: \$1,000,000;**
 33 **2020: \$1,000,000; 2021: \$1,000,000**

34 Underground residential district cable (underground cable or URD) has been used by the
 35 utility industry since the 1930s, though Avista did not begin installing the cable until the late

²² Dielectric strength refers to the ability of a material to resist carrying an electrical current, which is a measure of its potential to insulate against electric short circuit or fault.

²³ "PCBs Questions & Answers," United States Environmental Protection Agency, <https://www3.epa.gov/region9/pcbs/faq.html>.

1 1960's. During the 1990s it became apparent that the cable manufactured from the 1960s into
 2 the 1980s had numerous problems. These included the lack of adequate insulation resulting in
 3 numerous faults, the process of splicing the cable caused weaknesses and premature failure,
 4 and excessive corrosion on the neutral strands caused voltage levels to drop unexpectedly or
 5 the cable to entirely fail.²⁴
 6

7 In 2009 Avista's asset management group analyzed options for accelerating the replacement
 8 schedule from 10 years to a four year program. The analysis, which was based on savings
 9 from avoiding unplanned outages, estimated that the four-year program would save customers
 10 approximately \$7.3 million in capital installation, expenses, and failure consequences.²⁵ With
 11 the majority of the known vintage cable replaced by 2013, the program was ramped down to
 12 an annual investment of approximately one million dollars, which provides for the removal
 13 and replacement of this vintage cable as we find it on the system (usually through responding
 14 to an underground fault). The failure to fund this program at the planned levels for this period
 15 will result in more customer outages, and higher expenses and capital costs due to unplanned
 16 maintenance and repair.
 17

18 **Customer Requested:**

19 **Q. Please list and describe the infrastructure programs and projects for**
 20 **electric distribution that are assigned to the 'Customer Requested' investment driver?**

21 A. This classification of infrastructure investments is defined as: "*customer*
 22 *requests for new service connections, line extensions, transmission interconnections, or*
 23 *system reinforcements to serve a customer.*"²⁶ The related capital construction activities are
 24 typically limited to the electric distribution system, but may extend to substations and
 25 dedicated high voltage transmission lines. The capital investment required to fulfill customer
 26 requests for electric service represents 31.4% of the total distribution infrastructure spending
 27 planned in the five-year period.

28 **New Revenue – Growth - 2017: \$23,775,000; 2018: \$23,249,000; 2019: \$22,668,000; 2020:**
 29 **\$23,055,000; 2021: \$23,123,000**

²⁴ Medek, James D. P.E., "Early Underground Residential Distribution (URD) in the Midwest," 2002, https://www.pesicc.org/iccwebsite/subcommittees/E/E04/2002/fall02_medek.pdf

²⁵ Savings are based on the outages forecast to occur without the replacement program, minus the actual outages, multiplied by the average cost of responding to an average cable outage.

²⁶ Exh. SLM-3, page 18.

1 These investments include the costs for establishing a new service connection to a customer
 2 when requested, and which are provided for in the line extension allowance granted under our
 3 tariff. This work can be as simple as setting a new area light or running a new secondary
 4 service from an existing transformer, to the more involved instance of extending a primary
 5 distribution line to the customer, setting the transformer, running the service line, and setting
 6 the new meter. System reinforcements that are required to serve a solitary or a small group of
 7 customers, generally involve substation and feeder upgrades that are required to meet new
 8 capacity requirements. Because Avista is obligated to provide electric service or service
 9 enhancements when requested, we allocate the needed capital to this program based on the
 10 number of requests we expect to receive each year, and not through a competitive
 11 prioritization process. For this period, Avista expects to connect on average about 6,000 new
 12 electric customers each year. Avista is required by its service tariffs to make the investments
 13 necessary to connect customers when requested.
 14

15 **Failed Plant and Operations:**

16 **Q. Please describe the Failed Plant and Operations Investment Driver?**

17 A. The Failed Plant and Operations investment driver is defined as:

18 *“requirements to replace assets that have failed and which must be replaced in order to*
 19 *provide continuity and adequacy of service to our customers (e.g. capital repair of storm-*
 20 *damaged facilities). Also includes investments in natural gas and electric infrastructure that*
 21 *are performed by Avista’s operations staff.”²⁷* Avista must respond to various types of

22 equipment failures on our electric distribution system each year that result from natural forces
 23 such as wildfire, third-party damage caused by others, or the unanticipated failure of an asset.

24 In addition to replacing failed plant, investments under this program covers work performed
 25 through Avista’s ongoing capital work performed by operations’ staff.

26 **Distribution Minor Rebuild - 2017: \$9,105,000; 2018: \$8,900,000; 2019: \$8,900,000;**
 27 **2020: \$8,900,000; 2021: \$8,900,000**

28 A major portion of the investments made under this program are driven by faults or damage
 29 to our system that result in service outages for our customers. The vast majority of the outages
 30 our customers experience each year occur on our overhead distribution system. In 2016, there
 31 were 7,083 outages on the distribution grid compared to only 53 related to substations and 61

²⁷ Exh. SLM – 3, page 35

1 associated with transmission lines. The majority of these outages are related to weather (e.g.
 2 lightning, wind, rain and snow), downed trees, animals (e.g. squirrels and birds), and
 3 equipment failure. In addition to replacing assets that have failed, Avista's operations staff
 4 performs a wide range of limited capital infrastructure work that does not rise to the level of
 5 a project or program. This work includes the need to reconfigure, replace, repair, or upgrade
 6 distribution facilities that arise for a variety of reasons. Because the Company must promptly
 7 replace failed infrastructure in order to ensure the continuity of service to our customers,
 8 Avista allocates funding to this program based on the evaluation of historical trends, and not
 9 through a competitive prioritization process. If Avista did not make the required investments
 10 under this program, we would be unable to repair and / or replace infrastructure that is
 11 damaged or fails, and would therefore fail to provide service continuity to our customers.

12
 13 **Meter Minor Blanket - 2017: \$505,000; 2018: \$300,000; 2019 \$300,000; 2020: \$300,000;**
 14 **2021: \$300,000**

15 The Company has over 370,000 electric meters in service for measuring the kWh usage for
 16 our residential, commercial and industrial customers. Each year, in response to our customers'
 17 requests for a meter check, the Company's detection of billing anomalies, or the identification
 18 of failing meters through our annual meter testing program, Avista must promptly replace or
 19 repair failed meters to ensure our customers are accurately billed. The investments for meter
 20 replacements and repairs are included under this failed plant program.

21
 22 **Spokane Electric Network - 2017: \$2,605,000; 2018: \$2,300,000; 2019: \$2,300,000; 2020:**
 23 **\$2,300,000; 2021: \$2,300,000**

24 Avista operates an underground electric network in the core business district of downtown
 25 Spokane. This underground system includes cables encased in concrete reinforced duct lines
 26 and major equipment such as underground transformers that are located in concrete vaults
 27 beneath the city streets and sidewalks. Most mid-size to large cities rely on such networks,
 28 including for example, the cities of Seattle, Portland, and Tacoma. Avista's network is
 29 relatively small, consisting of 100,000 feet of primary cable and 125,000 feet of secondary
 30 cable interconnected with 170 transformers. The Spokane network system dates back to the
 31 early 1900s and some of the vaults still in service were constructed as early as 1910. Capital
 32 investments made under this program are predominantly to replace failed vault structures,
 33 transformers, switches, and cable. If Avista did not make the required investments under this
 34 program, we would be unable to repair and / or replace infrastructure that is damaged or fails,
 35 and would therefore fail to provide service continuity to our customers.

36
 37 **Mandatory and Compliance:**

38 **Q. Please describe the distribution investments you have grouped under the**
 39 **Mandatory and Compliance Investment Driver?**

1 A. Avista has defined this driver as: “*investments required to comply with laws,*
2 *rules, and contracts that are external to the Company (e.g. State and Federal laws, Settlement*
3 *Agreements, FERC, NERC, and FCC rules, and Commission Orders, and etc.).*”²⁸

4 **Electric Replacement/Relocation - 2017: \$2,600,000; 2018: \$2,700,000; 2019: \$2,800,000;**
5 **2020: \$3,000,000; 2021: \$3,100,000**

6 Each year Avista is required to respond to the projects of municipalities, counties and state-
7 level agencies to rebuild or realign roads, streets and highways. When these projects impact
8 our distribution facilities located in public rights-of-way, the Company is required to remove
9 and rebuild them in the clear zone of the new roadway, or to place them on a new purchased
10 private easement. This work must be performed at the Company’s expense, and while Avista
11 may have some latitude to negotiate the timing of the construction, it has no choice with regard
12 to removing and relocating its infrastructure and paying all of the associated costs.²⁹ If Avista
13 failed to make these investments we would be in violation of our operating franchises,
14 municipal codes, state laws and regulations, and would be subject to litigation and financial
15 and other penalties.

16
17 **Environmental Compliance - 2017: \$350,000; 2018: \$350,000; 2019: \$350,000; 2020:**
18 **\$350,000; 2021: \$350,000**

19 These required investments include implementation of U.S. Forest Service Special Use
20 Permits, waste oil disposal including PCB transformers, and environmental compliance with
21 storm water management, water quality protection, property cleanup and related issues. If
22 Avista failed to make these investments we would be in violation of mandated environmental
23 compliance regulations, and would be subject to litigation and financial and other penalties.

24
25 **Franchising for WSDOT - 2017: \$1,594,000; 2018: \$200,000; 2019: \$200,000; 2020:**
26 **\$200,000; 2021: \$200,000**

27 As in electric replacement / relocation above, Avista works closely with the Washington
28 Department of Transportation (WSDOT) to renew crossing and encroachment permits. This
29 work requires the Company realign or modify existing infrastructure to comply with state
30 clear zone, conductor clearance, and other regulations regarding the location of poles, guy
31 wires, pad mounted equipment, and overhead conductors. If Avista failed to make these
32 investments we would be in violation of mandated environmental compliance regulations, and
33 would be subject to litigation and financial and other penalties.

²⁸ Exh. SLM-3, page 23.

²⁹ This requirement is based on Avista’s facilities being in the public right-of-way established for this purpose. In cases when the Company’s facilities are located in private rights-of-way, while still required to be relocated, the move is at the expense of the governing body responsible for the roadway project.

1 **Q. How are these investments prioritized within the business units?**

2 A. Because Avista is obligated to remove and replace its facilities when requested,
3 and to meet environmental standards, the annual funding level is established based on
4 historical trends and any known specific projects.

5
6 **Performance and Capacity:**

7 **Q. What planned distribution investments have you grouped under the**
8 **Performance & Capacity Investment Driver?**

9 A. When the load-carrying capacity of electric facilities is exceeded for any
10 extended period of time it can stress and damage equipment, cause system instability, and lead
11 to equipment failures that result in customer outages. The investments required to resolve
12 these issues are defined as: *“a range of investments that address the capability of assets to*
13 *meet defined performance standards, typically developed by the Company, or to maintain or*
14 *enhance the performance level of assets based on need or financial analysis.”³⁰*

15 **LED Change Out Program - 2017: \$2,900,000; 2018: \$2,000,000; 2019: \$2,320,000 2020:**
16 **\$2,000,000**

17 LED lighting technology emerged as viable alternative to conventional and fluorescent
18 lighting around 2009, and by year 2012 over 14 million units had been installed in the U.S.
19 alone. It is estimated that LEDs will save U.S. consumers and businesses \$20 million per year
20 within a decade, and reduce U.S. CO₂ emissions by up to 100 million metric tons per year.
21 LED bulbs cut electricity use by 85% compared with incandescent bulbs, and 40% compared
22 with fluorescent lighting.³¹ Avista operates approximately 35,000 street lights we have
23 installed for many of our communities and other jurisdictions across our service territory as
24 well as area lights requested and paid for by individual customers. In 2013, in recognition of
25 the superior safety performance of LED lighting, the energy savings potential, Avista
26 evaluated the benefit of converting all our Schedule 042 street lights from High Pressure
27 Sodium (HPS) to LED fixtures. Also, the State of Washington has established a statewide

³⁰ Exh. SLM – 3, page 27.

³¹ “PCBs Questions & Answers,” United States Environmental Protection Agency,
<https://www3.epa.gov/region9/pcbs/faq.html>.

1 grant program, which is administered for the state by Avista, which provides small
 2 communities an offset to their street lighting costs when their systems are converted to LED
 3 lighting. If Avista did not invest in the LED lighting program, we would delay the safety and
 4 security benefits to customers, as well as the savings for energy efficiency and reduced
 5 operating expenses achieved by the program.

6
 7 **Segment Reconductor and FDR Tie Program - 2017: \$6,587,000; 2018: \$4,900,000; 2019:**
 8 **\$5,001,000; 2020: \$5,000,000; 2021: \$5,000,000**

9 The annual investments made under this program represent 7.1% of our planned distribution
 10 investments, and remedy the overloading of electric equipment and cable, as well as the
 11 conductor sag³² that results from overheating of the overhead wire. These instances of system
 12 overloading result from load growth and shifts in load demand that occur over time on the
 13 distribution system. Resolving these overloading issues involves a combination of two
 14 strategies known as “load shifting” and “segment reconductoring.” The strategy of load
 15 shifting extends existing lines on one feeder to an adjacent feeder that has the available
 16 capacity to carry the additional transferred load. Reconductoring involves the removal of the
 17 wire or conductor that is too small in diameter for the current loading and replacing it with
 18 larger conductor that can easily carry the load. Avista considers a range of options that not
 19 only meet the current need to relieve the overloading, but that also provide for the optimization
 20 of the overall distribution system.

21
 22 **Q. In conclusion, please summarize Avista’s investment plan for its electric**
 23 **distribution system.**

24 A. Our investment plans for our electric distribution system have been
 25 thoughtfully developed, thoroughly analyzed and optimized, and adjusted as appropriate to
 26 ensure we deliver cost effective value for our customers. The level of our investments has also
 27 been conservative as we have balanced distribution needs with our overall infrastructure
 28 demands. As an example, we have chosen to fund our grid modernization program at a level
 29 that does not achieve the optimized cycle interval in an effort to manage our overall investment
 30 needs as a part of being attentive to the price impacts to our customers.

³² When the overhead wire (conductor) on a distribution feeder is overloaded, the wire overheats and stretches, and in doing so, sags closer to the ground than designed, which can exceed electric code requirements for safety.

1 **Q. Do you believe that the Company’s investment in distribution**
2 **infrastructure is necessary in the time frame the projects are being completed?**

3 A. Yes, I do.
4

5 **IV. ELECTRIC TRANSMISSION INVESTMENTS**

6 **Q. Please discuss the investment drivers for the Company’s transmission**
7 **projects.**

8 A. Avista must continuously invest in its transmission infrastructure to maintain
9 safe and reliable service for our customers and to meet mandatory federal reliability standards.
10 These investments replace equipment that has reached the end of its useful life meet customer
11 requests for interconnection or service enhancement, repair or replace infrastructure that fails,
12 meet our regulatory compliance requirements, ensure the availability of critical equipment
13 when needed, and enhance the capacity or performance of the system to meet Company
14 standards or serve additional load. In the following testimony I will provide a description of
15 the transmission investments by investment driver category.

16 **Q. Please discuss the Asset Condition driver as it relates to transmission**
17 **investment.**

18 A. Investments in transmission infrastructure related to Asset Condition are “to
19 *replace assets based on established asset management principles and strategies adopted by*
20 *the Company, which are designed to optimize the overall lifecycle value of the investment for*
21 *our customers.*”³³ The Company’s Transmission System Asset Management Plan (Exh.

³³ Exh. SLM – 3, page 30.

1 HLR-5) recommends a 30-year replacement period for transmission assets, which requires an
2 investment of \$21.1 million per year, split \$11.3 million for 115 kV facilities and \$9.8 million
3 for 230 kV facilities. Current spending on the replacement of transmission facilities due to
4 asset condition is just under \$10 million per year, meaning the Company is currently on a
5 funding level track that will require some transmission assets to operate reliably at an age
6 beyond 60 years.

7 **Q. Please discuss the Customer Requested driver as it relates to transmission**
8 **investment.**

9 A. These projects are triggered by “*customer requests for new service*
10 *connections, line extensions, transmission interconnections, or system reinforcements to serve*
11 *a customer.*”³⁴ In some cases the Company must construct a distribution substation with an
12 associated transmission line extension in order to meet the requested new load requirements
13 of an industrial or large commercial customer. Other situations may involve a requested
14 transmission interconnection with a neighboring utility or generation project.

15 **Q. Please discuss the Failed Plant and Operations driver as it relates to**
16 **transmission investment.**

17 A. Transmission investments in this category are primarily the result of storm
18 damage to the Company’s transmission system, including damage caused by major wind
19 events, lightning, fire, and snow and ice.

20 **Q. Please discuss the Mandatory and Compliance Requirements driver as it**
21 **relates to transmission investment.**

³⁴ Exh. SLM – 3, page 18.

1 A. These investments in transmission infrastructure are primarily driven by North
2 American Electric Reliability Corporation (NERC) standards, which are nationwide
3 requirements for utilities to ensure the reliability of the interconnected transmission grid.
4 Compliance with these standards became mandatory under federal law in 2007, and failure to
5 comply may result in monetary penalties of up to \$1 million per day, per infraction. These
6 standards focus mainly on transmission planning, operation, and equipment maintenance. The
7 standards require utilities to plan and operate their systems to avoid customer outages and to
8 prevent adverse impacts to neighboring utility systems arising from the loss of transmission
9 service. Specifically, the transmission system must be designed so that the simultaneous loss
10 of up to two facilities will not impact the interconnected transmission system. Further, the
11 loss of any single facility must not cause any other facility in service to exceed its System
12 Operating Limit (voltage or capacity ratings)³⁵ or cause the interconnected transmission grid
13 to operate outside specified reliability limits (voltage and stability limits). This includes
14 circumstances where transmission facilities suffer an outage event, or are purposefully
15 removed from service for maintenance and construction work. Finally, the transmission
16 operator must determine in advance whether any single outage will result in a violation of a
17 System Operating Limit, and to mitigate for that occurrence in advance, prior to such
18 contingency occurring. This means the system must be designed to automatically adjust to a
19 reliable state or system operators must take proactive action to mitigate the expected impacts
20 of a potential contingency. Such mitigation efforts may include system configuration changes,
21 generation changes, or the controlled removal of firm load from the transmission system. As

³⁵ Facilities refer to transmission lines, sections of lines and transmission equipment in substations.

1 a result, Avista must ensure that its system can be operated reliably during a variety of
2 operational, seasonal and other scenarios.

3 Other federal rules that could require the construction of new transmission facilities
4 include Avista's compliance with its Open Access Transmission Tariff, which can require the
5 Company to construct new facilities at the request of its transmission system customers.

6 **Q. Would you please describe the recent change in the NERC transmission**
7 **planning standards and explain the possible impact on the Company's investments in**
8 **transmission and other infrastructure?**

9 A. Yes. In 2013, FERC mandated utility compliance with Requirement R2 of the
10 NERC transmission planning standard TPL-001-4, effective January 1, 2016. This
11 requirement underscores FERC's intent that disconnecting customers not directly connected
12 to a transmission facility that experiences a planned or unplanned outage cannot be generally
13 relied upon to ensure the planned reliability of the transmission system. The Company is now
14 required to make transmission investments to meet this standard or, if it is unable to do so due
15 to circumstances beyond its control, must initiate a broad public stakeholder process
16 explaining how it would rely on the option of disconnecting customers to meet transmission
17 reliability, which plans would be subject to Commission review. The Company believes that
18 relying upon disconnecting customers to meet reliability standards does not meet our customer
19 service or reliability objectives. Consequently, the Company is planning for significant new
20 transmission investments over the next several years that will allow it to comply with the
21 transmission planning standard. These investments will likely trigger the need to re-prioritize
22 other infrastructure projects during this planning period, resulting in the possible deferral of
23 other priority investment needs.

1 **Q. Please discuss the Performance and Capacity driver as it relates to**
2 **transmission investment.**

3 A. Just as with distribution facilities, transmission investments driven by
4 Performance and Capacity are “*a range of investments that address the capability of assets to*
5 *meet defined performance standards, typically developed by the Company, or to maintain or*
6 *enhance the performance level of assets based on need or financial analysis.*”³⁶ When the
7 load-carrying capacity of electric facilities is exceeded for any extended period of time it can
8 stress and damage equipment, and lead to equipment failures that result in customer outages.
9 Furthermore, in the case of substation and transmission facilities, the Company must plan for
10 sufficient capacity in the system to accommodate a planned or forced outage to any one system
11 component without customers having to experience an extensive outage. For example, to take
12 a substation out of service for necessary maintenance, the Company must plan for sufficient
13 capacity in its neighboring substations so that all lines serving customers from the substation
14 to be taken out of service can be transferred to neighboring substations before the maintenance
15 outage occurs. Other investments, like Supervisory Control and Data Acquisition (SCADA)
16 systems, enable those who operate the Company’s transmission system to effectively monitor
17 and control the system to ensure proper system performance.

18 **Q. How do Avista’s Transmission Planning, System Operations and**
19 **Engineering business units evaluate and prioritize proposed transmission projects**
20 **before they are submitted to the Company’s capital planning group?**

³⁶ Exh. SLM – 3, page 27.

1 A. These transmission projects are initiated through planning studies, engineering
2 and asset management analyses, and scheduled upgrades or replacements identified in our
3 operations districts. Projects developed through transmission planning studies undergo
4 internal review by multiple stakeholders who help ensure all system needs and alternatives
5 have been identified and addressed.

6 In addition to this traditional review, the Company recently implemented a new formal
7 review process referred to as the “Engineering Roundtable.” The objective of this process is
8 to provide added structure and increased transparency of the review process for both internal
9 and external stakeholders, for development of *all* proposed transmission projects whether
10 large specific projects or smaller, program-related proposals. Through this review all
11 substation and transmission projects are reviewed, evaluated, returned for additional analysis
12 as needed, and finally prioritized.

13 Representatives from ten business units participate in this process, which include
14 transmission planning, distribution planning, transmission design, substation design, system
15 protection, distribution design, system operations, asset management, communications
16 engineering, and transmission services groups. Each business unit proposing a project is
17 required to explain the problem that needs to be addressed, the alternatives considered, and to
18 provide the justification for the approach recommended. During the review, the potential
19 benefits of any cross-business unit synergies that could better optimize project benefits and
20 scope are also identified and evaluated.

21 Examples of proposed projects that have been revised or deferred in this review
22 process include the Noxon 230kV Switching Station Rebuild and the Devil’s Gap-Lind 115kV
23 Rebuild. While the Noxon Switchyard remains in need of a complete rebuild, members of the

1 engineering roundtable determined that the time required for the complete rebuild of the
2 station (which includes significant transmission line relocations in coordination with the
3 Bonneville Power Administration) was not appropriate in light of the immediate safety and
4 compliance need to replace the 230kV circuit breakers in the existing station. Portions of the
5 Devil's Gap-Lind 115kV Transmission Line needed to be rebuilt to meet requirements under
6 the 2012 NERC Alert. This line is also among the oldest of Avista's transmission facilities
7 (95th percentile in age). After reviewing which transmission structures required replacement
8 under the NERC alert and which structures needed to be replaced under the Company's wood
9 pole management program, the roundtable determined that those line sections with 80% or
10 more of its structures needing replacement would be entirely rebuilt. These beneficial cross-
11 departmental reviews and analyses are typical of the engineering roundtable process.

12 **Q. Please list the transmission infrastructure investments planned by the**
13 **Company and briefly describe each project by investment driver.**

14 A. The Company's planned transmission investments are listed on a system basis
15 in Table 2, below, organized by investment driver. These projects are briefly described in the
16 following Table.

Table No. 2

Transmission Capital Projects (System) In \$(000's)					
Business Case Name	2017	2018	2019	2020	2021
Traditional Pro Forma Study Projects:					
Asset Condition					
Substation - Station Rebuilds	\$ 17,524				
End of Period Rate Base Study and Rate Year Projects:					
Asset Condition					
SCADA - SOO & BUCC	1,270	920	1,013	920	920
Substation - Station Rebuilds		7,867	15,800	4,185	15,385
Transmission Minor Rebuild	5,132	1,843	1,908	1,970	2,015
Transmission Major Rebuild - Asset Condition	9,536	12,025	11,000	23,550	24,500
Customer Requested					
Growth - Hallet and White	1,458	1,409			
Failed Plant and Operations					
Electric Storms	3,183	3,278	3,377	3,169	3,200
Mandatory and Compliance					
Colstrip Transmission	325	449	391	365	442
Environmental Compliance	72	50	50	50	50
Garden Springs 230/115kV Station Integration	56		725	8,250	
Noxon Switchyard Rebuild	2,504				21,600
S Region Voltage Control	5,733				
Saddle Mountain 230/115kV Station Integration		1,500	14,500		
Spokane Valley Transmission Reinforcement	374	7,750			
Transmission - NERC Low Priority Mitigation	2,014	1,500	1,500	1,500	
Transmission - NERC Medium Priority Mitigation	2,000				
Transmission Construction - Compliance	15,309	13,159	13,000		
Tribal Permits and Settlements	621	250	150	250	250
Westside 230/115kV Station Rebuild	5,566				
Performance and Capacity					
SCADA Build-Out Program		2,500	6,000	7,670	7,670
Substation - Capital Spares	4,204	5,065	4,025	4,025	4,025
Substation - New Distribution Stations	2,424	850	6,375		5,000
	\$ 61,779	\$ 60,416	\$ 79,814	\$ 55,904	\$ 85,058
Total Planned Transmission Capital Projects	\$ 79,303	\$ 60,416	\$ 79,814	\$ 55,904	\$ 85,058

1 **Traditional Pro Forma Study Projects:**

2
3 **Asset Condition**

4
5 **Substation –Station Rebuilds - 2017: \$17, 524**

6 This program replaces and/or rebuilds existing substations as they reach the end of their useful
7 lives or where installed equipment that fails or is being replaced for capacity needs cannot be
8 accommodated within the physical constraints of the small, older stations. Included are wood
9 substation rebuilds as well as upgrading stations to current design and construction standards.
10 The failure to timely replace and rebuild end of life equipment in these substations will expose
11 the Company to the risk of more frequent and long duration outages that have a significant
12 impact on our customers. Examples of substation rebuilds to be completed under this program
13 in the next five years are Kamiah (wood substation), Ford (end of service life), 9th & Central,
14 Priest River and Colville.

15
16 **End of Period Rate Base Study and Rate Year Projects:**

17
18 **Asset Condition**

19
20 **SCADA – SOO & BUCC - 2017: \$ 1,270,000; 2018: \$920,000; 2019: \$1,013,000; 2020:**
21 **\$920,000; 2021: \$920,000**

22 This program replaces and/or upgrades existing electric and natural gas control center (System
23 Operations Center and Backup Control Center) telecommunications and computing systems
24 as they reach the end of their useful lives, require increased capacity, or cannot accommodate
25 necessary equipment upgrades due to existing constraints. Included are hardware, software,
26 and operating system upgrades, as well as deployment of capabilities to meet new operational
27 standards and requirements. Some system upgrades are initiated by other requirements,
28 including NERC reliability standards, growth, and new projects (e.g. Smart Grid). Examples
29 of upgrades to be completed under this program are Critical Infrastructure Protection version
30 5 (NERC standards requirement), Gas Control Room Management (PHMSA requirement),
31 PEAK Reliability Coordinator Advanced Applications, and Technology Refresh (network and
32 storage). The failure to make these investments in the timeframe planned will result in the
33 Company losing information connectivity with its transmission system and to be in violation
34 of NERC transmission planning standards, and subject to financial and other penalties.

35
36 **Substation –Station Rebuilds - 2018: \$7,867,000; 2019: \$15,800,000; 2020: \$4,185,000;**
37 **2021: \$15,385,000**

38 Please see the description for Substation –Station Rebuilds under the Traditional Pro Forma
39 Study.

40
41 **Transmission Minor Rebuild - 2017: \$5,132,000; 2018: \$1,843,000; 2019: \$1,908,000;**
42 **2020: \$1,970,000; 2021: \$2,015,000**

43 This project covers transmission structure (ER 2057) and air switch (ER 2254) replacements
44 based upon the results of the Company's annual Wood Pole and Aerial Patrol inspection
45 programs, and field operations. Both the Wood Pole and Aerial Patrol inspection programs

1 are undertaken to maintain compliance with NERC Standard FAC-501-WECC-1. Failing to
 2 make the necessary replacements identified by the Company’s inspection programs increases
 3 the risk of transmission system outages and the potential to ignite fires in dry areas. Air switch
 4 replacements are made based either on condition, capacity, or functionality issues.
 5 Prioritization of installations and replacements are made from information provided by
 6 System Operations, Substation Engineering or the Company’s regional operations centers.
 7 Failing to make the necessary replacements identified by the Company’s inspection programs
 8 risks placing Avista in violation of NERC standards, and will increase the risk of transmission
 9 system outages and the potential to ignite fires in dry areas.

10
 11 **Transmission Major Rebuild - Asset Condition – 2017: \$9,536,000; 2018: \$12,025,000;**
 12 **2019: \$11,000,000; 2020: \$23,550,000; 2021: \$24,500,000**

13 Projects in this program rebuild existing transmission lines based on overall asset condition
 14 (at the end of their useful life). The failure to timely replace aging transmission infrastructure
 15 on planned basis will subject our customers to the increased risk of service outages and
 16 increased restoration costs as we become less able to continue providing our current level of
 17 reliability. In addition to customer outages, the added risk of failure also impacts the economic
 18 dispatch of our Company’s generation resources and increases the risk of fire in dry areas.
 19 Finally, the failure to properly invest builds a “bow-wave” of needed investments to the future,
 20 which makes it more difficult to fund these projects in addition to our already-planned priority
 21 infrastructure needs. Projects include: ER 2550 – Burke-Thompson A&B 115kV
 22 Transmission Line rebuild; ER 2604 – Lind-Warden 115kV Transmission Line rebuild; ER
 23 2577 – Benewah-Moscow 230kV Transmission Line structure replacement; ER 2597 –
 24 Cabinet-Noxon 230kV Transmission Line rebuild; and ER 2596 – Lolo-Oxbow 230kV
 25 Transmission Line rebuild.

26
 27 **Customer Requested**

28
 29 **Growth - Hallett and White Substation - 2017: \$1,458,000; 2018: \$1,409,000**

30 An existing large retail customer is expecting to double its load over the next 7-10 years
 31 beginning in 2018. Additionally, a wholesale network transmission customer (Inland Power
 32 & Light) has requested an interconnection at the Hallett & White Substation. These requests
 33 together require an increase in substation transformer capacity and additional feeders. This
 34 project will rebuild the Hallett & White 115/13kV Substation with two 30MVA transformers
 35 and six feeder bays, with one feeder dedicated to Inland Power & Light, two feeders dedicated
 36 to the Company’s large retail customer, and the remaining feeders available to provide service
 37 to the Company’s local distribution system. Failure to construct this project will result in the
 38 inability to serve the requested load of the large retail customer, and the failure of the
 39 Company to provide the required interconnection and low-voltage wheeling service under
 40 FERC jurisdiction for its wholesale transmission customer.

1 **Failed Plant and Operations Projects:**

2
3 **Electric Storms - 2017: \$3,183,000; 2018: \$3,278,000; 2019: \$3,377,000; 2020:**
4 **\$3,169,000; 2021: \$3,200,000**

5 This ongoing program provides for the timely restoration of the Company's transmission,
6 substation and distribution facilities into serviceable condition during or following major
7 weather-related or other natural events including high winds, heavy ice and snow loads,
8 lightning storms, flooding and wildfires.

9
10 **Mandatory and Compliance Investments**

11
12 **Colstrip Transmission - 2017: \$325,000; 2018: \$449,000; 2019: \$391,000; 2020: \$365,000;**
13 **2021: \$442,000**

14 As a joint owner of the Colstrip Transmission System, Avista is obligated to pay its
15 commensurate ownership share of all capital improvements. NorthWestern Energy, the
16 designated Transmission Operator of the Colstrip Transmission System under the Colstrip
17 Transmission Agreement, implements the capital program for purposes of maintaining
18 reliable operation and complying with applicable reliability standards for the jointly owned
19 facilities. Avista's failure to pay its share of these investments would place us in violation of
20 the ownership agreement and subject us to the legal recourse provided for in the agreement.
21 The Company determined after the Rate Period Studies were completed for this case, that
22 there are amounts that will be transferred to plant in 2020 for this project. The Company will
23 update these transfer to plant amounts during this case.

24
25 **Environmental Compliance - 2017: \$ 72,000; 2018: \$50,000; 2019: \$50,000; 2020:**
26 **\$50,000; 2021: \$50,000**

27 This project covers the implementation of required Forest Service Special Use Permits (SUP),
28 Waste Oil Disposal, including polychlorinated biphenyls (PCBs), and Environmental
29 Compliance requirements related to storm water management, water quality protection,
30 property cleanup and related issues. The failure to make these investments would place the
31 Company in violation of mandatory environmental compliance requirements and the federal
32 and tribal permits that grant us authority to use lands for transmission facilities.

33
34 **Garden Springs 230/115kV Substation - 2017: \$56,000; 2019: \$725,000; 2020: \$8,250,000**

35 Due to a lack of redundancy and capacity with the existing system, the west Spokane area is
36 unable to meet the applicable NERC transmission planning standards. The project consists of
37 a new 230kV point of interconnection with BPA at a new station to be constructed on the
38 Coulee-Westside 230kV Line and the Garden Springs 230/115kV Substation. The project
39 will mitigate the identified system deficiencies and provide additional transformation capacity
40 in the area. If this project, or a less-than-optimum alternative project that allows us to meet
41 the standard, is not constructed in the timeframe planned, then the Company will be in
42 violation of NERC transmission planning standards and will be subject to the associated
43 penalties. In addition to violating the planning standard, Avista will also risk having to shed
44 load (instantaneous disconnecting of customers from the system) to maintain compliance with
45 NERC transmission operating standards in the long-range planning horizon. The Company's

1 Engineering Roundtable evaluation and prioritization process has deferred the implementation
2 of the 230kV portion of this project, pending completion of the Westside 230/115kV
3 Substation rebuild project, in an effort to balance our overall investment demands, and is
4 considering other possible alternatives to avoid any NERC transmission planning standard
5 violations.
6

7 **Noxon Switchyard Rebuild - 2017: \$2,504,000; 2021: \$21,600,000**

8 Today, Avista's Noxon Rapids 230kV Switching Station is subject to a potential fault current
9 of approximately 14,000 amps, which exceeds the 12,500 amp capability of six 230kV circuit
10 breakers in the station. This potential is not only an immediate safety issue, but it also exposes
11 the Company to a violation of NERC standards. Additionally, the existing station is at the
12 end of its useful life based on age and condition of the equipment in the station. The existing
13 bus has suffered a number of failures and is now configured as a single bus with a bus tie
14 breaker separating the East and West buses. The station is the point of integration for the
15 Noxon Rapids Hydroelectric development as well as a principle point of interconnection
16 between Avista and BPA, providing a key point of integration for the Western Montana Hydro
17 Complex and the Company's interconnection with NorthWestern Energy in Montana. The
18 current bus configuration requires Avista to curtail its own hydro generation for unplanned
19 outages of substation equipment to complete work in the station. The reconstructed Noxon
20 Rapids 230kV Switching Station will have a double-breaker double-bus configuration to
21 facilitate required maintenance activities without impacting local generation levels or transfer
22 loads to or from Montana. The Company's Engineering Roundtable process has resulted in
23 the deferral of the broader station rebuild project and the immediate replacement of the over-
24 dutied circuit breakers. This potential is not only an immediate safety issue, but our failure to
25 make the investments needed to meet this remedy this issue will result in the Company having
26 to curtail its own hydroelectric generation and further exposes the Company to a violation of
27 mandatory NERC planning standards.
28

29 **South Region Transmission Voltage Control - 2017: \$5,733,000**

30 Avista's south region 230kV system, primarily in the Lewiston-Clarkston area, experiences
31 excessively high voltage during even light load periods, where voltage exceeds equipment
32 ratings over 35% of the time. Operation of equipment outside of manufacturer's ratings
33 introduces safety risks to Company operations and employees, and it increases the possibility
34 of equipment failure and associated large scale outages. If the Company does not implement
35 this project in the timeframe planned, then we may be forced to remove our 230kV lines from
36 service (which is not possible to do) in order to maintain compliance with NERC transmission
37 operating standards. This project includes the installation of two 50MVar shunt reactors on
38 the 230kV bus at North Lewiston. With automatic control, overvoltages can be reduced, if not
39 eliminated, on the 230kV buses at Dry Creek, Lolo, North Lewiston, Moscow and Shawnee.
40

41 **Saddle Mountain Substation and Wind Project Integration - 2018: \$1,500,000; 2019:
42 \$14,500,000**

43 This project is the result of a joint regional transmission planning study team under
44 ColumbiaGrid and resolves a number of NERC transmission planning standard violations in
45 the Grant County PUD transmission system that are exacerbated by the Company's load in

1 the Othello area. Apart from the Grant County PUD system, the Company's Othello area load
2 is supported by only a single 115kV transmission line connection to the Bonneville Power
3 Administration. If Avista does not complete this project in the timeframe planned, then the
4 Company will be subject to possible litigation before the FERC for failing to timely complete
5 a project that has been specified by the sub-regional transmission planning process under the
6 Company's Open Access Transmission Tariff (OATT). The 230kV portion of the Saddle
7 Mountain 230/115kV Substation is also required to integrate a proposed 126MW wind
8 generation project in the Othello area.

9
10 **Spokane Valley Transmission Reinforcement - 2017: \$374,000; 2018: \$7,750,000**

11 Portions of the Spokane Valley Transmission Reinforcement Project already completed
12 include construction of the Opportunity Substation and Irvin-Millwood 115kV Transmission
13 Line. Currently planned projects include rebuilding the Beacon-Boulder #2 115kV
14 Transmission Line and construction of the Irvin 115kV Switching Station. This project must
15 be completed to mitigate our currently-existing failure to meet NERC transmission planning
16 standards, and to avoid future transmission system reliability issues in the Spokane Valley.

17
18 **Transmission – NERC Low Priority Mitigation - 2017: \$2,014,000; 2018: \$1,500,000;**
19 **2019: \$1,500,000; 2020: \$1,500,000**

20 This program was initiated in response to NERC's October 7, 2010 NERC Alert
21 Recommendation to the Industry, titled "Consideration of Actual Field Conditions in
22 Determination of Facility Ratings." It addresses mitigation required on Avista's "Low Risk"
23 115kV transmission lines, and brings these lines into compliance with National Electric Safety
24 Code (NESC) minimum clearance values. These safety code requirements have been adopted
25 into the State of Washington's Administrative Code (WAC 296-46B-010). This program
26 reconfigures insulator attachments, rebuilds existing transmission line structures, or removes
27 earth from beneath transmission lines to mitigate ratings/sag discrepancies found between
28 facility designs and actual field conditions. If the Company were to fail to make these
29 investments we would fail to meet the NERC-required facility ratings for the safe and reliable
30 operation of these lines.

31
32 **Transmission – NERC Medium Priority Mitigation - 2017: \$2,000,000**

33 This program was initiated in response to NERC's October 7, 2010 NERC Alert
34 Recommendation to the Industry, titled "Consideration of Actual Field Conditions in
35 Determination of Facility Ratings." It addresses mitigation required on Avista's "Medium
36 Risk" 230kV and 115kV transmission lines, and brings these lines into compliance with
37 National Electric Safety Code (NESC) minimum clearance values. These safety code
38 requirements have been adopted into the State of Washington's Administrative Code (WAC
39 296-46B-010). This program reconfigures insulator attachments, rebuilds existing
40 transmission line structures, or removes earth from beneath transmission lines to mitigate
41 ratings/sag discrepancies found between facility designs and actual field conditions. If the
42 Company were to fail to make these investments we would fail to meet the NERC-required
43 facility ratings for the safe and reliable operation of these lines.

1 **Transmission Construction – Compliance - 2017: \$15,309,000; 2018: \$13,159,000; 2019:**
 2 **\$13,000,000**

3 This program reconstructs and rebuilds existing transmission lines to maintain compliance
 4 with NERC transmission planning standards. Investments mitigate NERC transmission
 5 planning standard (TPL-001-4) deficiencies that have already been identified for both our
 6 current system and for the Near Term transmission planning horizon (1-5 years). Failure to
 7 make these planned investments will result in our failure to comply with mandatory NERC
 8 standards. Projects include: ER 2557 – 9th & Central-Sunset 115kV Transmission Line
 9 reconductor and rebuild; ER 2576 – Addy-Devils Gap 115kV Transmission Line reconductor
 10 and rebuild; ER 2457 – Benton-Othello 115kV Transmission Line reconductor and rebuild;
 11 ER 2556 – CDA-Pine Creek 115kV Transmission Line reconductor and rebuild; ER 2564 –
 12 Devils Gap-Lind 115kV Transmission Line reconductor and rebuild; and ER 2310 West
 13 Plains transmission reinforcement. Required construction on ER 2578, the Hatwai-Lolo #2
 14 230kV Transmission Line has been deferred by the Company’s Engineering Roundtable to
 15 accommodate the other priority investment demands.
 16

17 **Tribal Permits and Settlements - 2017: \$621,000; 2018: \$250,000; 2019: \$150,000; 2020:**
 18 **\$250,000; 2021: \$250,000**

19 The Company currently owns and operates approximately 82 miles of transmission facilities
 20 and a significantly greater amount of distribution facilities on Tribal lands. The failure to
 21 complete this work and to attain proper permitting or easement rights on Tribal lands would
 22 require the Company to relocate its facilities. This would be cost-prohibitive for its
 23 transmission facilities and not viable for distribution facilities considering the Company’s
 24 obligation to serve its retail customers. Current renewals are being negotiated for terms of
 25 from 30 to 50 years. Renewal costs include labor, appraisals, field work, legal review, GIS
 26 information, negotiations, survey (as needed), and applicable fees for easements and permits.
 27

28 **Westside 230/115kV Substation Rebuild Phase I - 2017: \$5,566,000**

29 This project is necessary to mitigate our current noncompliance with mandatory NERC
 30 transmission planning standards during heavy summer loading conditions. Failure to make
 31 these planned investments will result in our failure to comply with mandatory NERC
 32 standards. We will continue to overload the Westside #1 230/115kV transformer during Phase
 33 I of this project, which overloading will extend to the existing Westside Substation 115kV
 34 and 230kV buses, to allow for installation of a new 250MVA 230/115kV Autotransformer.
 35 The additional transformation capacity is necessary to eliminate transformer overload
 36 contingencies in the Spokane area. This project has two additional planned phases to complete
 37 the entire rebuild of the station. The Company’s Engineering Roundtable has deferred the
 38 Garden Springs 230/115kV Substation integration due to the timing of the planned completion
 39 of this project.
 40

41 **Performance and Capacity Investments**

42
 43 **SCADA – Install/Replace - 2018: \$2,500,000; 2019: \$6,000,000; 2020: \$7,670,000; 2021:**
 44 **\$7,670,000**

1 In order to provide the Company's System Operations group with the necessary Supervisory
 2 Control and Data Acquisition (SCADA) capability for reliable system operation, this project
 3 will complete the installations of SCADA and EMS/DMS (Energy Management
 4 System/Distribution Management System) capability to all Avista substations. This capability
 5 will provide full visibility of system conditions and operations, system status indication, and
 6 operator control at each substation. The communication infrastructure for SCADA will enable
 7 the installation of automation on applicable distribution feeders. Furthermore, SCADA
 8 capability to each substation will provide real time and historical system performance data to
 9 the Transmission System Planning, Asset Management, Operations and Engineering groups
 10 to enable efficient, flexible and safe design and operation the Company's transmission and
 11 distribution systems in the future. The failure to make these investments in the timeframe
 12 planned will result in the Company losing information connectivity with its transmission
 13 system and risk being in violation of NERC transmission planning standards, and subject to
 14 financial and other penalties.

15
 16 **Substation – Capital Spares - 2017: \$4,204,000; 2018: \$5,065,000; 2019: \$4,025,000;**
 17 **2020: \$4,025,000; 2021: \$4,025,000**

18 This program maintains our fleet of power transformers and high voltage circuit breakers,
 19 which have very long procurement lead times. Consequently, a sufficient inventory level
 20 needs to be maintained to ensure the Company has required equipment for construction
 21 projects and can quickly replace failed critical equipment. This critical equipment is
 22 capitalized upon receipt and placed in service for both planned and emergency installations as
 23 required. Annual program expenditures may vary significantly in years when a 230/115kV
 24 autotransformer is purchased.

25
 26 **Substation – New Distribution Stations - 2017: \$2,424,000; 2018: \$850,000; 2019:**
 27 **\$6,375,000; 2021: \$5,000,000**

28 This program adds new distribution substations to the system in order to serve new and
 29 growing load as well as to provide increased system reliability and operational flexibility.
 30 New substations under this program require planning and operational studies, justifications,
 31 and approved project diagrams prior to funding. Planned new projects include substation sites
 32 in downtown Spokane, the Spokane west plains area, north Spokane and the Pullman/Moscow
 33 stateline area. The failure to complete these projects in this planning horizon will result in
 34 equipment overloading and reliability issues, which are impossible to quickly rectify once
 35 they occur.

36
 37 **Q. Please provide some examples of Transmission Capital projects that were**

38 **not approved, and the risk associated with not completing or deferring these projects.**

39 A. A. The Hatwai-Lolo #2 230kV Transmission Line construction project,
 40 required to comply with NERC transmission planning standards, has been deferred in order
 41 to balance the overall demand for investment across the Company. The Company's engineers

1 continue to evaluate short-range operational solutions to mitigate transmission system
2 deficiencies in the southern portion of the Company's transmission system. Until this project
3 can be completed, for certain outages the Company will continue to have to disconnect its
4 transmission interconnection with Idaho Power and reconfigure major portions of its southern
5 system, leaving the majority of the Company's customers in this area exposed to additional
6 outages.

8 **V. NATURAL GAS SYSTEM INVESTMENTS**

9 **Q. What needs are driving the Company's planned investments in natural**
10 **gas distribution infrastructure for the period 2017 - 2021.**

11 A. There are many drivers, including the removal of capacity limitations, we have
12 identified on our natural gas system that could prevent us from meeting our customers' needs
13 during periods of very cold weather. Avista is required to meet a range of mandatory
14 requirements that aim to ensure the integrity of our natural gas system. It is Avista's goal,
15 along with these requirements, to make sure we deliver cost-effective energy services to our
16 customers in a manner that protects their health and safety, as well as that of our employees
17 and the general public. Finally, we face the continuous need to replace materials and
18 equipment that have reached the end of their useful life, based on asset condition; to protect
19 our system from damage by other parties, and respond to the infrastructure plans of
20 municipalities and others that can require us to relocate portions of our natural gas system.
21 More specifically, as I have explained in prior sections of my testimony, the need for our
22 natural gas system investments is organized by investment driver and is briefly explained for
23 each project and program in the following narrative.

1 **Q. How do the business units in Avista’s natural gas operations identify the**
2 **need for and prioritize requests for infrastructure investment?**

3 A. The need for investment is identified in a number of ways, including but not
4 limited to, 1) by our field personnel; 2) from needs identified through our systematic
5 maintenance of the system; 3) by our natural gas engineering group using the SynerGEE®
6 computer-based modeling tool evaluate current and future customer loads and our system
7 capacity to meet them; 4) from asset management analysis of specific issues; and 5) through
8 our plans to remediate threats to our system identified by Avista’s Distribution Integrity
9 Management Planning (DIMP) process. The integrity management plan processes follow a
10 rigorous federal protocol for identifying and ranking any risks or threats that, over time, could
11 impair the integrity of our natural gas system. Avista is then required to develop action plans
12 that reduce or eliminate these threats. Implementation of these plans is mandatory. Our natural
13 gas engineering group serves as the clearing house for evaluating and prioritizing these
14 investment needs, including which projects are forwarded to the Company’s Capital Planning
15 Group. Our engineers assess the range of needs to be met by each individual project, the
16 potential consequences of deferring or reducing the amount of the proposed investment, and
17 ranks all proposed projects across the Company’s entire natural gas system by overall priority
18 of need, with some deference to the geographical locations of the projects.

19 **Q. Please list the natural gas distribution investments planned for the current**
20 **period and provide a brief description of each project or program?**

21 A. Table 3 below lists Avista’s planned natural gas distribution projects by
22 investment driver on a system basis for the years 2017-2021. In the narrative that follows I
23 briefly describe each project or program, explaining why we are implementing the project, as

1 well as the likely consequence to Avista of our failure to make these investments in the
2 timeframe proposed.

Table No. 3

Natural Gas Distribution Capital Projects (System) In \$(000's)					
Business Case Name	2017	2018	2019	2020	2021
<u>Traditional Pro Forma Study Projects:</u>					
Failed Plant and Operations					
Gas Non-Revenue Program	\$ 6,096				
Mandatory and Compliance					
Gas Facilities Replacement Program (Aldyl A)	21,764				
Gas Replacement Street and Highway Program	3,319				
	31,179				
<u>End of Period Rate Base Study and Rate Year Projects:</u>					
Asset Condition					
Gas Deteriorated Steel Pipe Replacement Program	\$ 1,001	\$ 1,000	\$ 1,000	\$ 1,000	\$ 1,000
Gas ERT Replacement Program	240	260	280	330	716
Gas Regulator Stn Replacement Program	1,376	800	800	800	800
Customer Requested					
New Revenue - Growth	23,099	22,239	22,941	23,455	23,434
Failed Plant and Operations					
Gas Non-Revenue Program		6,000	6,000	6,000	6,000
Mandatory and Compliance					
Gas Cathodic Protection Program	900	700	700	700	700
Gas Facilities Replacement Program (Aldyl A)		20,700	21,160	21,629	22,109
Gas HP Pipeline Remediation Program	5,275	2,925	3,013	3,062	3,000
Gas Isolated Steel Replacement Program	2,050	2,000	2,000	2,000	2,000
Gas N-S Corridor Greene St HP Main Project	113				
Gas Overbuilt Pipe Replacement Program	500	500	500	500	400
Gas PMC Program	1,200	1,200	1,200	1,200	1,200
Gas Replacement Street and Highway Program		3,000	3,000	3,000	3,000
Performance and Capacity					
Cheney HP Reinforcement			5,000		
Gas N Spokane Hwy 2 HP Main Reinforcement Project	342				
Gas Pullman HP Reinforcement				2,500	
Gas Reinforcement Program	1,000	1,000	1,000	1,000	1,000
Gas Telemetry Program	209	200	200	200	200
Gas Warden HP Reinforcement			6,000		
Total End of Period Rate Base and Rate Year Projects	\$ 37,305	\$ 62,524	\$ 74,793	\$ 67,377	\$ 65,559
Idaho and Oregon Direct Business Cases					
Gas Schweitzer Mtn Rd HP Reinforcement		1,500			
Gas Pierce Rd La Grande HP Reinforcement	3,901				
Gas Rathdrum Prairie HP Main Reinforcement Project	4,426	4,000			
	8,327	5,500			
Total Planned Natural Gas Distribution Capital Projects	\$ 76,811	\$ 68,024	\$ 74,793	\$ 67,377	\$ 65,559

1 **Traditional Pro Forma Study Projects:**

2
3 **Failed Plant and Operations**

4
5 **Gas Non-Revenue Program - 2017: \$6,096,000**

6 The investments made under this program are responsive to issues identified by the Company
7 in real time, which is why the expected capital spend each year is estimated based on historical
8 trends. Typical activities include increasing the depth of existing gas lines that are identified
9 as not meeting the required depth,³⁷ performing customer-requested relocates, making leak
10 repairs on mains and service lines, installing meter barricades, eliminating farm taps from the
11 system, and relocating facilities as required (other than street and highway). Our failure to
12 regularly perform these activities would result in a greater likelihood of our shallow pipe being
13 damaged, which could result in citizen, customer, and employee safety, and prevent us from
14 prudently managing our natural gas system.

15
16 **Mandatory and Compliance**

17
18 **Gas Facilities Replacement Program (Aldyl A) - 2017: \$21,764,000**

19 The Company is continuing its program to systematically remove and replace select portions
20 of the DuPont Aldyl A medium density polyethylene pipe in its natural gas distribution system
21 in the States of Washington, Oregon and Idaho. Avista's asset management group identified
22 this piping as prone to the increased potential of leaking as it ages, and based on the risks to
23 our customers resulting from these leaks, Avista implemented its Priority Aldyl A Pipe
24 replacement program. In addition to the Company's own analysis, this piping has also been
25 identified as the highest threat to the integrity of Avista's natural gas system. Renamed the
26 Gas Facilities Replacement Program, this effort fulfills the Company's obligation to mitigate
27 such threats on its natural gas system.

28
29 **Gas Replacement Street and Highway Program - 2017: \$3,319,000**

30 Nearly all of Avista's distribution pipelines are located in public utility easements provided
31 for such service, which are under the control of local jurisdictions administered through the
32 Company's franchise agreements. Avista is mandated under these agreements to relocate its
33 facilities, at our cost whenever local jurisdictional projects require such a move. While Avista
34 has the opportunity to discuss these requirements and to suggest ways to avoid or minimize
35 the cost to our customers, we have no choice but to move our facilities if required. Our failure
36 to make such required investments would put in the Company in violation of its franchise
37 agreements, could subject us to penalties for the delay of a project, legal action, or the
38 revocation of our franchise to provide utility service in that jurisdiction.

³⁷ This situation most often occurs because soil above the line has been removed by other activities in the time after the line was installed.

1 **End of Period Rate Base Study and Rate Year Projects:**

2
3 **Asset Condition**

4
5 **Gas Deteriorated Steel Pipe Replacement Program - 2017: \$1,001,000; 2018: \$1,000,000;**
6 **2019: \$1,000,000; 2020: \$1,000,000; 2021: \$1,000,000**

7 Existing steel natural gas piping in the Company's distribution system is aging and showing
8 signs of deterioration, even when properly maintained, and it presents an increased risk of
9 failure in the event it has been subject to corrosion. Sections of gas main with known
10 corrosion-related issues need to be removed to avoid failure that could impact safety and
11 reliability. Avista's distribution integrity management program has identified this pipe
12 material as a threat that needs to be removed from the Company's natural gas distribution
13 system. If the Company fails to make the investments needed to remove this deteriorated
14 piping we would be exposing our customers and the general public to elevated risk and safety
15 concerns where pipe is located in the vicinity of high risk facilities, in particular, where we
16 have known leaks, leak potential and corrosion issues.

17
18 **Gas ERT Replacement Program - 2017: \$240,000; 2018: \$260,000; 2019: \$280,000; 2020:**
19 **\$330,000; 2021: \$716,000**

20 The majority of the Company's natural gas meters are equipped with an electronic device that
21 records the amount of natural used by the customer and wirelessly transmits that usage to
22 Avista for billing purposes. This device known as an Encoder Receiver Transmitter (ERT) is
23 battery powered, and when these batteries fail, customer's estimated usage must be collected
24 and entered into the billing system manually. Besides the additional cost, this manual process
25 can lead to high rates of customer dissatisfaction because of potential error associated with
26 estimating the customers' bill. Finally, because the Company has so many of these units in
27 service, the replacement of batteries as they failed would quickly become unmanageable as
28 the entire population of batteries reach the end of their useful life. The failure to make these
29 planned investments would eventually have an unsustainable impact on Avista's natural gas
30 billing system and would result in substantially greater costs for replacement compared with
31 the systematic approach.

32
33 **Gas Regulator Station Reliability Replacement -2017: \$1,376,000; 2018: \$800,000; 2019:**
34 **\$800,000; 2020: \$800,000; 2021: \$800,000**

35 Investments made under this program replace or upgrade Avista's natural gas regulator
36 stations and industrial meter sets that are at the end of their service life, or are obsolete and no
37 longer supported, based on the Company's performance standards. Avista's regulator stations
38 require federally-mandated annual maintenance, and if the equipment at the stations is
39 obsolete and replacement/maintenance parts are no longer commercially available, then
40 proper maintenance cannot be completed. These investments also enhance the performance
41 of our stations, improving natural gas system safety, reliability and operations. The failure to
42 timely inspect our regulators and industrial meter sets, and to perform required maintenance
43 and replacements, would render them less reliable and unsafe, and would expose the Company
44 to regulatory and other consequences as a result of choosing to not make such investments.

Customer Requested

New Revenue Growth -2017: \$23,099,000; 2018: \$22,239,000; 2019: \$22,941,000; 2020: \$23,455,000; 2021: \$23,434,000

This annual program addresses costs to serve new loads for natural gas service. This program includes the cost of new meters, new natural gas piping, the cost of new regulators, the cost of new encoder receiver transmitters (ERTs), and the associated installation cost of these investments. Avista is required by its service tariffs to make the investments necessary to connect customers when requested.

Failed Plant and Operations

Gas Non-Revenue Program -2018: \$6,000,000; 2019: \$6,000,000; 2020: \$6,000,000; 2021: \$6,000,000

Please see the Gas Non-Revenue Program description above under the Traditional Pro Forma Study Projects.

Mandatory and Compliance

Cathodic Protection -2017: \$900,000; 2018: \$700,000; 2019: \$700,000; 2020: \$700,000; 2021: \$700,000;

Cathodic protection involves making in-ground metal structures like steel pipelines part of a DC electrical circuit that prevents them from corroding. Avista is required by federal and state regulations to have effective cathodic protection systems on all steel natural gas piping in its system. Since these systems have a finite lifespan, and must be replaced when they are nearing the end of their service life, failing to timely replace them renders the underground steel lines vulnerable to corrosion. This failure would also expose the general public, our customers, and our employees to increased safety risks and would place the Company in violation of mandatory regulations.

Gas Facilities Replacement Program (Aldyl A) -2018: \$20,700,000; 2019: \$21,160,000; 2020: \$21,629,000; 2021: \$22,109,000

Please see the Gas Facilities Replacement Program description above under the Traditional Pro Forma Study Projects.

Gas High Pressure Pipeline Remediation Program -2017: \$5,275,000; 2018: \$2,925,000; 2019: \$3,013,000; 2020: \$3,062,000; 2021: \$3,000,000

Current industry practice and pipeline safety codes require natural gas distribution systems to be pressure tested, and the documentation of this testing and the material specifications of the pipelines to be properly maintained. Avista has identified deficiencies in its records resulting from practices generally prior to development of the code and current standards. This is not uncommon in our industry. A new rule in the Federal Pipeline Safety Code, making this testing and documentation mandatory and subject to penalties for non-compliance, will soon become final and effective. This program will perform the work required to develop traceable, verifiable, and complete pressure testing records for all segments of our high pressure pipeline

1 where the records do not currently exist. Failure to make these required investments will
 2 expose the Company to penalties for non-compliance with this mandatory requirement.
 3

4 **Gas Isolated Steel Replacement -2017: \$2,050,000; 2018: \$2,000,000; 2019: \$2,000,000;**
 5 **2020: \$2,000,000; 2021: \$2,000,000;**

6 The program identifies and documents areas in our natural gas system where we currently
 7 have steel pipe sections, including risers that are “isolated” from steel piping in cathodically-
 8 protected zones. Even though these isolated sections may be currently protected, the Company
 9 is required by Federal code and by agreement with the Commission to replace each riser or
 10 pipeline section within a specified timeframe once it has been identified. This program was
 11 initiated in our Washington service territory in November 2011, requiring the Company to
 12 replace isolated steel risers at a rate of at least 10% per year, and to replace short sections of
 13 isolated steel main within one year of when they are identified. Our program in Washington
 14 will be completed in 2021, and Avista will be extending this program to its Oregon and Idaho
 15 service territories. Our failure to make these required investments will place the Company in
 16 violation of its stipulated agreement with the Commission.
 17

18 **Gas N-S Corridor Greene St HP Main Project -2017: \$113,000**

19 Due to the planned construction of Spokane’s North-South Corridor (transportation) Project
 20 the Company may be required to relocate a section of its 20-inch Green Street high pressure
 21 main. The scope and schedule for this project are not finalized, and the Company is currently
 22 working with the Washington department of transportation, the city, and Burlington Northern
 23 Santa Fe Railway to develop a final plan that minimizes the impact to our line. This work
 24 is identical to projects conducted under our street and highway relocation program, however,
 25 this large project has been planned for and budgeted as a specific infrastructure project.
 26 Avista’s failure to make the investment required to relocate our high pressure line would
 27 expose the Company to violations of its franchise, potential litigation and financial exposure
 28 for delay of the transportation project, and would severely damage our ability to continue to
 29 work effectively with these important entities.
 30

31 **Overbuilt Pipe Replacement -2017: \$500,000; 2018: \$500,000; 2019: \$500,000; 2020:**
 32 **\$500,000; 2021: \$400,000;**

33 There are instances where our customers have constructed or placed structures, sheds and
 34 decks, etc., directly over sections of our natural gas distribution system. As a result of these
 35 “overbuilds” the Company may not have adequate access to operate, repair and safely
 36 maintain our system (such as conducting the annual leak survey of our system). Avista is
 37 required by Federal code to remediate these overbuilds. This program is focused mainly on
 38 identifying and addressing these issues in mobile home parks where we experience the highest
 39 incidence rates and risks. Avista’s failure to make these planned investments will expose our
 40 customers to risks associated with our inability to access our system, and will place the
 41 Company in violation of its mandatory federal requirements, and potential penalties.

1 **Gas Planned Meter Change-Out (PMC) Program-Capital Replacements -2017:**
2 **\$1,200,000; 2018: \$1,200,000; 2019: \$1,200,000; 2020: \$1,200,000; 2021: \$1,200,000**

3 Avista is required by Commission rules and tariffs to test a portion of our meters each year
4 for accuracy to ensure proper metering performance. The costs included under this program
5 include labor and minor materials. Major materials (meters, pressure regulators and encoder
6 receiver transmitters) are charged to the appropriate capital programs. Our failure to make
7 these investments would increase the likelihood that our customers' billing would be
8 inaccurate and would place the Company in violation of its tariffs, with the attendant
9 consequences of non-compliance.

10
11 **Gas Replacement Street and Highway Program -2018: \$3,000,000; 2019: \$3,000,000;**
12 **2020: \$3,000,000; 2021: \$3,000,000**

13 Please see the Gas Replacement Street and Highway Program description above under the
14 Traditional Pro Forma Study Projects.

15
16 **Performance and Capacity Investments**

17
18 **Cheney HP Reinforcement -2019: \$5,000,000**

19 Load studies performed by our natural gas planning group, coupled with pressure monitoring
20 during cold weather events have identified an issue of insufficient pressure at the south end of
21 the Cheney High Pressure (HP) pipeline that serves the town of Cheney, Washington. Without
22 reinforcement to increase the capacity of this line Avista will not be able to serve its firm
23 customer load in the Cheney area on a cold winter day that meets our design day standard.
24 Though the need for capacity reinforcement to serve our existing loads is the driver of this
25 project, it would also enable the Company to meet a potential need for additional firm capacity
26 to serve an existing large industrial customer in that area. There is also the possibility that the
27 new line would be routed through areas not yet served by gas, providing the additional benefit
28 of new growth. This project is still in the planning stage. Avista will gather and evaluate
29 additional load information before proceeding to the next steps of design and analysis of
30 alternatives. The failure to make this investment in the planned period exposes our customers
31 to a loss of natural gas service at a time when they are in the greatest need of reliable service
32 from the Company. In addition to this risk, Avista will have no capacity available for any
33 customer growth in the town of Cheney, Eastern Washington University, and the surrounding
34 area.

35
36 **Gas North Spokane Hwy 2 HP Main Reinforcement -2017: \$342,000**

37 Avista has identified an issue with the capacity of our distribution system in North Spokane.
38 Based on load studies performed by our natural gas planning group the Company does not
39 have sufficient pipeline capacity to meet our customer load obligations on a design day
40 standard. Further, Avista is currently not able to reliably serve an existing industrial customer
41 load in that area on a seasonal basis due to the capacity limitations of our system. As planned,
42 this project will install 12,000 feet of new High Pressure pipe and a new regulator station to
43 adequately reinforce our capacity in this area. If the Company fails to make this planned
44 investment we will continue to have insufficient capacity to serve the existing industrial

1 customer load and will expose approximately 4,300 of our customers to the risk of loss of
 2 service on a design day.

3
 4 **Gas Pullman HP Reinforcement -2020: \$2,500,000**

5 Load studies performed by our natural gas planning group have documented that, as a result
 6 of the load growth in the Pullman area, Avista has exceeded the capacity of our Pullman Gate
 7 Station (point of supply for Avista's system in that area). As a result, the Company's ability
 8 to reliably serve our customers on a design has been impacted. To relieve this capacity
 9 limitation the Company will install approximately 16,000 feet of high pressure main pipe
 10 linking the Pullman and Moscow high pressure systems. This solution will allow Avista to
 11 meet the needs of our customers in Pullman and to better utilize the available capacity on our
 12 Moscow system. Without this reinforcement project Avista will expose approximately 1,300
 13 of its customers to the risk of losing their service at a time when they are in the greatest need
 14 of reliable natural gas from the Company. Further, Avista will be unable to serve customer
 15 growth in that area without this project.

16
 17 **Gas Reinforcement -2017: \$1,000,000; 2018: \$1,000,000; 2019: \$1,000,000; 2020:**
 18 **\$1,000,000; 2021: \$1,000,000**

19 This ongoing program supports investments for smaller projects needed to reinforce the
 20 capacity of our natural gas distribution system in all our jurisdictions. Our failure to make
 21 these investments would expose our customers to the loss of their natural gas service on a
 22 design day, and would prevent Avista from meeting future load growth due to inadequate
 23 pressure and capacity.

24
 25 **Gas Telemetry -2017: \$209,000; 2018: \$200,000; 2019: \$200,000; 2020: \$200,000; 2021:**
 26 **\$200,000**

27 Projects under this program install natural gas telemetry throughout our natural gas system.
 28 Telemetry is the combination of communications and sensing systems that allow Avista to
 29 remotely monitor system pressures, volumes, and flows from areas of special interest such as
 30 Gate Stations (supply points into Avista's system), gas transportation customers, regulator
 31 stations (where operating pressure is reduced), selected large industrial customers, and
 32 distribution systems that are served by more than one source of natural gas. Having this
 33 detailed "visibility" of the gas transmission and distribution systems provides a more rapid
 34 response and better decision making by the Company when any abnormal operation or
 35 emergency situation strikes. The failure to timely make these investments would reduce the
 36 reliability of our system for customers resulting from low or high pressure situations, and the
 37 related safety risks, and a higher likelihood of equipment failures that impact our service.

38
 39 **Gas Warden High Pressure Reinforcement -2019: \$6,000,000**

40 Our customers in the community of Warden are currently exposed to two capacity concerns
 41 on our system: 1) the town is supplied gas from the fully-subscribed and capacity-constrained
 42 Moses Lake lateral (owned by Williams Northwest Pipeline), and 2) the Company's high
 43 pressure supply line into town has reached its capacity. These current capacity constraints
 44 limit opportunities for customer growth as well as expansion for industrial gas use in the Port
 45 of Warden Industrial Park. This project will install a new gate station on the supply pipeline,

1 connected to a new high pressure supply pipeline approximately 17,000 feet in length. This
2 new dedicated gate station will be appropriately sized to manage both current capacity
3 limitations and expected future growth. Without this reinforcement project, Avista does not
4 have sufficient capacity to meet its obligation to serve its customer loads in the Warden area
5 on a design day, exposing its customers to the risk of losing natural gas service. Additionally
6 there is no available capacity for future customers.
7

8 **Q. Please provide some examples of Natural Gas Plant Capital projects that**
9 **were not approved, and the risk associated with not completing or deferring these**
10 **projects.**

11 A. The Cheney HP Reinforcement was delayed one year from 2017-2018 to 2018-
12 2019. By delaying the project, Avista does not have sufficient capacity to serve Firm customer
13 loads in the Cheney, WA area on a design day scenario for one additional year. This puts the
14 Company at risk of outages during a cold weather event. Additionally, there would be no
15 capacity available for the large customer in Cheney to expand their operations.

16 The Overbuild Pipe Replacement Program was reduced from \$900,000 to \$500,000
17 per year. This resulted in an approximately 45% reduction of main and service replacement
18 work. The reduced funding would still allow us a benefit by addressing some of the overbuilt
19 facilities with known risk, but at a pace slower than normal plans to address these safety
20 concerns and maintain compliance. The outcome would result in the continued operation of
21 facilities known to be out of compliance and which are currently operating with higher risk to
22 customers and operations personnel. Additionally, Operations & Maintenance funds would
23 not decrease since Avista is often required to return to an overbuild locations multiple times
24 to attempt and complete a leak survey or other maintenance tasks that cannot be completed
25 due to the overbuild.

1 **VI. FLEET AND FACILITIES INVESTMENTS**

2 **General Plant Investments**

3 **Q. Please discuss the drivers for the Company's investments in infrastructure**
4 **grouped under the category of general plant for the period 2017-2021?**

5 A. The majority of these programs and projects are investments made to
6 maintain, improve or replace the Company's offices, service centers, material storage facilities
7 and their associated properties, based generally on asset condition or to address performance
8 and capacity needs. In addition to having responsibility for maintaining this infrastructure,
9 Avista's facilities management group responds to needs identified by the business and
10 develops responsive projects that support our customer service center; provide ample
11 employee work space; provide for employee and customer safety and efficiency in the flow
12 of pedestrian and vehicle traffic on our central campus, meet the needs of fleet operations,
13 provide space for our field service employees in electric and natural gas operations, ensure
14 adequate space for equipment in our warehouses and storage yards, accommodate the safe and
15 efficient handling of hazardous waste and to manage environmental issues, and provide for
16 safe and adequate employee and customer parking.

17 **Q. How does Avista's facilities group evaluate alternatives to meet identified**
18 **needs and prioritize capital projects before they are recommended to the Capital**
19 **Planning Group?**

20 A. The facilities group completed a survey of the structures and appurtenant
21 facilities at each of Avista's operations service centers. Each was rated on asset condition,
22 based on factors including site utilities, interior condition, plumbing and HVAC, and fire
23 safety systems. Using this information the facilities manager and one or more of the group's

1 project managers, met with employees representing electric and natural gas energy delivery,
2 environmental affairs, real estate, and finance, to review the survey results in the context of
3 the business needs identified by each area. Beyond these immediate needs they factored in the
4 needs of our customers, the potential for future expansion, current and expected materials
5 storage needs (including offsite storage yards), environmental concerns, safety and
6 compliance considerations, and site location. This team of employees representing the
7 respective areas of the business then recommended whether each service center should be sold
8 and replaced, replaced on the same site, or should continue to be maintained, repaired,
9 remodeled, and improved with capital upgrades as warranted. Facilities recommended for
10 replacement and upgrade were then prioritized based on the condition factors listed above.

11 **Q. Please briefly describe the infrastructure projects under general plant**
12 **planned for the period 2017 – 2021?**

13 A. These individual projects and programs and planned spending by year are
14 listed in Table No. 4, and are briefly described in my testimony below.

Table No. 4

General Plant Capital Projects (System) In \$(000's)					
Business Case Name	2017	2018	2019	2020	2021
Traditional Pro Forma Study Projects:					
Performance and Capacity					
New Downtown Netwk Bldg	\$ 6,559				
COF Long-Term Restructuring Plan 2 ⁽¹⁾	13,695				
	\$ 20,254				
End of Period Rate Base Study and Rate Year Projects:					
Asset Condition					
COF Long-Term Restructuring Plan	2,064				
Dollar Rd Service Center Addition and Remodel	321	17,710			
New Davenport Facility				6,500	
Noxon & Clark Fork Living Facilities	1,411	1,563			
Sandpoint Renovation				5,500	
Structures and Improvements/Furniture	3,294	3,600	3,600	3,600	3,600
Failed Plant and Operations					
Capital Tools & Stores Equipment	2,712	2,400	2,400	3,000	3,150
Performance and Capacity					
Apprentice Training	60	60	60	60	60
CNG Fleet Conversion	52				
COF Lng Trm Restruct Ph2		10,000		14,000	10,000
Company Aircraft Capital	296	3,000			
Ergonomic Equipment	616	300			
Jack Stewart Training Center Expansion				10,300	
Airport Hangar	1,500				
New Deer Park Service Center	6	6,247			
New Pullman Service Center				7,600	
Total Planned General Plant Capital Projects	\$ 32,585	\$ 44,880	\$ 6,060	\$ 50,560	\$ 16,810
⁽¹⁾ COF = Central Office Facilities					

Traditional Pro Forma Study Projects:**Performance and Capacity****New Downtown Network Building -2017: \$6,559,000**

The Downtown Campus project includes several related sub-projects discussed below. In the first phase of this plan in 2015 Avista purchased an existing office building with 22,000 square feet of space situated on a 2.3 acre parcel in Spokane. The office space was renovated in a second phase in 2016, and several employee project teams were relocated to this space, freeing up needed office space in our central office facilities. In considering an alternative to purchasing and renovating this property, the Company evaluated the cost of leasing office space and approximately 100 parking spaces, but determined that the lifetime cost of purchasing and renovating this facility, including the ability to expand operations at this site, was less than the long term expense associated with leasing. The third and final phase of this

1 project, estimated to be completed in late 2017, includes the construction of an operations
 2 center for the Company's electric network staff, craft workers, vehicles, equipment and
 3 materials storage.³⁸ This project will consolidate the downtown crews and equipment onto one
 4 integrated site, improving safety, efficiency and our response to network reliability issues.

5
 6 **COF Long-Term Restructuring Plan 2 -2017: \$13,695,000**

7 Phase 2 of this plan is a continuation of the long-term program to meet our ongoing and future
 8 operating needs by renovating, improving and expanding our existing central office and
 9 operating facilities. This phase is composed of three major projects that include re-routing a
 10 city street adjacent to our campus in 2017, constructing a new building for our fleet operations
 11 in 2017 and 2018, and constructing a parking garage in 2018. These three projects are
 12 interdependent because of their location, timing of construction and their relationship to the
 13 overall design of our central campus. These projects support Avista's objectives of 1)
 14 consolidating the footprint of our central facilities, which today consists of several disjointed
 15 parcels; 2) modernize and expand our aging fleet facilities to handle today's needs efficiently,
 16 meet compressed natural gas fleet compliance, better manage environmental concerns, and
 17 provide the space required for efficient queuing of fleet equipment; 3) Provide adequate
 18 campus parking for employees, which is currently short by about 400 spaces, and consolidate
 19 parking on company-owned land, improving employee and public safety by eliminating our
 20 parking sprawl, and 4) separate currently shared traffic routes for our construction vehicles
 21 and equipment and pedestrians to improve safety and increase workflow efficiency. Avista
 22 selected this plan from several options evaluated by the facilities group for meeting these
 23 combined needs. The failure to implement these plans in the timeframe proposed will result
 24 in work being terminated mid-stream on work underway, adding significantly to future costs
 25 to complete these projects, will require Avista to make alternative investments to mitigate the
 26 operational and environmental limitations of our existing fleet operations, and fail to resolve
 27 significant issues related to our current employee parking.

28
 29 **End of Period Rate Base Study and Rate Year Projects:**

30
 31 **Asset Condition**

32
 33 **COF Long-Term Restructuring Plan -2017: \$2,064,000**

34 The remaining investments under this plan conclude a multiyear effort that began in 2013 and
 35 included nine individual projects. These projects completed in their sequence were required
 36 for implementation of the Campus Repurposing Phase 2 plan. All of these projects have been
 37 completed, with the exception of the expansion of the warehouse storage yard. Without the
 38 expansion, the Company will lack adequate and efficient space for its materials storage needs,

³⁸ Network operations is currently housed in a portion of the Company's 1907 Post St. Substation building. The interior space was not designed to support modern operations and equipment, and the internal systems and equipment have long-since exceeded their useful life. This location has limited site access with poor visibility for pedestrians and traffic, and the Company must rely other downtown locations for storage of materials and equipment. Finally, the Post Street building is a Spokane icon and has designated historic status, which limits our ability to modify it to the degree required for efficient operations.

1 which today impact crews' efficient access to materials since they are stored at multiple
2 locations at our central office as well as offsite.
3

4 **Dollar Road Service Center Addition and Remodel -2017: \$321,000; 2018: \$17,710,000**

5 This planned investment would replace the existing natural gas operations service center at
6 the existing site. The Dollar Road Service Center is the main natural gas operations center
7 serving approximately 300,000 customers in the greater Spokane area, performed by
8 approximately 70 field crews and administrative support employees. The service center also
9 provides support for local gas crews from the Ritzville, Colville, and Davenport districts,
10 which serve an additional 50,000 customers. The existing Dollar Road Service Center is
11 approximately 22,000 square feet and was constructed in 1956. Our business needs have
12 changed substantially since that time as a result of industry advances and growth in customers.
13 In addition to work flow, many of the main building components, systems, and equipment
14 have deteriorated with age and are past their useful service life. The Dollar Road Service
15 Center scored the second lowest among the Avista facilities rated for asset condition in 2012.
16 If the Company fails to make this investment as planned, we will continue to operate at the
17 level of efficiency currently limited by this facility, we spend increasing amounts of capital
18 and expenses for heavy maintenance, replacement of internal systems, and repair of structures
19 and systems that fail prior to replacement.
20

21 **New Davenport Facility -2021: \$6,500,000**

22 This project is to build a new replacement service center at the location of our existing pole
23 yard or on a new site that could accommodate both the new service center and the pole yard.
24 The existing Davenport service center was purchased in 1966 and renovated in 1969-1970.
25 Avista has invested \$480,000 in maintenance of the facility since that time. The 0.7-acre
26 property does not have adequate space for fleet vehicles and poles, and the current garage bay
27 is too small for the equipment we use today. The facility also has environmental constraints
28 such as our inability to store transformers there without installing new environmental controls.
29 Trucks and materials, including transformers, equipment, and poles are currently stored at the
30 pole yard. The failure to build the new service center as planned will result in a continuation
31 of our current efficiency and safety limitations, and increasing annual capital costs and
32 expenses to replace and repair building systems needed to keep the building in usable
33 condition.
34

35 **Noxon & Clark Fork Living Facilities -2017: \$1,411,000; 2018: \$1,563,000**

36 This project includes the total rehabilitation of two living facilities at Clark Fork, Idaho and
37 Noxon, Montana, to address deteriorating condition of the facilities and their systems, extend
38 the life of the facilities, and update them to a more modern and energy efficient state. The
39 project combines required repair work with the facility renovation to avoid duplicating efforts
40 and saving costs on contractor mobilization and re-work. The living facilities were constructed
41 in 1983 and 1984 and have been in use for more than 30 years. They are 16-room bunkhouses
42 with a common space containing a kitchen, dining hall and laundry facility. Because of the
43 limited availability of lodging in this rural area, Avista crews and personnel lodge at these
44 facilities when performing work at Noxon Rapids Dam, Cabinet Gorge Dam, or on other
45 Avista equipment in the area. During inspections in 2015, extensive issues were found with

1 the facilities, including structural and water damage to the siding and framing due to water
2 penetration, inadequate and antiquated electric heating systems, HVAC deficiencies and non-
3 compliant electric breaker panels and inadequate insulation. This project would address the
4 structural and water damage, bring the building up to modern code, and extend the life of the
5 facility. The completed facilities would provide years of additional service, increase the
6 efficiency of energy usage, reduce annual O&M costs to maintain the structures, and provide
7 a suitable environment for housing our workforce at these remote sites. Disregarding the
8 continuing water penetration was not an option as this would render portions of, and
9 eventually the entire facility, uninhabitable over time. Maintenance and upgrade work is
10 ongoing at both dams and is planned for the foreseeable future. This work is essential to
11 maintaining the reliability of our power generation and associated infrastructure in the region.
12 Without the continued availability of the living facilities, it's estimated that it would cost more
13 than \$300,000 annually to procure lodging at alternate sites for work at the plants, likely in
14 Sandpoint or Thompson Falls, about an hour drive one way from the plant. With a centralized
15 workforce based out of Spokane, the ability to provide lodging near our worksites maximizes
16 available working hours.

17
18 **Sandpoint Service Center -2020: \$5,500,000**

19 This project includes the purchase of property and construction of a new operations center,
20 warehouse and materials yard. The Sandpoint operations facility was acquired by the
21 Company in 1995 as part of our purchase of the electric properties in that area. The original
22 date of construction is unknown but many additions to the facilities have occurred over time.
23 Today, many of the main building components, systems, and equipment are in deteriorated
24 condition, and the site has extensive damage to concrete and asphalt areas, and fencing of the
25 property. Emergency exit lighting and a smoke detection systems are missing from the
26 building, which also has minor code compliance and security issues. Further, the layout of the
27 facility and the existing storage yards cannot efficiently meet our current business needs. The
28 failure to make this investment in the timeframe planned would require the Company to make
29 alternative capital investments needed to update, repair, add on, and otherwise retrofit the
30 existing facility in order to meet code requirements and continue our operations at that site,
31 and to forego the efficiency and other benefits provided by the replacement facility.

32
33 **Structures and Improvements/Furniture -2017: \$3,294,000; 2018: \$3,600,000; 2019:**
34 **\$3,600,000; 2020: \$3,600,000; 2021; \$3,600,000**

35 This ongoing capital program funds lifecycle equipment replacements and needed
36 improvements at more than 40 Avista offices and service facilities (exceeding 900,000 square
37 feet). These needs are compiled, evaluated and prioritized based on need and asset condition
38 and lifecycle standards, designed to address: 1) Lifecycle asset replacements (examples:
39 roofing, asphalt, electrical, plumbing); 2) Lifecycle furniture replacements and new furniture
40 additions (to support growth), and 3) Business additions or site improvements (examples:
41 adding a welding bay, vehicle storage canopy, expanding an asphalt yard, and can sometimes
42 include property purchases to support site expansions). The replacements based on asset
43 condition are intended to achieve a more stable and predictable level of capital requirements,
44 and to avoid peak investments caused by coincident and large-scale failures. The failure to
45 make these timely investments will result in reduced efficiency, safety issues, accelerated

1 deterioration and failure of assets, such as roofing or HVAC systems, which can result in
 2 major damage to the facilities, and a bow-wave of needed investments to the future.
 3

4 **Failed Plant and Operations**

6 **Capital Tools & Stores Equipment -2017: \$2,712,000; 2018: \$2,400,000; 2019: 7 \$2,400,000; 2020: \$3,000,000; 2021: \$3,150,000**

8 Avista's capital tools program provides Company employees with proper tooling and
 9 equipment needed to safely and efficiently construct, monitor, manage system integrity, and
 10 properly repair and maintain our electric, gas, communications, fleet, facilities, and generation
 11 infrastructure. If the Company fails to provide its employees proper tools and equipment when
 12 they are needed, we would be unable to provide our customers with adequate, reliable and
 13 cost effective services that meet their expectations for quality and value. These tools and
 14 equipment also support the safety of our employees.
 15

16 **Performance and Capacity**

18 **Apprentice Training -2017: \$60,000; 2018: \$60,000; 2019: \$60,000; 2020: \$60,000; 2021: 19 \$60,000**

20 This investment consists of on-going capital facility improvements needed to support required
 21 training for apprentice, pre-apprentice, and journey level craft workers, ensuring they are
 22 prepared to safely meet the specialized technical needs to build and properly maintain electric
 23 and natural gas utility systems. Expenditures include expanding existing or constructing new
 24 facilities, purchase of training equipment, and the construction and maintenance of actual
 25 utility infrastructure designed specifically for the training of employees.
 26

27 **Compressed Natural Gas (CNG) Fleet Conversion -2017: \$52,000**

28 This program supports the continuing conversion of a portion of Avista's fleet vehicles to run
 29 on compressed natural gas (CNG). The use of natural gas by our vehicles helps Avista reduce
 30 vehicle emissions and lower our operating costs. Operating our natural gas-powered fleet has
 31 also allowed us to provide our customers and others, who have been considering a natural gas
 32 powered vehicle, with practical experience on the requirements of owning and operating
 33 natural gas fueled vehicles. Importantly, we also use our natural gas compression system to
 34 fuel our truck and trailer-mounted natural gas storage tanks that allow us to maintain natural
 35 gas service to our customers when the distribution system has been damaged or is being
 36 serviced by the Company.
 37

38 **Campus Repurposing Plan Phase 2 -2018: \$10,000,000; 2020: \$14,000,000; 2021: 39 \$10,000,000**

40 Please see the Campus Repurposing Plan Phase 2 Program description above under the
 41 Traditional Pro Forma Study Projects listed above.
 42

43 **Company Aircraft Capital -2017: \$296,000; 2018: \$3,000,000**

44 This investment is to purchase the 18-year old Cessna Citation VII aircraft that the Company
 45 has leased since 2000. In March 2018, the current lease will expire, which provides for an

1 end-of-term purchase option that applies prior lease payments toward the purchase in a lump-
 2 sum amount. In addition to the purchase price of approximately \$2.5 million, the planned
 3 investment also includes updating the avionics to comply with new FAA mandates at a cost
 4 of approximately \$500,000, and self-funding the parts plan for the aircraft. The planned
 5 purchase option will save approximately \$1.1 million in annual expenses. Approximately 50%
 6 of flights made each year directly support the Company's utility regulatory activities and the
 7 remainder supports travel to Avista's regional offices and other business requirements. A large
 8 portion of these destinations is not served by a commercial airline.

9
 10 **Ergonomic Equipment -2017: \$616,000; 2018: \$300,000**

11 It is the Company's goal to help our employees be more engaged with maintaining their health,
 12 wellness and work productivity. An important step has been the introduction of ergonomic
 13 programs, office equipment and education. This effort reduces workplace injuries and other
 14 health impacts and helps Avista avoid the associated health costs. This program provides
 15 employees with ergonomic equipment and training.

16
 17 **Jack Stewart Training Center Expansion -2020: \$10,300,000**

18 The Jack Stewart Training Center, located in north Spokane, was originally constructed for
 19 apprentice and journeyman line training and over its history the annual enrollment of students
 20 at the Avista/SCC Pre-Apprentice Line School³⁹ has more than tripled. The training center
 21 has also been expanded to accommodate new mandatory requirements for training across craft
 22 areas, such as natural gas operator qualifications training. Today, the center supports Avista's
 23 Electric Operations, Natural Gas Operations, Generation, Production and Substation Support,
 24 Compliance & Safety, and a broad range of corporate employee training needs. A modular
 25 building was located at the center to provide classroom space in the early 1980s. A training
 26 classroom building was added later, and a second 10-year-old modular unit was added in 2006.
 27 In addition to not having the capacity for our current training needs, the two modular facilities
 28 have deteriorated over time and regular maintenance is no longer sufficient to maintain them
 29 in good condition. This project replaces the modular buildings with three new buildings at the
 30 current location, providing classroom space and laboratory and other facilities needed to meet
 31 our current training demands. This project is required to enable the Jack Stewart Training
 32 Center to continue to meet the Company's ongoing training needs, and the failure to make
 33 these investments in the timeframe planned would require Avista to make alternative
 34 accommodations that would be less efficient and more costly today and over the long term.

35
 36 **Airport Hanger -2017: \$1,500,000**

37 This project is to build an Avista-owned hangar on leased land at Spokane International
 38 Airport. This facility will replace the hangar we currently sublease, which will be demolished
 39 after our sublease is withdrawn in July 2018. Avista's facilities group considered four options
 40 for securing a hangar for the aircraft, which included building a new hangar, extending use of
 41 the current leased hangar, relocating to another airport, and co-use of an existing hangar. The
 42 solution to construct a hangar on land leased from the Spokane International Airport was
 43 selected for several reasons, including the location, site security, cost, efficiency and cost of

³⁹ The line school is a long-standing partnership between Avista and Spokane Community College (SCC).

1 aircraft maintenance, and operational safety and efficiency. The failure to make this
 2 investment in the timeframe planned will require Avista to adopt an alternative from among
 3 those already evaluated and determined to be inferior.

4
 5 **New Deer Park Service Center -2017: \$6,000; 2018: \$6,247,000**

6 This planned investment is to construct a new replacement service center on a vacant 10-acre
 7 parcel located in a new Local Improvement District created by the city of Deer Park. The
 8 existing service center is staffed by ten Avista field crews and administrative support
 9 employees, and supports both electric and gas operations for approximately 16,500 customers
 10 in the Deer Park and surrounding area, including Colbert, Chattaroy, Elk, and Loon Lake. This
 11 facility is also an important base for our local operations during major storm events in north
 12 Spokane and Stevens Counties. The existing Deer Park Service Center was constructed about
 13 1971, and many of its building components, systems, and equipment have deteriorated with
 14 age and must be replaced. In 2012, The Deer Park Service Center scored the third lowest in
 15 the Company's 2012 survey of its facilities based on overall asset condition. There are also
 16 environmental concerns with the existing site and the facility is undersized for modern line
 17 truck and service vehicles, which have grown considerably in length since Avista's 1970 fleet.
 18 As a result we must currently leave several of these expensive vehicles parked outside on a
 19 permanent basis. The failure to replace this service center in the timeframe planned will result
 20 in the continuation of our current efficiency limitations, pose continuing environmental
 21 concerns, and will require increasingly greater capital and expense repairs of building systems,
 22 as well as structural modifications needed to continue operations.

23
 24 **New Pullman Service Center -2020: \$7,600,000**

25 This planned investment includes replacement of the existing service center on a new site, and
 26 includes construction of an associated warehouse and materials yard. The Pullman Service
 27 Center was constructed in 1959, and has been upgraded, remodeled and added onto over the
 28 succeeding decades to accommodate changing operations and business needs. The existing
 29 center is confined and cannot provide adequate materials storage, has numerous building
 30 issues, and environmental concerns and limitations resulting from poor storm water treatment
 31 at the site and runoff from the adjacent highway. The interior of the main building is in need
 32 of reconstruction or renovation. The building does not comply with current codes and ADA
 33 requirements. Many of the internal building systems have reached the end of their useful life,
 34 and the existing septic drain field is saturated causing the system to back up. Other continuing
 35 issues include continuing problems with the sump pump system, and all of the vehicle roll-up
 36 doors must be replaced. In addition to the above, failure to make this planned investment will
 37 result in the Company having to forego the benefits of having environmentally safe and
 38 adequate storage for transformers, poles, and all other materials inventory, the efficiency
 39 benefits associated with centralizing all operations functions at one location, and the
 40 efficiency provided by a design and capacity needed for our operations today and into the
 41 future.

42
 43 **Q. Are there additional infrastructure projects planned for the period 2017**

44 **– 2021 that have not been previously addressed in your testimony?**

A. Yes. Two additional projects are listed in Table No. 5, and are briefly described in my testimony below.

Table No. 5

Other Capital Projects (System) In \$(000's)					
Business Case Name	2017	2018	2019	2020	2021
Asset Condition					
Fleet Budget	\$ 7,898	\$ 7,850	\$ 7,850	\$ 7,850	\$ 7,850
Mandatory and Compliance					
Jackson Prairie Storage	1,718	1,562	1,483	1,478	1,483
	\$ 9,616	\$ 9,412	\$ 9,333	\$ 9,328	\$ 9,333

Asset Condition

Fleet Capital Replacement Program -2017: \$7,898,000; 2018: \$7,850,000; 2019: \$7,850,000; 2020: \$7,850,000; 2021: \$7,850,000

Avista’s replacement of its service vehicles and heavy equipment is based on the analysis of total life cycle costs, optimized to achieve the lowest total cost of ownership. To perform this analysis, the Company relies on the “Vehicle Replacement Model” provided by Utilimarc. The model uses benchmarking information, purchase and auction sales data, combined with a range of nationwide vehicle statistics, to produce a robust estimate of the optimum timing for replacement of vehicles based on its residual value, the maintenance required to keep the vehicle in service, and the cost of a replacement. Capital project requests are created for each vehicle and piece of equipment to be replaced and the prioritization of projects is based on minimizing our overall business risk and costs of ownership. This approach to replacing assets based on condition, prior to its likely failure, has helped the Company avoid numerous incidents of vehicles failing while in service, resulting in extended vehicle and crew down time, high cost for parts and labor required for emergency repairs, and unplanned replacements. These costly incidents would be the result if the Company were to fail to make the investments in its service vehicles and equipment planned during this timeframe.

Mandatory and Compliance

Jackson Prairie Storage -2017: \$1,718,000; 2018: \$1,562,000; 2019: \$1,483,000; 2020: \$1,478,000; 2021: \$1,483,000

These projects include various capital improvements that Avista and its partners will complete at the Jackson Prairie facility. The Company is one-third owner in the Jackson Prairie Storage Facility and as such, is a part of the Jackson Prairie Storage Management Committee that meets annually to discuss and approve the capital and O&M projects needed for this facility. The Company’s failure to make these investments in the timeframe planned would place us in violation of the joint owners’ agreement to make these needed investments.

1 **Q. Please provide some examples of General Plant Capital projects that were**
2 **not approved at the requested amount, and the risk associated with not completing or**
3 **deferring these projects.**

4 A. In 2015 and 2016, capital tools and equipment requests exceeded what was
5 funded by approximately \$800,000 each year. (see Exh. HLR-6 under the Capital Tools
6 Business Case Justification Narrative). Capital tool requests are prioritized by safety and
7 compliance, replacement, and enhanced productivity. When the budget needs to be reduced,
8 reductions are first made to requests in the category of enhanced productivity, then
9 replacement. Replacement is intended to replace aging units to achieve more predictable
10 capital requirements and avoid replacement peaks caused by large-scale failures. Cutting into
11 these requests over an extended period could lead to reduced efficiency and have safety
12 impacts. All construction, maintenance, and repair work performed at Avista is dependent on
13 the use of capital tools and equipment. Without the necessary equipment, workers cannot
14 perform their duties safely or efficiently, and Avista facilities and equipment could no longer
15 be maintained.

16 The Facilities Structures and Improvements program funds the capital maintenance, site
17 improvement, and furniture budgets at Avista's offices, storage buildings, and service centers.

18 This program is intended to address the following needs:

- 19 • Lifecycle asset replacements (examples: roofing, asphalt, electrical, plumbing);
- 20 • Lifecycle furniture replacements and new furniture additions (to support growth);
- 21 and
- 22 • Business additions or site improvements (examples: adding a welding bay, vehicle
23 storage canopy, expanding an asphalt yard, and can sometimes include property
24 purchases to support site expansions.)

1 Lifecycle asset replacements are typically funded first, with furniture replacements and
2 business site improvement requests taking a lower priority. Each year, requests for funding
3 through this program far exceed available funds. In 2017 we funded \$3.3 million of \$7.4
4 million in requested projects. In 2016, requests totaled \$6.3 million and we funded \$3.6. In
5 2015, requests totaled \$9.8 million, and we funded \$4.6 million.

6 Sites decline due to normal wear and tear. The failure of certain systems, such as
7 roofing or HVAC, can cause major damage to other areas of the building. Walkways and
8 structural issues not being addressed could have safety impacts to employees, visitors and
9 customers.

10 Replacement is intended to replace aging units to achieve more predictable capital
11 requirements and avoid replacement peaks caused by large-scale failures. Cutting into these
12 requests over an extended period could lead to reduced efficiency and have safety impacts.
13 Business site improvement requests are intended to address changing business needs. These
14 projects are usually linked to an enhanced productivity outcome. Having the ability to
15 incorporate structures and equipment that fall within the improvement and business needs
16 category can help support improved processes and lead to enhanced safety and longer
17 lifecycles.

18 **Q. Does this conclude your pre-filed direct testimony?**

19 A. Yes.