EXH. RBB-8 DOCKETS UE-22___/UG-22__ 2022 PSE GENERAL RATE CASE WITNESS: ROQUE B. BAMBA

BEFORE THE WASHINGTON UTILITIES AND TRANSPORTATION COMMISSION

WASHINGTON UTILITIES AND TRANSPORTATION COMMISSION,	
Complainant,	
v.	Docket UE-22 Docket UG-22
PUGET SOUND ENERGY,	
Respondent.	

SEVENTH EXHIBIT (NONCONFIDENTIAL) TO THE PREFILED DIRECT TESTIMONY OF

ROQUE B. BAMBA

ON BEHALF OF PUGET SOUND ENERGY



TONO SUBSTATION Annual Budget Record Corporate Spending Authorization (CSA)

Date Submitted:	6/4/2021				
Officer Sponsor:	Dan Koch				
Project Director:	Roque Bamba				
Responsible Cost Center:	4022				
I. <u>Project Overview</u>					
Business Need:	One of the single phase 500-115kV transformers (XFR 0473) at Tono Substation is nearing failure with an estimated remaining service life of twelve months with no available spare transformer. The other two single phase transformers currently in service are also showing signs of failure with an estimated remaining service life of five years. If one or more of the Tono Substation transformers fail, a long term outage would occur due to the 12+ month lead time of this non-standard equipment. Transformer 0473 was the spare, but it was placed into service in October 2018 following the failure of transformer 0470 in September 2018.				
	To compound the issue:				
 Power flow contingency analysis simulations show a long ter outage of the Tono substation EHV source (via the transform can significantly degrade reliability, resiliency and operability the electric grid in Thurston County and neighboring electric systems; Tono substation has additional maintenance concerns due to aged infrastructure equipment operating beyond their recommended service life; Though grandfathered from policies effective after the substate went into service, the substation is non-compliant with currer IEEE 979 (spacing between the transformers) and environment policies (no spill prevention counter measures in-place). 					
Proposed Solution:	The preferred solution consists of replacing the aging transformers with two new three-phase 500-115 kV transformers with one as a spare and additional substation work to remediate the aging infrastructure.				
Project Outcome/Results:	 The proposed solution will: Solve the asset management need for a spare transformer and low voltage concerns in south Thurston County. Solve aging infrastructure concerns by replacing two 115 kV oil circuit breakers with SF6 circuit breakers, replace all protection relays and faulty control cables as they are all operating beyond their expected service life. 				
OCM, Process & Training					
Impact:	NA				
Primary ISP Alignment:	Processes & Tools ISP strategy descriptions				

Page 1 Version 6.0

Exh. RBB-8 2 of 3

ISP Strategy Description: Process & Tools - System reliability and integrity

Portfolio Description: Risk Mitigation Capital Allocation Definitions

Project Complexity: ☐ Straightforward and ☐ Complex and well understood well understood ☐ Complex and not well articulated

II. Key Schedule and Financial Information

Expected Start Date If Funded:	Q2 of 2020
Expected In-Service Date:	Q4 of 2022

High-Level Schedule 2 years

		Duration		
Planning	Design	Execution	Total Project	Anticipated Closeout date
2 months	12-18 months	6 months	24 months	10/2022

Initial Estimated Funding by Phase as of 04/8/2020:

Initiation	Planning	Design	Execution	Closeout	Total
2.5%	5%	10%	80%	2.5%	\$17 million

Initial Grand Total Estimate	Capital: \$17-26 million	
(contingency included):	(initial planning estimate from	OMRC/Project O&M: \$0
Contingency Standard	solutions report)	

Estimated Five Year Allocation:

Category:	Lifetime Actuals	2021	2022	2023	Total
Capital (contingency included)	\$600,000	\$600,000	\$15,500,000	\$300,000	\$17,000,000
OMRC / Project O&M	\$0	\$0	\$0	\$0	\$0

III. Ongoing Benefits:

Summary Benefits:	 Maintain reliability and integrity of Tono Substation and South Thurston County. Having direct tie between BPA - CW Paul and Tono saves PSE approximately \$7 million a year in wheeling fees for Centralia Generation. Main source into South Thurston County bulk electric system. Eliminates aging infrastructure concerns by replacing equipment past its
	expected service life.
	 Solves the asset management need for a spare transformer.
	 Provides voltage support during certain outage conditions.

Category:	2019	2020	2021	2022	2023	Total
Ongoing O&M (to be funded by	NA	NA	NA	NA	NA	NA
business)						

Page 2 Version 6.0

Exh. RBB-8 3 of 3

Ongoing O&M (requesting \$'s)	NA	NA	NA	NA	NA	NA
Ongoing Capital (Capital Tail)	NA	NA	NA	NA	NA	NA
Benefits	NA	NA	NA	NA	NA	NA
Net impact (= Benefits – O&M)	NA	NA	NA	NA	NA	NA
* Payback in Years	Years = Total Costs / Annual Cash Benefits					

^{*} Enter positive amount or Not Applicable

IV. Risk Management Summary

Summary of high level risks sentence:	All three of the existing transformers at Tono Substation are operating beyond their expected service life with one transformer nearing failure with an estimated remaining service life of twelve months. If one of the transformers fails, there are no available spares, and this would cause a long term outage to occur.
---------------------------------------	---

V. Phase Gate Change Summary

Phase:	Initiating to Planning
Scope:	Replace the existing three single phase transformers with two new three phase transformer and address additional concerns due to aging infrastructure concerns.
Budget:	\$17-26 million (Note: The previous CSA that was approved in May 2020 was intended to be used for the 5 year budget planning process only. The project has since completed the initiation phase with updated costs which are reflected in this CSA).
Schedule:	Energize Tono Substation by 2022
Benefits:	No change to the benefits with this phase gate change.

Prepared by:

VI. CSA Approvals

Project Phase	Initiation to Planning			
Approved By	Title	Role	Date	Signature
Tony Pagano	Manager Project Management	Manager	June 17, 202	Tony Pagano
Roque Bamba	Director Project Delivery	*Director Sponsor	June 21, 202	C7D3BC09443BAAC DocuSigned by: Kozw Bamba BC203E4E58BB426

^{*}Director Sponsor attests that all considered documentation has been approved.

Page 3 Version 6.0