

**EXH. RBB-1T
DOCKETS UE-22 ___/UG-22 ___
2022 PSE GENERAL RATE CASE
WITNESS: ROQUE B. BAMBA**

**BEFORE THE
WASHINGTON UTILITIES AND TRANSPORTATION COMMISSION**

**WASHINGTON UTILITIES AND
TRANSPORTATION COMMISSION,**

Complainant,

v.

PUGET SOUND ENERGY,

Respondent.

**Docket UE-22 ___
Docket UG-22 ___**

PREFILED DIRECT TESTIMONY (NONCONFIDENTIAL) OF

ROQUE B. BAMBA

ON BEHALF OF PUGET SOUND ENERGY

JANUARY 31, 2022

PUGET SOUND ENERGY

**PREFILED DIRECT TESTIMONY (NONCONFIDENTIAL) OF
ROQUE B. BAMBA**

CONTENTS

I. INTRODUCTION1

II. PSE’S OPERATIONS DELIVERY APPROACH.....3

III. MAJOR BACKBONE INFRASTRUCTURE PROJECTS GREATER THAN \$10 MILLION THAT WERE PLACED IN SERVICE BETWEEN JANUARY 1, 2019 AND JUNE 30, 202113

 A. Lake Hills – Phantom Lake Transmission Line Project13

 B. Bellingham Substation Project.....17

 C. Tacoma LNG Project Distribution Upgrades21

IV. MAJOR BACKBONE INFRASTRUCTURE PROJECTS THAT WILL BE PLACED IN SERVICE BETWEEN JULY 1, 2021 AND DECEMBER 31, 2025.....26

 A. Sammamish – Juanita 115kv Transmission Line Project27

 B. Electron Heights – Enumclaw 55/115kV Conversion Project.....31

 C. Bainbridge Island Project.....34

 D. Tono Substation Project.....38

 E. Lynden Substation42

 F. Sedro Woolley – Bellingham #4 115kV46

 G. Vashon – Gig Harbor Long Term Solution Project.....49

V. CONCLUSION.....52

PUGET SOUND ENERGY

**PREFILED DIRECT TESTIMONY (NONCONFIDENTIAL) OF
ROQUE B. BAMBA**

LIST OF EXHIBITS

- | | |
|-------------|---|
| Exh. RBB-2 | Professional Qualifications of Roque B. Bamba |
| Exh. RBB-3 | Lake Hills – Phantom Lake 115kV Transmission Line
CSA |
| Exh. RBB-4 | Bellingham Substation CSA |
| Exh. RBB-5 | Sammamish – Juanita 115kV Transmission Line CSA |
| Exh. RBB-6 | Electron Heights – Enumclaw 55/115 Conversion CSA |
| Exh. RBB-7 | Bainbridge Island CSA |
| Exh. RBB-8 | Tono Substation CSA |
| Exh. RBB-9 | Lynden Substation CSA |
| Exh. RBB-10 | Sedro Woolley - Bellingham #4 115kV Mid-Phase
Change Request |
| Exh. RBB-11 | Vashon – Gig Harbor Long Term Solution CSA |

1 **PUGET SOUND ENERGY**

2 **PREFILED DIRECT TESTIMONY (NONCONFIDENTIAL) OF**
3 **ROQUE B. BAMBA**

4 **I. INTRODUCTION**

5 **Q. Please state your name, business address, and position with Puget Sound**
6 **Energy.**

7 A. My name is Roque B. Bamba. My business address is 355 110th Ave. NE,
8 Bellevue, WA 98004. I am the Director of Project Delivery with Puget Sound
9 Energy (“PSE” or the “Company”).

10 **Q. Have you prepared an exhibit describing your education, relevant**
11 **employment experience, and other professional qualifications?**

12 A. Yes, I have. Please see Exh. RBB-2.

13 **Q. Please describe your responsibilities as Director of Project Delivery.**

14 A. I am responsible for overseeing the management and execution of capital
15 infrastructure projects and programs within PSE’s Operations organization.
16 Project Delivery is comprised of Major Projects, Infrastructure Program
17 Management, AMI Program, and Project Controls. My responsibilities include
18 providing for safe and effective delivery of PSE’s infrastructure projects and
19 programs, resolution of complex operational challenges, and project-related
20 customer and stakeholder inquiries. Additionally, I am responsible for adherence
21 to and ongoing refinement of PSE project and program governance standards and
22 policies. In my role, I work closely with PSE System Planning, Engineering,

1 Finance, Accounting, and Regulatory so projects and programs are well-
2 coordinated among all stakeholders.

3 **Q. Please summarize the purpose of this prefiled direct testimony.**

4 A. My testimony provides an overview of how PSE manages the capital
5 infrastructure projects and programs needed to deliver safe, reliable, and
6 affordable energy to customers. I describe the methodical approach that guides
7 PSE project and program management and how through this approach, PSE
8 invests customer funds wisely and optimizes the benefits flowing from each
9 project or program selected for development and execution. I also describe how
10 optimizing benefits may, from time to time, require PSE to alter the way projects
11 and programs are sequenced to reflect unexpected conditions that unfold naturally
12 in the course of PSE's operations, such as unanticipated weather events, new
13 economic development needs, and emerging public policy priorities.

14 I then describe how PSE's methodology applies in practice by discussing certain
15 major projects in greater detail. I explain that differences in project and program
16 profiles imply the need for limited and reasonable modifications to PSE's general
17 project and program management methodology. I illustrate the need for flexibility
18 in applying project and program management structures.

19 **Q. What is PSE requesting in your testimony?**

20 A. PSE is requesting recovery of costs associated with the three major backbone
21 infrastructure projects with capital costs greater than \$10 million placed in service
22 between January 1, 2019 and June 30, 2021: i) Lake Hills – Phantom Lake 115kV

1 Transmission Line; ii) Bellingham Substation; and iii) distribution upgrades
2 related to Tacoma Liquid Natural Gas (“LNG”) project. My testimony describes
3 these projects and the prudence of investing in them.

4 In addition, my testimony provides an explanation for PSE’s need for flexibility
5 in applying capital and Operating and Maintenance (“O&M”) budgets to
6 fulfilment of our public service obligations over the multiyear rate plan. This
7 flexibility is crucial for PSE to provide safe and reliable utility service.

8 **II. PSE’S OPERATIONS DELIVERY APPROACH**

9 **Q. Please describe how PSE is organized to plan and manage work.**

10 A. There is significant and necessary collaboration between many functions within
11 PSE to plan and manage work. For planned discretionary work, PSE’s Project
12 Delivery organization, which I oversee, is responsible for executing discretionary
13 plans and performing project and program management to deliver plans on
14 schedule, scope, and budget. PSE’s Delivery System Planning organization, led
15 by Catherine A. Koch, is responsible for monitoring, identifying, and analyzing
16 delivery system needs and building solutions that address performance issues and
17 identified needs. Ms. Koch describes PSE’s Delivery System Planning process in
18 her Prefiled Direct Testimony, Exh. CAK-1T.

19 **Q. Please explain projects and programs at a high level.**


20 A. PSE defines a project as a temporary endeavor undertaken to provide a unique
21 service or result. Projects are temporary and close down upon completion of the
22 work they were chartered to deliver. In contrast, PSE defines a program as the

1 coordinated organization, direction, and implementation of a collection of related
2 projects and complex activities which, when executed together, achieve outcomes
3 and realize benefits not available from managing them individually.

4 **Q. Please explain how PSE manages projects at a high level.**

5 A. PSE's project management process follows industry best practices and is based on
6 PSE's Infrastructure Project Lifecycle Phase/Gate Model ("Project Lifecycle
7 Model"), which includes five phases: Initiation, Planning, Design, Execution, and
8 Close-out. For a given project, each phase includes deliverables to provide that
9 scope, schedule, and budget are controlled, risks are managed, benefit realization
10 plans are updated, and the overall solution is re-evaluated as the project
11 progresses through each phase by way of phase gate approvals. The Project
12 Lifecycle Model is designed to deliver consistency and scalability. Guided by the
13 Project Lifecycle Model, each project maintains ongoing governance
14 documentation in the form of Corporate Spending Authorizations ("CSA") and
15 Project Change Requests. The PSE Project Lifecycle Model is illustrated in
16 Figure 1, below.

Figure 1: PSE Project Lifecycle Model



Q. Please explain how PSE manages programs at a high level.

A. PSE’s program management process follows industry best practices and is based on PSE’s Infrastructure Program Management model. This methodology includes deliverables to provide that scope, schedule, and budget are controlled, risks are managed, and benefits are optimized as a portfolio on an ongoing basis. Robust project controls are in place to manage individual project costs, which are used by Program Management to optimize portfolio benefits. An example of PSE’s Program Management capability is the Gas Cost Recovery Mechanism, which includes programs such Dupont Pipe Replacement where PSE has consistently delivered on plan since its inception.

1 **Q. Does PSE’s project and program management methodology align with**
2 **industry standards?**

3 A. Yes. PSE’s methodology for managing and overseeing projects and programs is
4 based on guidance from industry best practices, PSE Enterprise Program
5 Management Organization standards, and the Project Management Institute
6 (“PMI”), which is a professional association for project professionals worldwide
7 and a leading authority on project management approaches. The PMI maintains a
8 resource called the Project Management Book of Knowledge (“PMBOK”) that
9 serves as a standard and is used widely across many industries.

10 PSE’s Project Lifecycle Model approximates the flow of project development that
11 the PMI advises. For example, project development actions that take place in the
12 Initiating, Planning, and Design phases of PSE’s projects align with practices
13 described in the PMBOK’s Initiation and Planning project phases. PSE’s
14 Execution-phase project development encompasses the activities described in the
15 PMBOK Execution, Monitoring, Controlling, and Close-out phases. This includes
16 rigorous project oversight so that PSE projects are managed to mitigate risk
17 effectively, that contractor performance meets or exceeds expectations, and to
18 optimize benefits that result from the Company’s investments. In addition, PSE’s
19 methodology contains extensive communications and governance guidance so
20 that project and Company executive management are apprised of challenges as
21 they arise so that decisions can be made, and issues addressed quickly and
22 efficiently.

1 **Q. Please describe PSE's Project Lifecycle Model in more detail.**

2 A. The Project Lifecycle Model provides a consistent and scalable framework and
3 governance model for managing a wide range of infrastructure projects. This
4 methodology provides that PSE consistently applies project management best
5 practices, governance, and the appropriate level of rigor and oversight based on
6 the complexity and overall risk of each project.

7 **Q. Is this methodology applied rigorously for every Operations project that PSE**
8 **undertakes?**

9 A. This model is generally applied for every major project PSE pursues. However,
10 each project has unique characteristics and may require specific means and
11 methods to address the project's needs. Projects may have varying degrees of
12 initiation, planning, design, and execution project management as required for
13 successful mitigation of delivery risk.

14 **Q. Please describe what features would cause PSE to apply the Project Lifecycle**
15 **Model in a manner that deviates from the Company standard.**

16 A. Some large projects are so unique that they require additional rigor and a highly
17 customized approach. For example, PSE's Tacoma LNG project, the Energize
18 Eastside transmission project, and the Baker River Hydro regrouting project are
19 major capital projects with sophisticated engineering needs and correspondingly
20 complex procurement and contractor oversight requirements. Please see the
21 Prefiled Direct Testimony of Ronald J. Roberts, Exh. RJR-1CT, for a detailed
22 description of the Tacoma LNG project. Please see the Prefiled Direct Testimony

1 of Dan'l R. Koch, Exh. DRK-1CT, for a comprehensive discussion of the
2 Energize Eastside Project. And please see the Prefiled Direct Testimony of Ryan
3 P. Blood, Exh. RPB-1T, who discusses PSE's plans concerning the refurbishment
4 of the Baker River Hydro facility in his testimony. Such projects receive
5 additional scrutiny and management attention.

6 **Q. Please describe what happens in PSE's Initiation Phase of project**
7 **development.**

8 A. During the Initiation Phase of the PSE Project Lifecycle Model, PSE evaluates
9 and confirms the project's need, analyzes alternatives including, when feasible,
10 non-wires options, and recommends a specific solution that accounts for risks in
11 execution, benefits that will be achieved, and associated costs. A Project Manager
12 ("PM") and team are assigned, and a preliminary scope is developed. This
13 preliminary scope consists of a project description and "Work Breakdown
14 Structure" that defines the key objectives and any interdependencies. At this point
15 in a project, the costs are typically estimated using a range that reflects the
16 considerable uncertainty, i.e., -50 to +100 percent.

17 **Q. Please describe what happens in PSE's Project Planning Phase of project**
18 **development.**

19 A. The PM assigned to a project leads a rigorous project implementation planning
20 process throughout the project Planning Phase of the PSE Project Lifecycle
21 Model. This involves detailed scope definition, identification of engineering,
22 permitting, and resource needs; assembly of a team with representation from

1 various corporate areas with project expertise; and the development of a
2 communications plan so that internal and external stakeholders are apprised of
3 project development milestones and challenges.

4 **Q. Please describe what happens in PSE’s Design Phase of project development.**

5 A. PSE’s Design Phase includes detailed engineering design with typical reviews
6 including constructability at 30, 60 and 90 percent engineering design completion
7 milestones. This stage of project development is when procurement activities
8 begin to significantly inform the Project Implementation Plan (“PIP”). The PIP
9 documents all aspects of the project plan and is maintained throughout the project
10 lifecycle. When necessary, PSE defines commercial and contracting strategies and
11 conducts market outreach to determine whether there is sufficient competition to
12 hold a competitive procurement for contracted support.

13 In addition, during the Design Phase, the PM pursues and secures all necessary
14 environment and land use permits and Rights of Way (“ROW”). With all permits
15 and ROWs established, the PM documents project and program plans and seeks
16 PSE management approval to proceed to the Execution Phase. At this point, a
17 project’s scope is understood to a much greater degree than in earlier phases.

18 Project costs for known and knowable scope can be estimated to within
19 approximately 15 percent by the close of the Design Phase and is considered the
20 baseline lifetime budget. Contingency budgets are also set at approximately 15
21 percent of cost estimates to reflect remaining uncertainty.

1 **Q. Please describe what happens in PSE's Execution Phase of project**
2 **development.**

3 A. The Execution Phase of the project is focused on contractor selection,
4 construction, and commissioning activities. Procurements for contractor services
5 and professional support are conducted in a manner consistent with PSE's
6 procurement guidance at the beginning of the Execution Phase. Please see the
7 Prefiled Direct Testimony of Dawn M. Reyes, Exh. DMR-1T, for a detailed
8 description PSE's Procurement process. The project team works closely with
9 PSE's Procurement team throughout the contractor selection process and makes a
10 final award recommendation to PSE Management. Construction activities are
11 initiated once the contract has been awarded and fully executed. Throughout
12 construction, all project risks are actively managed and associated oversight
13 mechanisms are in place. These include onsite Environmental Managers,
14 Construction Managers, Quality Assurance and Quality Control, and materials
15 testing necessary to insulate the project and customers from construction activity
16 risks. Once the construction work is complete, PSE conducts all necessary testing
17 and commissioning activities, and the project is placed in service.

18 **Q. Please describe what happens in PSE's Close-out Phase of project**
19 **development.**

20 A. In this phase, the asset and all supporting documentation are officially transferred
21 to the appropriate business owners and all project records are reviewed and filed
22 for future reference. Any open action items, punch lists, or ongoing program-level

1 activities can be officially closed or assigned to the appropriate support
2 organization.

3 **Q. Are projects ever re-prioritized?**

4 A. Yes. Projects are part of the broader PSE portfolio and are subject to re-
5 prioritization or re-sequencing which may result in deferring project activities for
6 a period of time. Additionally, projects may be re-prioritized as the result of
7 external factors such as unexpected weather conditions, permitting delays, public
8 opposition, legal challenges, or broader economic circumstances.

9 Successful program management requires the flexibility to adjust for individual
10 project variability by continuously monitoring and adjusting projects so that
11 emergent needs are met and program-wide benefit targets are achieved. PSE's
12 program management methodology is structured to make necessary adjustments
13 for impacts that delay individual projects and affect the program benefit targets.

14 This kind of reprioritization is common due to unexpected events such as weather
15 anomalies or other exogenous factors that cannot be accurately predicted. The
16 Prefiled Direct Testimony of Joshua A. Kensok, Exh. JAK-1T, discusses how the
17 Company's financial management and associated governance practices address
18 this kind of challenge. PSE's project/program management approach is similarly
19 designed to be flexible to allow PSE to quickly and effectively respond to
20 unexpected events when they occur. For example, in the event a specific program
21 focused on reliability benefits experiences disproportionate impacts related to

1 external factors, PSE will evaluate, reprioritize, and accelerate other programs
2 focused on reliability benefits so that overall benefits are achieved.

3 **Q Please describe Program Management cost controls.**

4 A. Infrastructure Program Management conducts budgetary cost estimates with a
5 basis and level of granularity that is particular to the project maturity at the time
6 of the estimate.

7 Costs basis typically include historic estimates, which are used at an early level of
8 project maturity, and detailed estimates, which are used when the project design is
9 nearly complete or at completion. A historic-based estimate is predicated on an
10 average of comprehensive actualized costs per high-level scoping unit (mileage,
11 quantity of structures, etc.) of past projects with a percentage multiplier to account
12 for relative complexity and risk.

13 A detailed estimate is based on a robust database of typical cost items, including
14 hourly rates from different roles throughout the Company, material cost items,
15 consultant support, and construction crew contract rates.

16 The level of project maturity and cadence for which estimates are conducted can
17 vary between programs depending on the complexity of budgeting the projects
18 within the program's portfolio.

1 **III. MAJOR BACKBONE INFRASTRUCTURE PROJECTS GREATER**
2 **THAN \$10 MILLION THAT WERE PLACED IN SERVICE BETWEEN**
3 **JANUARY 1, 2019 AND JUNE 30, 2021**

4 **Q. Please describe the major backbone infrastructure projects with capital costs**
5 **greater than \$10 million placed in service between January 1, 2019 and June**
6 **30, 2021.**

7 A. There are three major backbone infrastructure projects with capital costs greater
8 than \$10 million placed in service between January 1, 2019 and June 30, 2021: i)
9 Lake Hills – Phantom Lake 115kV Transmission Line; ii) Bellingham Substation;
10 and iii) distribution upgrades related to Tacoma LNG project. For each project,
11 my testimony describes the need, alternatives considered, how management was
12 informed, and any major changes during the project lifecycle following the
13 project management process described above.

14 **A. Lake Hills – Phantom Lake Transmission Line Project**

15 **Q. Please describe the Lake Hills – Phantom Lake 115kV Transmission Line**
16 **project.**

17 A. The Lake Hills – Phantom Lake 115kV Transmission Line project is located in
18 east Bellevue in central King County. The project consisted of installing 2.5 miles
19 of new 115 kV transmission line extending from the Lake Hills substation to the
20 Lakeside – Phantom Lake transmission line. This eliminates three substations
21 from being radially fed and provides increased reliability in the Bellevue-
22 Redmond area. Exh. RBB-3 contains the CSA for the Lake Hills – Phantom Lake
23 115kV Transmission Line project.

1 **Q. Is Lake Hills – Phantom Lake 115kV Transmission Line project operating**
2 **and providing service to customers?**

3 A. Yes.

4 **Q. What was the timeline for the completion of Lake Hills – Phantom Lake**
5 **115kV Transmission Line project?**

6 A. This project was initiated in 2006. After engaging the neighboring communities
7 on route alternatives, PSE moved forward with Lake Hills – Phantom Lake
8 115kV Transmission Line project in 2011 by starting the City of Bellevue
9 permitting process. 2011 through 2019 was spent on permitting and easement
10 acquisition. Work associated with the Lake Hills – Phantom Lake 115kV
11 Transmission Line project was completed and placed in service October 2020
12 with final site restoration to be completed in early 2022.

13 **Q. What was the final cost of Lake Hills – Phantom Lake 115kV Transmission**
14 **Line?**

15 A. The cost of the project was \$15.9 million without allowance for funds used during
16 construction (“AFUDC”) as of July 1, 2021. PSE recovered \$5 million in the
17 2019 general rate case. Final mitigation and closeout costs are expected to be an
18 additional \$4.15 million resulting in an overall cost of \$20.1 million.

19 **Q. Describe the system need for Lake Hills – Phantom Lake 115kV**
20 **Transmission Line.**

21 A. The primary need for the project was to improve the reliability of the Phantom
22 Lake, Lake Hills, and College substations which are serving a total of over 12,000

1 customers. Each substation was fed radially. Any transmission outage on the
2 radial feeds resulted in an extended outage to one or two of these substations. The
3 larger area between Redmond and Eastgate along the west side of Lake
4 Sammamish also benefited from the new transmission line. Six substations
5 serving 23,000 customers were served by an existing transmission line. The line
6 resulted in a third feed to Ardmore, connecting Ardmore to the Lakeside
7 Switching Station, allowing for automated switching between the Sammamish
8 and Lakeside substations and increasing reliability for these six substations.

9 **Q. Describe the alternatives evaluated and how this solution was chosen.**

10 A. Two alternatives, including the selected alternative, were evaluated. PSE's
11 solution criteria required all identified needs be addressed, specifically the
12 customer reliability objectives and PSE's long-term transmission reliability
13 objectives in the Bellevue-Redmond area.

- 14 1. **Construct Westminster Switching Station and a new Pickering –**
15 **Phantom Lake 115kV Line** – This alternative considered construction of
16 a new Westminster switching station and building a new six mile
17 transmission line from the existing Pickering substation to the Phantom
18 Lake substation. This alternative was rejected because it did not meet the
19 reliability objectives, and the Lake Hills – Phantom Lake line would
20 inevitably still be needed to relieve loading issues and maintain reliability
21 in the Bellevue-Redmond area.
- 22 2. **Construct a new 115kV line between the Lakeside – Phantom Lake**
23 **Line and Lake Hills Substation** – This alternative was selected because
24 it fully met the project needs of transmission reliability. The new line
25 limited the customer outages for the 12,000 customers served by the three
26 substations. This also supported the long-term planning efforts for the
27 Bellevue-Redmond area with a full automatic switching scheme from the
28 Sammamish to Lakeside substations resulting in reliability improvements
29 for six substations.

1 **Q. What benefits does the Lake Hills – Phantom Lake 115kV Transmission Line**
2 **provide for customers?**

3 A. This project improved reliability for over 12,000 customers by adding a second
4 feed to each of the three radially fed substations and improved bulk power supply
5 reliability by adding a third feed to Ardmore substation.

6 **Q. Describe how PSE kept management informed during this project.**

7 A. Using PSE's Project Lifecycle Model, management provided review and
8 approvals for the project. This project was reviewed by management to proceed to
9 the project design phase in June 2014. The project was approved for construction
10 funding in 2019. However, due to permitting delays, construction did not start
11 until 2020 which was also communicated to and approved by management. The
12 Lake Hills – Phantom Lake 115kV Transmission Line project was tracked within
13 PSE's Strategic Project Portfolio and Project Change Request processes
14 throughout the execution phase of the project.

15 **Q. Were there any material changes that impacted the project scope, schedule**
16 **or budget? If so, describe.**

17 A. Yes. At the execution approval, the estimate was \$13.2 million without AFUDC.
18 The major changes to the project that increased the cost from \$13.2 million to the
19 estimated final expenditure of \$20.1 million are as follows:

- 20 • \$1.8 million for increased costs of necessary easements, legal
21 support of easement acquisition, transmission line design changes
22 to include engineered foundations, and increased consultant
23 support for additional trees that were identified for removal and the
24 associated permitting;

- \$600,000 for permit delays that impacted the schedule;
- \$1.2 million for design revisions to include installation of service to the motor operated transmission switches, permit conditions that required police traffic escorts for pole site delivery, COVID-19 “Stay Home, Stay Safe” orders that extended the construction schedule, and additional equipment necessary for vegetation removal; and
- \$3.2 million for increased landscape mitigation that was a result of plant availability and unforeseen permit conditions and increase in resources to address six new permits required to document changes to mitigation and restoration areas.

Q. Have the benefits from the Lake Hills – Phantom Lake 115kV Transmission Line been realized?

A. Yes. As described above, this project is providing improved operational flexibility and transmission reliability to approximately 12,000 customers in the Bellevue-Redmond area.

B. Bellingham Substation Project

Q. Please describe the Bellingham Substation project.

A. The Bellingham Substation project is located in the Bellingham area of Whatcom County. The Bellingham Substation project consisted of rebuilding the existing 115 kV switching station to a breaker-and-a-half bus configuration and included construction of a new station control house and perimeter fencing for station expansion. Exh. RBB-4 contains the CSA for the Bellingham Substation project.

Q. Is the Bellingham Substation project operating and providing service to customers?

A. Yes.

1 **Q. What was the timeline for the Bellingham Substation project?**

2 A. This project was initiated in 2006 with an anticipated need date of 2010. The
3 project was delayed due to: (i) a change in growth projections in 2009 caused by a
4 change in development plans for the area and (ii) the need to focus on another
5 capacity project. The project resumed in 2014 but was deferred for higher priority
6 reliability and capacity projects until 2018. The Bellingham Substation project
7 was completed and placed in service in July 2019.

8 **Q. What was the final cost of the Bellingham Substation project?**

9 A. The final cost of the project was \$27.8 million without AFUDC.

10 **Q. Describe the system need for the Bellingham Substation project.**

11 A. There were several needs for this project. First, the substation is the central
12 switching station for the region, and the layout of the previous substation created
13 reliability concerns that would cause loss of service to 20,000 customers and the
14 Encogen generating plant. Second, the capacity of several portions of the
15 substation infrastructure was not able to serve long term capacity needs for the
16 Bellingham area. Third, and more specifically, the capacity of the bus would be
17 beyond the NERC allowable limits for certain transmission system contingencies
18 (or outages) and anticipated load growth. Last, there is a significant amount of
19 aging infrastructure in the substation between degrading, low-capacity oil
20 breakers and electro-mechanical relays.

1 **Q. Describe the alternatives evaluated and how this solution was chosen.**

2 A. Four alternatives, including the selected alternative, were evaluated. PSE's
3 solution criteria required all identified needs be addressed.

4 1. **Rebuild bus to breaker-and-a-half configuration** – This alternative
5 consisted of constructing a breaker and a half bus configured substation in
6 the former Bellingham substation 55kV yard and demolishing the existing
7 Bellingham 115kV substation. This alternative was selected because it
8 fully met the project needs, including improved reliability in the
9 Bellingham area, met long-range capacity needs for the Bellingham area,
10 and addresses future capacity compliance.

11 2. **Rebuild bus with two bus section circuit breakers and an aux bus with**
12 **bus tie circuit breaker** – This alternative consisted of constructing a main
13 bus with two bus section circuit breaker and an auxiliary bus with a bus tie
14 circuit breaker in the former Bellingham substation 55kV yard. This
15 alternative was rejected because it did not offer the same reliability
16 benefits of a breaker-and-a-half configuration at a similar cost.

17 3. **Rebuild the existing 115kV substation** – This alternative consisted of
18 rebuilding both bus sections one bus section at a time and installing two
19 bus section breakers with a new auxiliary bus and bus tie circuit breaker.
20 This alternative was rejected because it offered lower reliability than the
21 selected option at a similar cost. This option also presented the added risk
22 of outage coordination during construction and building adjacent to
23 energized infrastructure.

24 4. **Do nothing** – This alternative consisted of not upgrading any portion of
25 the substation or replacing any aging infrastructure. This alternative was
26 rejected because it did not address any of the existing and future system
27 deficiencies.

28 **Q. What benefits does the Bellingham Substation project provide for**
29 **customers?**

30 A. This project improved Bellingham area reliability for 20,000 customers and the
31 Carolina substation is now connected to the new 115kV bus eliminating outages
32 for 4,236 customers. The improvement also allows for the future capacity needs
33 of expected growth in the Bellingham area.

1 **Q. Describe how PSE kept management informed during this project.**

2 A. Using PSE's Project Lifecycle Model, management provided review and approval
3 of the project. This project was reviewed by management in April 2015 to
4 proceed to the Design Phase. The project was also reviewed by management in
5 June 2016 to proceed to the Execution Phase. The Bellingham project was tracked
6 within PSE's Strategic Project Portfolio and Project Change Request processes
7 throughout the execution phase of the project.

8 **Q. Were there any material changes during execution that impacted the project
9 scope, schedule, or budget? If so, describe.**

10 A. Yes. Prior to execution, the project estimate was \$21.4 million without AFUDC.
11 The major changes to the project that increased the cost from \$21.4 million to the
12 actual expenditure of \$27.8 million are as follows:

- 13 • \$1.7 million for support of efforts related substantial permitting,
14 new substation security installations, updated costs for new control
15 house, updated costs for transmission pole foundation installations
16 and removal of existing spill prevention, and control and
17 countermeasures;
- 18 • \$3.2 million for increased costs associated with removal of
19 unsuitable soils and replaced with clean imported fill, design
20 revisions that required deeper foundations and associated
21 installation costs, removal of existing duct bank, additional conduit
22 due to inadequate existing asbestos concrete conduit and additional
23 grounding due to lack of existing grounding; and
- 24 • \$1.5 million for construction crew overtime to maintain
25 energization schedule, construction coordination, and safety watch
26 support for contractor installations.

1 **Q. Have the benefits from this project been realized?**

2 A. Yes. System reliability has been increased for the Bellingham substation and for
3 each of the nine interconnected substations. Aging infrastructure has been
4 removed from the stations prior to failure. This project also provided additional
5 station capacity on the 115kV bus meeting the needs of the Bellingham area and
6 NERC requirements.

7 **C. Tacoma LNG Project Distribution Upgrades**

8 **Q. Please describe the distribution upgrades related to the Tacoma LNG**
9 **project.**

10 A. The dual-use Tacoma LNG project at the Port of Tacoma was constructed for use
11 by PSE as a peak day resource for natural gas customers and by Puget LNG, a
12 subsidiary of Puget Energy, as a source of LNG for transportation fuel for the
13 maritime and trucking industries. There were three primary upgrades necessary to
14 connect the Tacoma LNG project to the PSE gas distribution system. First, four
15 miles of new piping and a meter station to connect the Tacoma LNG Facility to
16 the PSE natural gas distribution system. Second, the existing Frederickson Gate
17 Station was rebuilt. Third, one mile of 12-inch-high pressure piping was installed
18 along Golden Given Road East, and installation of the new Golden Given Limit
19 Station. Please see Roberts, Exh. RJR-1CT, for additional information about this
20 project.

21 **Q. Are all three upgrades operating and providing service to customers?**

22 A. Yes.

1 **Q. What was the timeline for distribution upgrades related to the Tacoma LNG**
2 **project?**

3 A. The three upgrades were planned for construction to be completed over the course
4 of three years with final completion in advance of the original in-service date for
5 the Tacoma LNG Facility, which was planned for early 2019. Construction of the
6 four miles of new piping was placed into service in October 2017. The meter
7 station was placed into service in December 2020. Construction of the
8 Frederickson Gate Station rebuild was completed and placed into service in
9 September 2017. Due to permitting delays related to the Tacoma LNG Facility,
10 construction of the one mile of 12-inch-high pressure piping and new Golden
11 Given Limit Station was deferred until 2020; those facilities were placed in
12 service in October 2020.

13 **Q. What was the final cost of the distribution upgrades related to the Tacoma**
14 **LNG project?**

15 A. The final cost of the distribution upgrade projects related to the Tacoma LNG
16 Facility is \$46.4 million without AFUDC. This includes \$30 million for the four
17 miles of new pipe and meter station connecting the Tacoma LNG Facility to the
18 PSE natural gas distribution system, \$4.1 million for the Fredrickson Gate Station,
19 and \$12.3 million for the one mile of 12-inch-high pressure piping and new
20 Golden Givens Limit Station. Consistent with Docket UG-151663,¹ the costs

¹ *In the Matter of the Petition of Puget Sound Energy, Inc. for (i) Approval of a Special Contract for Liquefied Natural Gas Fuel Service with Totem Ocean Trailer Express, Inc. and (ii) a Declaratory Order Approving the Methodology for Allocating Costs Between Regulated and Non-regulated Liquefied Natural Gas Services*, Docket UG-151663, Final Order 10 (Oct. 31, 2016).

1 related to the four miles of new pipe and meter station connecting the Tacoma
2 LNG Facility to the PSE distribution system were charged to the Tacoma LNG
3 Project costs. The costs of the Fredrickson Gate Station and the Golden Givens
4 Limit Station were charged to PSE distribution system costs. The Prefiled Direct
5 Testimony of Jon A. Piliaris, Exh. JAP-1T, provides further explanation of the
6 allocation of these costs between the Tacoma LNG project and the PSE
7 distribution system.

8 **Q. Describe the system need for distribution upgrades related to the Tacoma**
9 **LNG project.**

10 A. First, the four miles of new piping and meter station are utilized to supply natural
11 gas to the Tacoma LNG Facility for liquefaction and to transport vaporized
12 natural gas from the Tacoma LNG Facility to the distribution system. These four
13 miles of new piping and the meter station support both uses of the Tacoma LNG
14 Facility, PSE's use for system peaking and Puget LNG's use of LNG as
15 transportation fuel.

16 Second, prior to adding the peaking service to be provided by the Tacoma LNG
17 Facility, the Fredrickson Gate Station had a delivery capacity of 2,356,000
18 standard cubic feet per hour ("SCFH"). The peak design day required 92 percent
19 of this capacity, and the addition of the volumes for the Tacoma LNG Facility
20 would have exceeded the capacity of the Fredrickson Gate Station. This required
21 the Frederickson Gate Station to be rebuilt to serve 6,000,000 SCFH to meet
22 anticipated loads.

1 Finally, the Tacoma natural gas distribution system was served from the North
2 Tacoma high pressure line and the South Tacoma high pressure line. These two
3 lines operated independently, both serving limit stations that feed the remainder of
4 the North and South Tacoma distribution systems. The addition of the Tacoma
5 LNG Facility natural gas load would exceed the capacity of the North Tacoma
6 high pressure line unless reinforcement actions were taken to increase system
7 capacity. The installation of the 12-inch-high pressure line along Golden Given
8 Road East and the new limit station connect the North Tacoma high pressure line
9 and the South Tacoma high pressure line, allowing the South Tacoma high
10 pressure line to support more of the load and increase overall system capacity.
11 The need for the Fredrickson Gate Station and the new line and limit station
12 connecting the North Tacoma high pressure line to the South Tacoma high
13 pressure line was driven by the peaking service to be provided by the Tacoma
14 LNG Facility and therefore, benefit the PSE distribution system.

15 **Q. Describe the alternatives evaluated and how this solution was chosen.**

16 A. Two alternatives, including the selected alternative, were evaluated. PSE's
17 solution criteria required all identified needs to be addressed and met.

- 18 1. **Upgrade the North Tacoma supply system** – This alternative consisted
19 of upgrading the North Tacoma supply system by looping the existing
20 system with five miles of 16-inch pipe. This alternative also included the
21 four-mile pipeline to connect the Tacoma LNG project to the gas
22 distribution system. This alternative was rejected because of higher
23 estimated costs and additional risk of a river crossing and steep hill to
24 complicate construction.
- 25 2. **Increase capacity of the existing South Tacoma supply system** – This
26 alternative consisted of increasing capacity of the existing South Tacoma

1 supply system and providing a connection to the North Tacoma supply
2 system. In addition to the work already identified in the area, this
3 alternative would require the installation of a one-mile connector pipeline,
4 a pressure regulating station, and rebuild of the Frederickson gate station.
5 This alternative also included the four-mile pipeline to connect the
6 Tacoma LNG project to the gas distribution system. This alternative was
7 accepted because it was the most cost-effective solution.

8 **Q. What benefits do the distribution upgrades related to the Tacoma LNG**
9 **project provide for customers?**

10 A. The improvements made to the distribution system outside of the Port of Tacoma
11 improved existing low pressure issues in the Dupont, Steilacoom, University
12 Place and Fircrest areas. These upgrades also support PSE providing reliable
13 service in Tacoma and surrounding areas.

14 **Q. Was PSE management informed and involved during development and**
15 **construction of the upgrades related to the Tacoma LNG project?**

16 A. Yes. The distribution upgrades related to the Tacoma LNG project were part of a
17 much larger dual-use project. Roberts, Exh. RJR-1CT, describes the efforts that
18 were undertaken to involve PSE management and the PSE Board of Directors in
19 decisions related to development and construction of the larger Tacoma LNG
20 project. See Exh. RJR-3 for a detailed narrative timeline of the process by which
21 PSE developed and the PSE Board of Directors approved the Tacoma LNG
22 project.

1 **Q. Were there any material changes during execution that impacted the project**
2 **scope, schedule or budget? If so, describe.**

3 A. No. The upgrades related to the Tacoma LNG project were initially estimated at
4 \$49.26 million and the final cost for the upgrades was \$46.4 million.

5 **Q. Have the benefits from this project been realized?**

6 A. Yes, the improvements made to the distribution system outside of the Port of
7 Tacoma improved existing low-pressure issues in the Dupont, Steilacoom,
8 University Place and Fircrest areas as well as increased reliability in the Tacoma
9 area. Additional benefits will be realized when the PSE distribution system relies
10 on the Tacoma LNG Facility to meet peaking needs, through the increased
11 capacity at the Fredrickson Gate Station and the connection of the North Tacoma
12 high pressure line to the South Tacoma high pressure line.

13 **IV. MAJOR BACKBONE INFRASTRUCTURE PROJECTS THAT WILL BE**
14 **PLACED IN SERVICE BETWEEN JULY 1, 2021 AND DECEMBER 31, 2025**

15 **Q. Please describe the major backbone infrastructure projects with capital costs**
16 **greater than \$10 million currently in progress.**

17 A. The projects described in this section are not in-service. However, they are
18 underway and have a lifetime cost above \$10 million. The table below
19 summarizes these projects including phase, estimated budget, and planned in
20 service year.

Table 1: Major Backbone Infrastructure Projects with Capital Costs Greater than \$10 million Currently in Progress

Project	Current Lifecycle Phase	Lifetime Budget (EST)	Project In Service Year (EST)
Sammamish - Juanita 115kV Transmission Line	Design	\$30.1M	2023
Electron Heights - Enumclaw 55/115kV Conversion	Execution	\$21.2M	2024
Bainbridge Island	Planning	\$48.82M	2025
Tono Substation	Planning	\$17M	2022
Lynden Substation	Planning	\$9.6M	2024
Sedro Woolley - Bellingham #4	Design	\$23M	2025
Vashon – Gig Harbor Long Term Solution	Planning	\$35.3M	2026

A. Sammamish – Juanita 115kv Transmission Line Project

Q. Please describe the Sammamish – Juanita 115kV Transmission Line project.

A. The Sammamish – Juanita 115kV Transmission Line project (“Sammamish - Juanita”) is located in the Moorlands area of King County. The Sammamish – Juanita project consists of installing 4.65 miles of new 115 kV transmission line and upgrading another 0.15 miles of existing 115kV transmission line to connect Sammamish and Juanita substations. The project will also loop through the existing Totem Lake substation, removing it from being radially fed from the Sammamish – Vituli 115kV transmission line. Exh. RBB-5 contains the CSA for this project.

1 **Q. Is the Sammamish – Juanita 115kV Transmission Line operating and**
2 **providing service to customers?**

3 A. No.

4 **Q. What is the timeline for the Sammamish – Juanita 115kV Transmission Line**
5 **project?**

6 A. This project was initiated in 2007. After considering alternatives to the project,
7 PSE moved forward with the Sammamish – Juanita 115kV Transmission Line
8 project in 2008 seeking community, City of Kirkland, and City of Redmond input
9 on five route alternatives. The project team has been working with the City of
10 Redmond and City of Kirkland since on specifics of the route and permitting.
11 Easement acquisition started in 2021 with anticipated construction in 2022.

12 **Q. What is the final projected cost of the Sammamish – Juanita 115kV**
13 **Transmission Line project?**

14 A. The expected final cost of the project is \$30.1 million without AFUDC.

15 **Q. Describe the system need for the Sammamish – Juanita 115kV Transmission**
16 **Line.**

17 A. The primary need for the project is to increase transmission capacity and
18 reliability in the Moorlands area. The existing Moorlands area infrastructure
19 serves 56,000 customers from twelve substations supported by three transmission
20 lines. The summer and winter peak capacity of the substations exceeds the
21 capacity limit for two of the transmission lines and approaches capacity limits of
22 the third. The area load is already higher than the capacity of the existing lines

1 and PSE has instituted plans to drop load, if necessary, to prevent overloads. This
2 reduces customer reliability in operating the transmission system to meet capacity
3 requirements. Finally, outage scenarios can cause one line in the area to support
4 the twelve substations. Adding the Sammamish – Juanita 115kV Transmission
5 Line would reduce the likelihood of this occurrence.

6 **Q. Describe the alternatives evaluated and how this solution was chosen.**

7 A. Five alternatives, including the selected alternative, were evaluated. PSE's
8 solution criteria required all identified needs be addressed.

9 1. **Build new 115kV transmission line between Sammamish and Juanita**
10 **substations with loop through of Totem substation** – The Sammamish –
11 Juanita 115kV Line will result in three of the twelve substations being
12 moved off of the three existing transmission lines, reducing the total load
13 served by the three transmission lines. This alternative will also allow for
14 a future line to be extended from the Juanita substation to the Moorlands
15 substation. This was the preferred alternative because it improves both
16 reliability and capacity while allowing for future development.

17 2. **Build new 115kV transmission line between Sammamish and**
18 **Moorlands substations with loop through of Juanita substation** – This
19 alternative included construction of a new transmission line from the
20 Sammamish substation through the Juanita substation (Alternative 1) to
21 the Moorlands substation. This would create a four-line system with better
22 reliability than the existing three-line system and improve reliability for
23 the three substations that would be removed from the three-line system.
24 While this expansion may be necessary in the future, this option was
25 rejected in favor of doing the project individually.

26 3. **Rebuild three lines serving Moorlands with Bittern conductor** – This
27 alternative consisted of rebuilding and reconductoring the Sammamish –
28 Vitulli, Vitulli – Brightwater, and Sammamish – Moorlands #1 lines to
29 Bittern conductor. This alternative was rejected because it only addresses
30 the capacity needs of the area and does not resolve the reliability need.

31 4. **Build new underground 115kV transmission line between**
32 **Sammamish and Juanita substations with loop through to Totem**
33 **substation** – This alternative is similar to Alternative 1 and addresses the

1 capacity and reliability need. This alternative was rejected due to higher
2 cost than standard overhead construction.

- 3 5. **Do nothing** – This alternative consisted of no new line construction. This
4 alternative was rejected because it did not address the reliability or
5 capacity needs in the Moorlands area.

6 **Q. What benefits does the Sammamish – Juanita 115kV Transmission Line**
7 **provide for customers?**

8 A. This project will improve Moorlands area reliability for 56,000 customer that
9 would have been impacted by line overloads. Serving two of the twelve
10 substations with a separate line will reduce capacity required of the existing three-
11 line system by approximately 40 MW. This will lower the potential for outages on
12 these three lines and allow for increased load growth in the area.

13 **Q. Describe how PSE kept management informed during this project.**

14 A. Using PSE's Project Lifecycle Model, management provided review and approval
15 of the project. This project was reviewed by management in May 2014 to proceed
16 to the planning phase. The project was reviewed by management in August 2019
17 for scope updates. The project was reviewed by management in May 2020 to
18 proceed to the design phase. Finally, the project was reviewed by management in
19 November 2021 for budget and schedule updates.

20 **Q. Describe the current state of the Sammamish – Juanita 115kV Transmission**
21 **Line project.**

22 A. The project is currently in the design phase of the Project Lifecycle Model. PSE is
23 pursuing easements and permits consistent with the designs for anticipated
24 construction and in service in 2022.

1 **B. Electron Heights – Enumclaw 55/115kV Conversion Project**

2 **Q. Please describe the Electron Heights – Enumclaw 55/115kV Conversion**
3 **project.**

4 A. The Electron Heights – Enumclaw 55/115kV Conversion project (“Electron
5 Heights – Enumclaw”) is primarily located in the Wilkeson and Buckley areas of
6 Pierce County and Enumclaw area of King County. The Electron Heights –
7 Enumclaw project consists of converting the 22-mile existing Electron Heights –
8 Stevenson 55kV transmission line to a 115kV transmission line and 0.5 mile of
9 existing transmission between Stevenson and the Enumclaw substation. This will
10 require upgrading the 55kV breaker at the Electron Heights substation to 115kV,
11 rebuilding the transmission side of the Wilkeson substation to 115kV
12 infrastructure, relocating the Buckley substation to be rebuilt at 115kV, and
13 adding a new deadend tower and circuit switcher at the Enumclaw substation to
14 allow for the new loop through. Exh. RBB-6 contains the CSA for the Electron
15 Heights – Enumclaw project.

16 **Q. Is the Electron Heights – Enumclaw 55/115kV Conversion operating and**
17 **providing service to customers?**

18 A. No.

19 **Q. What is the timeline for Electron Heights – Enumclaw 55/115kV Conversion**
20 **project?**

21 A. This project was initiated in 2008. The first phases consisted of rebuilding the
22 transmission line for 115kV between the Electron Heights substation and

1 Stevenson switching station. The remaining substation and transmission upgrades
2 to be completed in the final phase were deferred because of budget constraints.
3 The project was started again in 2017 evaluating location alternatives for the
4 Buckley substation and Enumclaw area alternatives with respective jurisdictions.
5 The project is currently working through the permitting process and easement
6 acquisition with construction scheduled to start in 2022 and be completed by the
7 end of 2024.

8 **Q. What is the final projected cost of the Electron Heights – Enumclaw**
9 **55/115kV Conversion project?**

10 A. The expected final cost of the final phase of the project is \$21.2 million without
11 AFUDC.

12 **Q. Describe the system need for Electron Heights – Enumclaw 55/115kV**
13 **Conversion project.**

14 A. There are several needs for this project. First, this project will support capacity
15 needs for the Krain Corner substation and eliminate overloading existing 115kV
16 to 55kV transformers at Krain Corner and Electron Heights and the White River –
17 Krain Corner 55kV transmission line in certain outage conditions. Second, this
18 will remove aging infrastructure from various substations including the Electron
19 Heights, Wilkeson, and Buckley substation transformers. Finally, the project
20 brings increased reliability for the Enumclaw and Buckley areas by 1) providing a
21 115kV loop to the Enumclaw substation opposed to current radial service and 2)
22 installing 115kV midline breakers at the new Buckley substation with

1 communications to Krain Corner to improved fault isolation and clearing times
2 for the Buckley area.

3 **Q. Describe the alternatives evaluated and how this solution was chosen.**

4 A. Six alternatives, including the selected alternative, were evaluated. PSE's solution
5 criteria required all identified needs be addressed.

- 6 1. **Convert Electron Heights – Enumclaw from 55kV to 115kV** – This
7 alternative was selected because it is the least cost alternative (estimated
8 \$11-15 million) that meets the capacity needs for the Krain Corner
9 substation.
- 10 2. **Convert White River – Krain Corner 55kV to 115kV** – This alternative
11 was rejected because it was a larger cost alternative (estimated \$30-40
12 million) due to jurisdictional requirements for a seven-mile section of the
13 line.
- 14 3. **Build a new 115kV transmission line between Berrydale and Krain**
15 **Corner substations** – This alternative was rejected because it was a larger
16 cost alternative (estimated \$35-50 million) due to construction of 19.7
17 miles of new transmission line and upgrades to various substations.
- 18 4. **Build new substation west of Buckley substation and install a three**
19 **winding transformer to provide 115kV** – This alternative was rejected
20 because it did not fully meet project needs and it was a larger cost
21 alternative (estimated \$24-48 million) due to building two new
22 transmission line segments and new substation.
- 23 5. **Install new 115/55kV transformer at Krain Corner and Electron**
24 **Heights** – This alternative was rejected because PSE is working to
25 eliminate 55kV infrastructure from the system.
- 26 6. **Do nothing** – This alternative was rejected because of possible future
27 conflicts with NERC compliance and continued risk of outages for
28 customers.

1 **Q. What benefits does Electron Heights – Enumclaw 55/115kV Conversion**
2 **provide for customers?**

3 A. This project will increase reliability for the 9,962 customers served by the line in
4 the various areas. The overload scenarios required at Krain Corner that result in
5 an outage for 29,000 to 45,000 customers will be eliminated with this project.

6 **Q. Describe how PSE kept management informed during this project.**

7 A. Using PSE’s Project Lifecycle Model, management provided review and approval
8 of the project. This project was reviewed by management in April 2014 to
9 proceed to the design phase. The project was reviewed by management in May
10 2020 for scope updates. The project was reviewed by management in January
11 2022 to proceed to the execution phase.

12 **Q. Describe the current state of the Electron Heights – Enumclaw 55/115kV**
13 **Conversion.**

14 A. The project is currently in the execution phase of the Project Lifecycle Model.
15 PSE is acquiring permits and easements consistent with the designs for
16 anticipated construction and in service in 2024.

17 **C. Bainbridge Island Project**

18 **Q. Please describe the Bainbridge Island project.**

19 A. The Bainbridge Island project is located on Bainbridge Island in Kitsap County.
20 The Bainbridge Island project consists of three components that address each of
21 the identified system needs separately: First, constructing a 115kV transmission

1 line between the Winslow and Murden Cove substations with upgrades at each
2 station that allow for the new transmission interconnection; second, rebuilding the
3 existing 4.5 mile Winslow Tap 115kV transmission line; third, installation of an
4 approximate 3.3 MW 5MWh energy storage battery and implementation of an
5 approximate 3.3 MW distributed energy resource portfolio. Exh. RBB-7 contains
6 the CSA for the Bainbridge Island project.

7 **Q. Is the Bainbridge Island project operating and providing service to**
8 **customers?**

9 A. No.

10 **Q. What is the timeline for the Bainbridge Island project?**

11 A. This project was initiated in 2019. The project is currently working through
12 design and preparing for easement acquisition and permit submittals. The
13 Winslow Tap replacements are scheduled to be completed by the end of 2023.
14 The energy storage battery and distributed energy resources are scheduled to be
15 completed by the end of 2023. The new transmission line between the Winslow
16 and Murden Cove substations is scheduled to be completed by the end of 2025.

17 **Q. What is the projected final cost of the Bainbridge Island project?**

18 A. The expected final cost of the project is \$48.82 million without AFUDC.

19 **Q. Describe the system need for the Bainbridge Island project.**

20 A. There are several needs for this project. First, the Winslow Tap transmission line
21 was built in 1960 with wishbone crossarm construction. PSE has started to see

1 wishbone crossarms of similar vintage failing in other parts of PSE's service area
2 and considers this type of construction to be a reliability risk. An inspection of
3 this transmission line in early 2019 indicated that nearly half of the wishbone
4 crossarms will require replacement. Second, two of the three substations on
5 Bainbridge Island, the Winslow and Murden Cove substations, are radially fed
6 substations with no operating flexibility at the transmission level and no back up
7 feed. When managing transmission outages to either of these two substations,
8 customers are switched to adjacent substations. This switching is time consuming
9 and complex. During winter when customer demand is highest, some customers
10 on the affected transmission line and its substation may not be transferred and can
11 experience extended outages. Third, Bainbridge Island and the north Kitsap
12 County substations are at the end of the transmission system serving the Kitsap
13 peninsula. Studies of various contingencies in compliance with federal reliability
14 requirements have found that certain multiple contingencies on the transmission
15 system off-island on Kitsap peninsula may cause low voltage or overloading of
16 the transmission lines on the peninsula. Under such contingencies, PSE may be
17 forced to shed load by de-energizing some or all of Bainbridge Island substations.
18 Finally, a distribution substation group capacity need of 14.6MW was identified
19 on Bainbridge Island within the 10-year planning horizon to support general load
20 growth of 4.6 MW.

21 **Q. Describe the alternatives evaluated and how this solution was chosen.**

22 A. Several alternatives were evaluated and classified in three categories:
23 conventional wires alternatives, non-wires alternatives, and hybrid alternatives.

1 Of these three categories, the best solutions were evaluated in-depth, including the
2 selected alternative. PSE's solution criteria required all identified needs be
3 addressed.

- 4 1. **Wires Alternative** – This alternative included rebuilding Winslow Tap
5 transmission line, constructing a 115kV transmission line between
6 Winslow and Murden Cove substations, and building a new 25MVA
7 substation in south Bainbridge Island. This alternative was not selected
8 because it cost more, required building a substation that other alternatives
9 did not require, and possibly over-built capacity needs.
- 10 2. **Non-Wires Alternative** – This alternative consisted of five batteries to be
11 installed at locations around Bainbridge Island. This alternative was not
12 selected because of the higher cost relative to other alternatives.
- 13 3. **Hybrid Solution** – This alternative included a new transmission line
14 between Murden Cove and Winslow substations, a battery sized to meet
15 50% of the capacity needs, and rebuilding the Winslow Tap 115kV
16 transmission line. This alternative was selected because it is the least cost
17 alternative that addresses reliability issues, provides transmission
18 operation flexibility on Bainbridge Island by making the Murden Cove
19 and Winslow substations no longer radial substations, and addresses
20 distribution capacity with a non-wires alternative.
- 21 4. **Do nothing** – This alternative included only replacing aging infrastructure
22 on the Winslow Tap transmission line because of safety and overall
23 reliability considerations. This alternative was not selected because it does
24 not address future capacity needs of Bainbridge Island and does not
25 address the transmission reliability need of the Winslow Tap. Customers
26 fed from this station will continue to see a high frequency of interruptions
27 from the transmission source. With the limited group capacity operating
28 flexibility this load cannot be shifted to other substations resulting in
29 lengthy outages.

30 **Q. What benefits does the Bainbridge Island project provide for customers?**

31 A. This project will increase the reliability for customers on Bainbridge Island. The
32 Winslow substation has experienced 21 transmission outages in a five-year test
33 period between 2013 and 2017. Fifteen of those outages involved loss of radial
34 transmission taps serving Winslow and Murden Cove substations, with the loss of

1 Winslow Tap transmission line as the primary cause. Rebuilding this line and
2 redundancy of connecting the Winslow and Murden Cove substations will
3 dramatically reduce the number of outages. The added capacity will meet load
4 growth for Bainbridge Island.

5 **Q. Describe how PSE kept management informed during this project.**

6 A. Using PSE's Project Lifecycle Model, management provided review and approval
7 of the project. This project was reviewed by management in November 2019 to
8 proceed to the planning phase. The project was reviewed by management in June
9 2021 for scope, schedule and cost updates. The Winslow Tap rebuild was
10 approved by management to proceed to the design phase in June 2021.

11 **Q. Describe the current state of the Bainbridge Island project.**

12 A. The Winslow Tap upgrades are currently in the design phase of the Project
13 Lifecycle Model, preparing final designs and preparing for permit submittals and
14 easement acquisition. The energy storage battery and distributed energy resources
15 are in the planning phase preparing initial designs. The new transmission line
16 between the Winslow and Murden Cove substations is in the planning phase and
17 recently completed the route selection process.

18 **D. Tono Substation Project**

19 **Q. Please describe the Tono Substation project.**

20 A. The Tono Substation project is located near Centralia in Lewis County. The Tono
21 Substation project consists of replacing the four single 500/115kV transformers
22 with two new three phase 500/115kV transformers. One transformer has already

1 exceeded allowable hydrogen levels and is currently offline to prevent service
2 failure, and the other two transformers are projecting failure within five years.
3 The project will also replace two 115kV oil circuit breakers and
4 electromechanical relays within Tono substation. Exh. RBB-8 contains the CSA
5 for Tono Substation project.

6 **Q. Are the upgrades to the Tono Substation operating and providing service to**
7 **customers?**

8 A. No.

9 **Q. What is the timeline for the Tono Substation project upgrades?**

10 A. The Tono Substation project started evaluating project needs in 2019. Since 2020,
11 the project team has been working on material procurement, design, and
12 permitting. The project is scheduled to be placed in service in 2022.

13 **Q. What is the expected final cost of Tono Substation project?**

14 A. The expected final cost of the project is \$17 million without AFUDC.

15 **Q. Describe the system need for the Tono Substation project.**

16 A. The Tono 500/115kV transformers serve as PSE's only Extra High Voltage
17 ("EHV") source into the Thurston County South region and is one of three EHV
18 sources supporting Thurston County. Sustained outages of the Tono substation
19 EHV source can significantly degrade reliability, resiliency, and operability of
20 Thurston County and neighboring electric systems. The Tono substation has

1 additional maintenance concerns due to aged infrastructure equipment operating
2 beyond their recommended service life.

3 **Q. Describe the alternatives evaluated and how this solution was chosen.**

4 A. Nine alternatives, including the selected alternative, were evaluated. PSE's
5 solution criteria required all identified needs be addressed.

- 6 1. **Replace failing transformer with one in-kind transformer** – This
7 alternative consisted of replacing the failing transformer with one new or
8 used in-kind transformer. This option was rejected because of the
9 difficulty of matching the existing transformer impedance and requires a
10 custom order to match the impedances. This option was also rejected
11 because it did not support the long-term holistic solution strategy, as the
12 two other transformers are showing signs of failure with an estimated five
13 years or less of remaining service life.
- 14 2. **Replace failing transformer with one in-kind transformer and**
15 **purchase and store a spare in-kind transformer** – This alternative
16 consisted of replacing the failing transformer with one new or used in-kind
17 transformer and purchasing a second new or used unit to store as a spare
18 in-kind transformer. This option was rejected because of the difficulty of
19 matching the existing transformer impedance. In addition, this alternative
20 did not support the long-term holistic solution strategy, as the two other
21 transformers are showing signs of failure with an estimated five years or
22 less of remaining service life.
- 23 3. **Replace with four in-kind single-phase transformers** – This option
24 consisted of replacing the existing transformers with four new single phase
25 in-kind transformers, with one being a non-connected spare. This option
26 was not selected because of the slightly higher costs and design and
27 construction issues related to clearance requirements for the configuration
28 of three transformers within the existing layout of the substation.
- 29 4. **Replace failing transformers with two new 500/115kV transformers** –
30 This option consisted of replacing the existing single-phase transformers
31 with two new three phase transformers with one being a non-connected
32 spare. This option was the preferred option because it replaces all aging
33 infrastructure. It is a lower cost alternative and is a more feasible design
34 and construction configuration given the existing layout of the substation.
35 This option also supported the long-term holistic solution strategy.

- 1
2
3
4
5
6
7
8
5. **Replace failing transformers with two three phase 500/230kV transformers and one three phase 230/115kV transformer** – This option consisted of replacement with two new three-phase 500/230kV transformers with one being a non-connected spare and a used or new three phase 230/115kV transformer. This option was not selected due to higher costs and the extensive rebuild necessary to add a 230kV section with physical constraint concerns, including spacing limitations and topological concerns.
- 9
10
11
12
13
14
15
16
17
6. **Acquire and connect to BPA Big Hanaford Substation** – This option included acquiring BPA’s Big Hanaford substation, which is currently de-energized, and interconnecting the substation to the existing Transalta 500kV transmission line to Centralia 500kV switching station. A 500/230kV transformer would be added at Big Hanaford substation and a new 0.7 mile, 230kV transmission line built from Big Hanaford Substation to Tono Substation. A 230/115kV transformer would be installed at Tono Substation. This option was rejected because of the elevated cost and nine-year estimated project schedule.
- 18
19
20
21
22
23
24
25
26
7. **Add a three phase 230/115kV transformer at Tono substation and add double circuit 230kV transmission line tap to existing Transalta 230kV transmission line** – This option consists of looping the Transalta 230kV transmission line into Tono Substation with two 0.5-mile 230kV transmission lines and adding a 230/115kV transformer to Tono Substation. A reconductor of 2.2 miles of the Transalta 230kV line would be necessary to increase its capacity rating for this connection. This option was rejected because of the capacity deficiencies, an extended three to five year estimated schedule, and higher cost.
- 27
28
29
30
31
32
33
34
35
8. **Connect to Transalta 230kV Startup Substation at Centralia Generating Station** – This option consisted of connecting a 0.9-mile 230kV transmission line from Tono Substation to the existing Centralia Generating Startup substation. A reconductor of 2.5 miles of Transalta’s transmission line from the Startup Substation to the existing tap point on BPA’s Chehalis – Covington 230kV transmission line would be needed to increase the capacity rating. This option was rejected because of the capacity deficiencies, an extended three to five year estimated schedule, and higher cost.
- 36
37
38
39
40
41
42
9. **Add 500/230kV transformer at Transalta Centralia 500kV switching station and add 230kV transmission line to Tono substation** – This option consisted of acquiring land next to Transalta’s Centralia 500kV Switching Station to expand the Transalta Centralia 500kV substation and add a new 500/230kV transformer there and add a 230/115kV transformer at Tono Substation. A new 0.5-mile 230kV transmission line would be run from the Tono Substation to the existing Centralia Switching Station. This

1 option was rejected because of the extended 15+ year estimated project
2 schedule due to needing to go through Transalta's interconnection process
3 and higher cost.

4 **Q. What benefits does Tono Substation upgrades provide for customers?**

5 A. The Tono substation serves as PSE's EHV for the southern region of Thurston
6 County. This provides reliability for approximately 40,000 customers. Similarly,
7 Tono substation serves as one of three PSE EHV sources for Thurston County.
8 The upgrades provide improved reliability for approximately 129,000 customers.

9 **Q. Describe how PSE kept management informed during this project.**

10 A. Using PSE's Project Lifecycle Model, management provided review and approval
11 of the project. This project was reviewed by management in August 2020 to
12 proceed to the planning phase. The project was reviewed by management in June
13 2021 for budget updates.

14 **Q. Describe the current state of the Tono Substation project.**

15 A. The project is currently in the planning phase of the Project Lifecycle Model,
16 where PSE is preparing designs and permit submittals.

17 **E. Lynden Substation**

18 **Q. Please describe the Lynden Substation project.**

19 A. The Lynden Substation project is located in the City of Lynden in Whatcom
20 County. The Lynden Substation project consists of expanding the substation
21 footprint and rebuilding the substation, adding a 115kV circuit breaker for the

1 BPA Bellingham – Lynden transmission line. Exh. RBB-9 contains the CSA for
2 the Lynden Substation project.

3 **Q. Is the Lynden Substation project operating and providing service to**
4 **customers?**

5 A. No.

6 **Q. What is the timeline for Lynden Substation project?**

7 A. The Lynden Substation project started evaluating project needs in 2019. Since
8 2020, PSE has been working on project design and evaluating permitting
9 requirements. The project is scheduled to be placed in service in 2024.

10 **Q. What is the expected final cost of Lynden Substation project?**

11 A. The expected final cost of the project is \$9.6 million without AFUDC.

12 **Q. Describe the system need for Lynden Substation project.**

13 A. There are several needs for this project. First, there are several pieces of
14 equipment that are beyond their economic life and in need of replacement.
15 Second, the BPA Bellingham – Lynden transmission line terminating at the
16 Lynden substation does not terminate at a circuit breaker. Without a circuit
17 breaker on this line, a fault on this 5.8-mile line segment results in a full station
18 outage at Lynden. Third, the unique layout of the substation and physical spacing
19 constraints would require an extended period of time for replacement of the Bank
20 #2 transformer and regulator because there is not enough space in the present
21 configuration as well as challenging crews' ability to work efficiently and safely.

1 Finally, there are distribution reliability and operation concerns at the station, as
2 there is no bus tie switch between the two 12.5kV feeder structures and substation
3 controls are spread between two control houses.

4 **Q. Describe the alternatives evaluated and how this solution was chosen.**

5 A. Seven alternatives, including non-wires alternatives, were evaluated. This
6 includes the selected alternative. PSE's solution criteria required all identified
7 needs be addressed.

8 1. **Improvements on existing site** – This option evaluated the existing site
9 for how much improvement could be obtained without expanding the
10 substation site. This option was rejected because of space limitations in the
11 existing substation, it is not possible to address replacing Bank #2 and
12 install a 115kV circuit breaker for the BPA Bellingham – Lynden
13 transmission line.

14 2. **Expand and rebuild substation with 115kV main bus and install one**
15 **metalclad feeder** – This option expands the substation footprint for
16 upgrading the substation with an open-air 115kV bus. This option was
17 rejected because it did not provide the reliability benefits of two metalclad
18 alternatives while having similar cost requirements.

19 3. **Expand and rebuild substation with 115kV main bus and install two**
20 **metalclad feeders** – This option expands the substation footprint for
21 upgrading the substation and replaces both open air feeder structures with
22 metalclad switchgear. This alternative was selected because it was the
23 lowest cost alternative that met reliability and operability concerns with
24 replacement of aging infrastructure.

25 4. **Expand substation with 115kV ring bus and two metalclad feeders** –
26 This option expands the substation footprint for installing a 115kV ring
27 bus and two metalclad feeders. This alternative was rejected because of
28 the cost impacts related to expanding the substation beyond other
29 alternatives.

30 5. **New substation at new site with 115kV ring bus and 2 metalclad**
31 **feeders** – This option included relocating the substation to a new site
32 located within one mile of the existing substation. This alternative was
33 rejected because of the cost and schedule risks of finding an alternative
34 site and relocating the existing transmission and distribution systems.

1 6. **Remove transformer, perform distributed energy resources measures**
2 **and reduced scope of work in existing substation footprint** – This non-
3 wires alternative was rejected because of the increased costs associated
4 with the solution.

5 7. **Do nothing** – This option consists of replacing the Bank #2 transformer
6 upon failure. This will require an extended outage for the work to enable
7 proper installation of the equipment to integrate a load-tap-changing
8 transformer. This option was rejected because it did not provide a circuit
9 breaker on the BPA Bellingham – Lynden transmission line, address other
10 aging infrastructure within the station, or substation operating limitations.

11 **Q. What benefits does the Lynden Substation project provide for customers?**

12 A. The project will improve reliability for the 6,300 customers served by the Lynden
13 substation and reduce risks for momentary or sustained outages to another 15,700
14 customers in northern Whatcom County.

15 **Q. Describe how PSE kept management informed during this project.**

16 A. Using PSE’s Project Lifecycle Model, management provided review and approval
17 of the project. This project was reviewed by management in January 2021 to
18 proceed to the planning phase. The project was reviewed by management in June
19 2021 for funding updates.

20 **Q. Describe the current state of the Lynden Substation project.**

21 A. The project is currently in the planning phase of the Project Lifecycle Model,
22 preparing initial designs and evaluating permitting requirements.

1 **F. Sedro Woolley – Bellingham #4 115kV**

2 **Q. Please describe the Sedro Woolley – Bellingham #4 115kV project.**

3 A. The Sedro Woolley – Bellingham #4 115kV Reconductor Transmission Line
4 project (“Sedro #4”) is located in western Whatcom and Skagit Counties serving
5 Burlington and Sedro Woolley. Sedro #4 consists of rebuilding and
6 reconductoring the existing 24-mile-long Sedro Woolley-Bellingham #4 115 kV
7 line. The line helps connect the Skagit County and Whatcom County 115 kV
8 systems together and directly feeds two distribution substations, Alger and
9 Norlum. To coordinate concurrent distribution system upgrades, this project will
10 be constructed in five phases: Phase A, which was completed in February 2018,
11 included approximately four miles of the line in Skagit County; Phase B, which
12 was completed in December 2018, included approximately seven and a half miles
13 of the line in Skagit County; Phase C includes approximately six miles of the line
14 in Skagit and Whatcom Counties; Phase D includes approximately six miles of
15 the line in Whatcom County; and Phase E includes rebuilding the final a half mile
16 of the line in Skagit County. Exh. RBB-10 contains a Mid-Phase Change Request
17 prior to project deferment in 2019.

18 **Q. Is Sedro #4 operating and providing service to customers?**

19 A. Partially. Phases A and B are operating and providing service to customers.
20 Phases C, D and E are not.

1 **Q. What is the timeline for Sedro #4?**

2 A. The Sedro #4 project was initiated in 2010. Phase A was constructed and placed
3 in service February 2018. Phase B was constructed and placed in service
4 December 2018. In 2019 and 2020, the remaining phases were deferred for higher
5 priority reliability and capacity projects. The project team is working on
6 evaluating existing designs prior to acquiring remaining permits and easements.
7 Phase C construction is planned to be completed and in service in 2024. Phases D
8 and E are planned to be constructed and in service in 2025.

9 **Q. What is the estimated final cost of Sedro #4?**

10 A. The expected final cost of the project is approximately \$23 million without
11 AFUDC. The \$8 million costs associated with Phases A and B were recovered in
12 the 2017 and 2019 general rate cases.

13 **Q. Describe the system need for Sedro #4.**

14 A. There are several needs for this project. First, the low capacity line ratings could
15 cause the line to exceed its allowable ratings for several contingencies and limit
16 generation capacity in Whatcom and Skagit Counties. The small copper wires also
17 could cause high line losses and the aging infrastructure would lead to extended
18 outages. Second, the low capacity of the Bellingham-Sedro Woolley #4 line has
19 caused constraints on regional power flows for over twenty years due to the
20 parallel higher-voltage transmission line, which requires PSE to protect the line
21 from overloading by automatically opening the Sedro Woolley substation circuit
22 breaker. Opening this circuit breaker reduces system reliability in both Whatcom

1 and Skagit Counties, including the Norlum and Alger substations. Customers
2 served by Norlum and Alger substations are at an increased risk of outage during
3 this time as each substation has only one transmission source. Third, the aged
4 equipment of the line contributed to 27 momentary outages and four sustained
5 outages in the five years prior to construction of Phases A and B.

6 **Q. Describe the alternatives evaluated and how this solution was chosen.**

7 A. Three alternatives, including the selected alternative, were evaluated. PSE's
8 solution criteria required all identified needs be addressed.

- 9 1. **Rebuild the 115 kV transmission line** – This alternative was selected
10 because it addressed both the capacity deficiency and the reliability
11 problems related to the aging infrastructure for the most economical cost.
12 This option includes replacing all of the aging wood poles and
13 reconductoring the line to a larger conductor size.
- 14 2. **Maintain existing transmission line, replace aging transmission poles
15 and keep Corrective Action Plan (“CAP”)** – This alternative was
16 rejected because it does not decrease the number of line outages, results in
17 increased maintenance activities and costs, and does not address line
18 overloading issues.
- 19 3. **Build a new 115 kV transmission line** – This alternative was rejected
20 because of its high cost from purchasing land and easements for a new
21 right-of-way and the associated permitting challenges with a new right of
22 way. In addition, this alternative did not address the aging infrastructure of
23 the existing transmission line.

24 **Q. What benefits does Sedro #4 provide for customers?**

25 A. Replacement of the aging infrastructure reduces the likelihood of unplanned
26 customer outages for the 6,240 customers served by Norlum and Alger
27 substations. Similarly, with the increased line capacity, PSE will be able to
28 remove an automatic tripping scheme that opens the south end of the line when

1 system events cause the line to overload, which decreases exposure of the
2 customers to subsequent line outages and strengthens the transmission system
3 between Whatcom and Skagit Counties.

4 **Q. Describe how PSE kept management informed during this project.**

5 A. Using PSE’s Project Lifecycle Model, management provided review and approval
6 of the project. This project was reviewed by management in February 2011 for the
7 substation work to proceed to the design phase. The transmission line work was
8 approved to proceed to the design phase in June 2014. The project budget was
9 reviewed and approved by management in June 2015, October 2018, and June
10 2019.

11 **Q. Describe the current state of the Sedro #4 project.**

12 A. The project is currently in the design phase of the Project Lifecycle Model for
13 Phases C, D and E, evaluating existing designs prior to acquiring remaining
14 permits and easements.

15 **G. Vashon – Gig Harbor Long Term Solution Project**

16 **Q. Please describe the Vashon – Gig Harbor Long Term Solution project.**

17 A. The Vashon – Gig Harbor Long Term Solution project (“Marine Crossing”) is
18 located between Des Moines, Gig Harbor, and Vashon Island. Currently, there is a
19 single gas supply from the mainland that serves customers on Vashon Island and
20 in Gig Harbor. This single feed includes two subsea marine crossings of parallel
21 pipelines that run approximately 11,000 feet from Des Moines underwater to
22 Vashon Island (the East Passage), and 9,000 feet from Vashon Island underwater

1 to Gig Harbor (the Colvos Passage). These pipelines were designed and installed
2 to rest on the seafloor. Sections of unsupported pipeline have occurred as a result
3 of seafloor movement and third-party analysis has indicated that the pipelines
4 may be approaching the end of their useful lives. The Marine Crossing project
5 consists of implementing a long-term supply to customers on Vashon Island and
6 the Gig Harbor area. Exh. RBB-11 contains the CSA for the Marine Crossing
7 project.

8 **Q. Is the Marine Crossing operating and providing service to customers?**

9 A. No.

10 **Q. What is the projected timeline for the Marine Crossing project?**

11 A. The Marine Crossing project was approved by management for the planning
12 phase in June 2020. Since 2020, PSE has engaged in a needs assessment and the
13 evaluation of solution alternatives. The long-term solution is anticipated to be
14 placed in service by 2026.

15 **Q. What is the current lifetime cost estimate of the Marine Crossing project?**

16 A. The current lifetime cost estimate of the project is \$35.3 million without AFUDC.

17 **Q. Describe the system need for the Marine Crossing project.**

18 A. A third-party analysis showed that tidal flow around the exposed pipelines
19 originally installed in 1969 may induce stresses that ultimately lead to failure of
20 the pipe. The analysis recommended that PSE further assess pipeline conditions
21 and develop a plan of ensuring long-term gas supply to existing customers.

1 Damage to the pipeline could result in sustained outages for customers on Vashon
2 Island and Gig Harbor.

3 **Q. Describe the alternatives being evaluated.**

4 A. Various alternatives are being evaluated between replacement and reinforcement,
5 alternative routing, and non-pipe solutions to address the long-term needs. A
6 preferred alternative has not yet been finalized. PSE's solution criteria require that
7 all identified needs are addressed.

8 **Q. What benefits does the Marine Crossing project provide for customers?**

9 A. The completion of a solution will reduce risk of disruption to natural gas supply to
10 PSE's existing customers thereby increasing reliability of natural gas service for
11 13,000 customers.

12 **Q. Describe how PSE kept management informed during this project.**

13 A. Using PSE's Project Lifecycle Model, management provided review and approval
14 of the project. This project was reviewed by management and approved in June
15 2020 to proceed to the planning phase. The project was reviewed and approved by
16 management in April 2021 for budget updates.

17 **Q. Describe the current state of the Marine Crossing project.**

18 A. The project is currently in the planning phase of the Project Lifecycle Model. PSE
19 is analyzing alternatives for a long-term solution while completing technical
20 feasibility analyses and designs.

1

V. CONCLUSION

2

Q. Does this conclude your testimony?

3

A. Yes, it does.