

**EXH. RPB-1T
DOCKETS UE-22 ___/UG-22 ___
2022 PSE GENERAL RATE CASE
WITNESS: RYAN P. BLOOD**

**BEFORE THE
WASHINGTON UTILITIES AND TRANSPORTATION COMMISSION**

**WASHINGTON UTILITIES AND
TRANSPORTATION COMMISSION,**

Complainant,

v.

PUGET SOUND ENERGY,

Respondent.

Docket UE-22 ___

Docket UG-22 ___

PREFILED DIRECT TESTIMONY (NONCONFIDENTIAL) OF

RYAN P. BLOOD

ON BEHALF OF PUGET SOUND ENERGY

JANUARY 31, 2022

PUGET SOUND ENERGY

**PREFILED DIRECT TESTIMONY (NONCONFIDENTIAL) OF
RYAN P. BLOOD**

CONTENTS

I. INTRODUCTION1

II. OVERVIEW OF PSE’S BAKER RIVER HYDROELECTRIC
GENERATING STATION AND RE-GROUTING PROJECT.....2

III. PSE’S APPROACH TO THE BRH PROJECT6

IV. PSE’S PROJECT MANAGEMENT AND OVERSIGHT PLANS14

V. PROJECT MILESTONES COMPLETED AND EXPECTED
DURING THE RATE PLAN18

VI. CONCLUSION.....19

PUGET SOUND ENERGY

**PREFILED DIRECT TESTIMONY (NONCONFIDENTIAL) OF
RYAN P. BLOOD**

LIST OF EXHIBITS

Exh. RPB-2	Professional Qualifications of Ryan P. Blood
Exh. RPB-3	Board of Consultants' Report
Exh. RPB-4	PSE Jan. 29, 2018 Letter to FERC
Exh. RPB-5	FERC March 12, 2018 Response Letter to PSE
Exh. RPB-6	Shannon & Wilson Alternatives Analysis
Exh. RPB-7	HDR Cost and Schedule Risk Analysis
Exh. RPB-8	AMC Presentation

1 **PUGET SOUND ENERGY**

2 **PREFILED DIRECT TESTIMONY (NONCONFIDENTIAL) OF**
3 **RYAN P. BLOOD**

4 **I. INTRODUCTION**

5 **Q. Please state your name, business address, and position with Puget Sound**
6 **Energy (“PSE”).**

7 A. My name is Ryan P. Blood. My business address is 355 110th Ave. NE, Bellevue,
8 WA 98004. I am the Director of Northern Generation with PSE.

9 **Q. Have you prepared an exhibit describing your education, relevant**
10 **employment experience, and other professional qualifications?**

11 A. Yes, I have. Please see Exh. RPB-2 for an exhibit describing my education,
12 relevant employment experience, and other professional qualifications.

13 **Q. Please describe your responsibilities as Director of Northern Generation?**

14 A. I am responsible for overseeing power generation operations and budgeting of
15 PSE’s Northern fleet of power plants, including Encogen, Sumas, PSE’s Simple
16 Cycle Fleet, Wild Horse Wind Farm, and the Baker River Project. In particular I
17 am responsible for ensuring the safe and reliable operation of all of our facilities.

18 **Q. Please summarize the purpose of this prefiled direct testimony.**

19 A. My testimony provides an overview of PSE’s plans to regrout and modernize the
20 Baker River Hydro generating station. My testimony describes the purpose of the

1 project, the need it is intended to meet, and the approach PSE is taking to enable
2 construction and grouting activities to be planned and executed effectively and in
3 the best interest of customers. I describe these plans in detail and present the
4 estimated schedule and cost milestones that apply to the project.

5 **II. OVERVIEW OF PSE'S BAKER RIVER HYDROELECTRIC**
6 **GENERATING STATION AND RE-GROUTING PROJECT**

7 **Q. Please describe the Baker River Hydroelectric Project.**

8 A. The Baker River Hydroelectric Project ("BRH Project") is the largest
9 hydroelectric facility in PSE's generation fleet. It is comprised of Upper Baker
10 Dam and Lower Baker Dam, as well as their associated powerhouses and
11 facilities. The project's reservoirs, Baker Lake and Lake Shannon, are fed by
12 runoff from Mount Baker and Mount Shuksan, while the dams themselves sit on a
13 tributary of the Skagit River in northwest Washington. Upper Baker Dam,
14 completed in 1959, is a concrete gravity dam with a height of 312 feet and power-
15 generating capacity of 107 megawatts ("MW"). The Lower Baker Dam ("LBD"),
16 completed in 1925, is a semi-gravity concrete arch dam with a height of 285 feet,
17 crest length of 550 feet, and power-generating capacity of 111 MW. Leakage
18 through LBD and through geologic features within the bedrock has occurred since
19 original construction. Prior grouting programs were carried out on the dam in
20 1934, 1959, and 1982.

1 **Q. How has hydroelectric power, and particularly the BRH Project, benefited**
2 **PSE's customers?**

3 A. Hydroelectric power, and the BRH Project in particular, continues to play a
4 crucial role in PSE's generating fleet. The two dams that compose the BRH
5 Project have been in operation since 1925 and 1959 and provide a combined 218
6 MW of clean, renewable power. For nearly a century the BRH Project has
7 provided numerous and substantial benefits to Washington electric customers by
8 reliably producing carbon-free energy, enhancing fuel diversity, and insulating
9 customers from commodity price spikes. Into the future, the BRH Project will
10 make a material contribution to PSE's achievement of mandates under the Clean
11 Energy Transformation Act ("CETA").

12 **Q. Please explain why PSE initiated the BRH Project.**

13 A. In terms of station operations, the BRP Project continues to run safely and
14 efficiently, producing power at levels as would be expected. However, in 2012,
15 during a regularly-scheduled comprehensive inspection by independent
16 consultants (which occurs every five years, as required by the Federal Energy
17 Regulatory Commission ("FERC")), it was determined that the leakage through
18 the Lower Baker Dam bedrock foundation was increasing with time, and it could
19 pose a threat to dam stability if left unmitigated.

20 That same year, at PSE's request, Tetra Tech Inc. conducted several
21 investigations into the nature of the leakage, potential erosion below the dam

1 apron, and the presence of sub-channel flow pathways. These investigations were
2 not definitive, and Tetra Tech, and later Shannon & Wilson, performed
3 subsequent further studies and testing.

4 In February 2013, FERC required PSE to establish a three-member independent
5 Board of Consultants (“BOC”) to assist FERC with assessing the ongoing
6 investigations and the potential threat the leakage posed to dam stability. The
7 members of the BOC are experts in rock mechanics, geological engineering, and
8 structural engineering.

9 Based on the extensive studies conducted through 2017, PSE determined that the
10 ongoing leakage through the dam foundation did indeed present a potential dam
11 safety issue. PSE presented the results of these studies to the BOC in December
12 2017 and solicited its opinion on whether it felt the ongoing leakage presented a
13 dam safety issue. Specifically, PSE asked the BOC if it was necessary to mitigate
14 the leakage to ensure dam safety. The BOC responded in the affirmative, and its
15 response is captured in a BOC Report, Exh. RPB-3.

16 On January 29, 2018, PSE submitted to FERC the BOC Report, plus a plan and
17 schedule to comply with the BOC’s recommendations. PSE’s letter to FERC is
18 provided as Exh. RPB-4. FERC responded to PSE’s letter on March 12, 2018 and
19 did not dispute the BOC’s conclusion that the leakage at Lower Baker Dam posed
20 a dam safety issue if left unmitigated. See Exh. RPB-5.

1 **Q. What are PSE's plans to address the leakage at the BRH Project ?**

2 A. PSE plans to treat the Lower Baker Dam foundation with a modern,
3 comprehensive grout curtain. This grout curtain will treat a much wider and
4 deeper area than previous grouting projects and will result in longer flow
5 pathways that will decrease flow velocities and thus lower the potential for
6 foundation erosion and degradation. Debris upstream of the dam will also be
7 grouted to increase the effectiveness of the grout curtain. Such activity will not
8 only address the current leakage but will also minimize the potential for future
9 leakage.

10 **Q. What are the estimated costs for this treatment?**

11 A. Total construction costs for this treatment from 2021 forward are estimated to be
12 \$341 million. This figure includes the construction itself, a construction
13 management contract, the engagement of an engineer of record, PSE labor
14 associated with the project and its oversight, PSE overhead costs that are typical
15 for construction projects of this nature, and a contingency allowance to account
16 for unexpected scope elements that are often discovered through the course of a
17 project of this scale.

18 **Q. Why is it in the public interest to make these investments in the BRH**
19 **Project?**

20 A. First and foremost, this is a dam safety issue that must be resolved to retain PSE's
21 operating license for the facility from FERC. Also, this grouting project will

1 enable the BRH Project to continue to generate carbon-free electricity for another
2 five decades or more. The clean power the BRH Project provides to PSE's
3 customers is stable and predictable, and the construction will help PSE's meet its
4 objectives related to environmental stewardship.

5 In addition, maintaining diversity in PSE's generating fleet through pursuit of this
6 project is particularly important in light of its ability to mitigate exposure to fuel
7 price volatility that would exist with a fleet concentrated on one specific
8 generating fuel, such as natural gas.

9 **III. PSE'S APPROACH TO THE BRH PROJECT**

10 **Q. Please describe how PSE identified the best method for accomplishing the**
11 **project.**

12 A. PSE convened a team of subject matter experts, including the FERC-required
13 BOC and engineering experts from Shannon & Wilson, Hatch, GeoHydros, and
14 PSE. This team participated in a comprehensive alternatives analysis workshop in
15 July 2017 to evaluate six methods that had been identified and determined to be
16 suitable for consideration to mitigate leakage at the BRH Project. The team of
17 experts considered the following criteria for evaluation: fatal flaws, relative cost,
18 constructability, schedule, environmental issues, licensing, reliability, and dam
19 safety during construction as.

1 **Q. What did this team of experts determine?**

2 A. The team of experts determined that the combination of a grout curtain of
3 significant depth and width, including grouting of the debris upstream of the dam,
4 was the most effective method for reducing the seepage and resolving the dam
5 safety concerns. The BOC's support for this determination is memorialized in its
6 Board of Consultants Report for Meeting No. 6. See Exh. RPB-3.

7 **Q. What alternatives were considered, and why were those approaches**
8 **rejected?**

9 A. PSE considered the following five alternatives to the BRH Project:

10 **Low hydraulic conductivity blanket over the reservoir bottom upstream of**
11 **the dam.** The team considered several variations on this alternative, with
12 differing features such as the blanket material (synthetic fabrics versus low
13 permeability sediments) and extent of the treatment area (extensive blanket versus
14 targeting the known leakage paths). Ultimately, the team concluded this option
15 would be challenging to construct and only an effective solution for a limited
16 period (days to months, versus decades). This option was originally included in
17 the request for proposals ("RFP") as a measure to assist with the grout curtain
18 installation. It was eventually removed due to the uncertainty in effectiveness and
19 its price of approximately \$50 million. A more localized geosynthetic blanket is
20 still being used to control localized flows in the rock face on the right side of the
21 reservoir.

1 **A continuous, positive cutoff wall.** The team considered several permutations of
2 this alternative, including variations in location (upstream of the dam versus
3 through the dam) and construction methodology (hydromill versus secant pile).
4 Ultimately, this option was not the preferred option due to a number of factors,
5 including: 1) the larger equipment necessary to construct a cutoff wall would
6 necessitate a larger platform, which would ultimately need to be free standing and
7 therefore significantly more expensive than the grout curtain platform; 2) cutoff
8 walls constructed with slurries require the ground to be pretreated by grouting to
9 prevent slurry loss during construction and would therefore be more expensive;
10 and 3) the site is quite confined, and execution of cutoff walls requires a working
11 area much larger than that available at site.

12 **Grouting debris and soil just above its contact with bedrock in the reservoir**
13 **upstream of the dam.** This alternative was ultimately rejected as a stand-alone
14 option because of leakage occurring through the bedrock at elevations above the
15 top of the debris. However, this alternative has been incorporated into the larger
16 grout curtain program. PSE anticipates that this will improve the ability to execute
17 the grout curtain and ultimately reduce grouting time and materials and reduce
18 overall project cost.

19 **Injecting gravel and sand through the debris upstream of the reservoir to**
20 **partially fill joints and fractures.** This option was also originally included in the
21 suite of 2019 proposals and presented lower costs than other options considered.
22 However, historic reports indicate that similar measures had not proven effective

1 in the past. At other areas within the forebay, after placing material in the debris,
2 the seepage paths simply migrated elsewhere within a period of hours or days.

3 This option was subsequently removed as a standalone option.

4 **Construction of a new dam downstream of the existing dam.** This option was
5 considered but relatively quickly dismissed as the most expensive and least timely
6 of the options considered. Construction of a new dam would require decades of
7 study and design and would be significantly more costly than the preferred
8 alternative. And, if this alternative was approved by FERC, it would still require
9 some form of interim safety measures that would be nearly as costly as the
10 preferred alternative.

11 Although not officially considered as a mitigation measure for the ongoing
12 seepage, removal of the dam was informally considered. As with the construction
13 of a new dam, dam removal would require decades of environmental studies and
14 relicensing and would ultimately be as costly, or more costly, than the preferred
15 alternative. All the alternatives, including the preferred alternative, are discussed
16 in the Shannon & Wilson report Seepage Reduction Alternatives, Lower Baker
17 Dam, Concrete, Washington dated July 7, 2017. See Exh. RPB-6.

18 **Q. Please describe how PSE selected the contractor for the BRH Grouting**
19 **Project.**

20 A. Once the best method for accomplishing the project was identified, PSE worked
21 with Shannon & Wilson and experts in the field of ground treatment to identify

1 specialty contractors to execute the project. These contractors are leaders in
2 drilling and grouting, heavy civil construction, marine construction, geotechnical
3 engineering, and instrumentation. The contractors were invited to submit
4 statements of interest and qualifications in June 2018. They were also invited to
5 an industry day at Lower Baker Dam on July 18, 2018 to review the project.
6 Thirty-four individuals from sixteen contractors participated. Four prospective
7 contractor teams ultimately submitted statements of interest and qualifications and
8 three were found to be qualified and responsive and were selected to receive the
9 formal RFP.

10 The three prequalified teams received the RFP on March 18, 2019 and all three
11 responded on August 22, 2019. Teams were evaluated by a panel of four
12 engineering experts based on technical approach, management plan, schedule,
13 experience, past performance, proposed monitoring system, and proposed
14 temporary structures. Once teams were ranked for technical ability, the proposed
15 bid prices were reviewed and all three were found to be within 10 percent of the
16 mean. Based on proposal evaluation and price, the Lower Baker Constructors,
17 LLC was identified as the team that provided the best value. However, the total
18 price proposal was higher than PSE had anticipated, and the decision was made to
19 work with the preferred contractor in an “early contractor involvement” (“ECI”)
20 relationship to lower the overall project cost while still achieving the desired
21 project outcome. Following a successful ECI period, the construction contract was
22 awarded to Lower Baker Constructors, LLC on October 22, 2021.

1 **Q. Please briefly describe the contractor's team and the work each member will**
2 **perform on the project.**

3 A. Lower Baker Constructors, LLC is a joint venture of Traylor Bros. Inc (heavy
4 civil construction), Ballard Marine (marine construction), and Advanced
5 Construction Techniques (drilling and grouting specialist). The joint venture team
6 members are supported by Golder Engineering, Schnabel Engineering, and VAK
7 Engineering.

8 Traylor Bros. Inc will perform site preparation and construction of the temporary
9 access/working platform. Ballard Marine will execute the marine construction to
10 include installation of all underwater features and any required diving support.

11 Advanced Construction Techniques will be performing all of the onsite drilling,
12 drill hole washing and surveying, and all grout preparation and injection. Golder
13 Engineering will be supporting Advanced Construction Techniques in the
14 interpretation of the grouting results and in real-time adjustments to grout mixes
15 and injection rates. Schnabel Engineering will be providing geotechnical and dam
16 safety engineering support. VAK Engineering will provide structural engineering
17 support.

18 PSE issued an additional RFP on July 20, 2020 seeking construction management
19 services for the duration of the project. This RFP was provided to three well-
20 established construction management firms. Two of the three firms provided
21 responses. The two proposals were evaluated based on team experience,
22 knowledge and experience of key individuals, project understanding, and

1 implementation and staffing plan. HDR, Inc was selected and will be providing a
2 resident engineer, office engineer, and inspector support during construction.

3 Shannon & Wilson is the engineer of record and will provide engineering support
4 during construction.

5 **Q. How has PSE estimated the costs for this work?**

6 A. Project cost estimates at the conceptual stage were based on scaling of the 1983
7 grouting project costs. As the project progressed, costs were estimated by PSE
8 personnel with considerable drilling and grouting experience, as well as by
9 representatives from Shannon & Wilson.

10 **Q. How is PSE validating the cost estimates?**

11 A. PSE hired Jim Cockburn, a recognized expert in the industry, to review PSE's and
12 the contractors' cost estimates. PSE also hired HDR to review the validity of the
13 contractors cost estimates. Reviews indicate that the estimates were correct, and
14 that conclusion is supported by the close spread in the three proposals received in
15 2019. As stated above, all three proposals fell within ten percent of the mean
16 projected cost.

17 In addition, PSE asked HDR to perform a Monte Carlo simulation on the project
18 costs with many of the design and execution variables in hand. This resulted in a
19 Cost and Schedule Risk Analysis Report, which is provided as Exh. RPB-7.

1 **Q. How did PSE prepare for the possibility of higher costs?**

2 A. PSE incorporated both contingency and management reserves into the cost
3 estimates.

4 **Q. What is contingency, and why is it included in the project cost?**

5 A. Contingency is incorporated into a project to account for known and measurable
6 risks, as identified through a risk assessment process (i.e., “known unknowns”).
7 Contingency can apply to both the project budget and project schedule, which are
8 often correlated. Contingency is particularly important for projects similar in
9 profile to the BRH Project. Geotechnical projects in general and grouting projects
10 in particular are subject to moderate to large swings in costs associated with
11 unknown conditions below the surface. Contingency reserves are under the
12 purview of the Project Manager.

13 **Q. What is a management reserve, and why is it applicable for this project?**

14 A. In contrast to contingency reserves, management reserves are set aside to account
15 for unidentified risks (i.e., “unknown unknowns”). With a project of the scale and
16 complexity of the BRH Project grouting, it is difficult to identify every risk at the
17 outset. The work that must be done is somewhat comparable to projects that have
18 been completed in the North American hydro generation industry, but aspects of
19 the engineering are unique, the river flow dynamics are specific to the BRH
20 Project, and other project elements can be considered “first-of-a-kind” challenges.
21 It is reasonable to expect that conditions will appear that have not been

1 considered, despite the rigorous risk inventory and management activities that
2 PSE has completed with its vendors. This type of project management challenge
3 is not uncommon in the power construction industry. Such uncertainty is
4 managed, mitigated, and accounted for through a Management Reserve.

5 **Q. Has PSE's Board of Directors been apprised of plans related to the BRH**
6 **Project?**

7 A. Yes. Because the BRH Project grouting is part of PSE's strategic project
8 portfolio, the Board of Directors has been receiving, and continues to receive,
9 formal monthly updates on the health of the project (scope, schedule, budget,
10 resources). The Board also received regular updates on project status during its
11 quarterly meetings. On September 27, 2021, the BRH Project grouting work was
12 formally presented to the Board of Directors' Asset Management Committee
13 ("AMC") for project approval, as is standard practice for projects of this
14 magnitude. See Exh. RPB-8, for a copy of the AMC presentation. The AMC
15 recommended project approval and the full Board of Directors concurred.

16 **IV. PSE'S PROJECT MANAGEMENT AND OVERSIGHT PLANS**

17 **Q. Does PSE have a Project Implementation Plan that will guide execution of**
18 **the BRH Project's modernization and grouting?**

19 A. Yes. The BRH Project's modernization and grouting project will be conducted in
20 a manner generally consistent with PSE's approach to all large capital projects.
21 The requirement to incorporate the FERC mandated Board of Consultants into the

1 project has resulted in some deviation from a standard construction project in that
2 studies and design often progressed concurrently. The project execution will be
3 operated consistent with best practices for project management and construction
4 management in use throughout the energy industry. A Project Implementation
5 Plan has been maintained during the project development and is considered a
6 living document that will continue to be updated as the project moves forward.
7 Detailed execution plans are developed for individual phases of the project and
8 will be captured in the construction management system being maintained by
9 PSE's construction management contractor. Schedule and project costs will be
10 closely monitored and tracked throughout the life of the project.

11 **Q. In addition to PSE's Board of Directors, what internal organizations have**
12 **been and will continue to be involved in planning the BRH Project?**

13 A. PSE has engaged subject matter experts from across a range of its operating teams
14 to plan the BRH Project, including: Dam Safety, Resource Sciences and Asset
15 Management, Project Management, Project Controls, Procurement, Financial
16 Planning and Analysis, Internal Legal, Internal Audit, Environmental Services,
17 and Licensing and Permitting.

18 Each of these functions will be critical to ensuring a successful project execution
19 process. Please see Table 1 below for an explanation for how each will contribute
20 to cost-effective project execution.

Table 1: PSE Internal Organizations

Function	Description
Dam Safety	This project has been developed in response to a potential dam safety issue, and the Dam Safety team has been intimately involved to make sure it can be executed without causing harm to the existing dam and appurtenant structures.
Project Management	The Project Manager is an experienced industry professional with 27 years of heavy construction experience. The Project Manager is part of the Dam Safety team and will be responsible for managing of the project's budget, scope, and schedule. PSE has contracted with an outside construction management firm to assist the Project Manager.
Project Controls	PSE has engaged an external construction management firm to conduct all project controls so that the project is executed in a manner consistent with the project design and contract terms. PSE personnel will provide technical oversight of the construction management firm and provide guidance when needed.
Procurement	The Procurement team has been instrumental in all phases of the project, including issuing RFPs and awarding contracts for engineering services, construction management services, and construction. The procurement team will remain a core function to certify that all resources are procured in a manner consistent with PSE's corporate procurement processes and regulatory obligations.
Quality Assurance/Quality Control	PSE's QA/QC organization will see that project execution, including assembly of safety-related equipment, is consistent with industry best practices.
Internal Audit	The Internal Audit function conducts assessments of the budgeting and invoicing practices and will ascertain that project costs are appropriate and properly allocated to PSE's cost centers. Also, PSE's project management staff will review all invoices with the external construction management firm.
Resource Sciences and Asset Management and Environmental Services	The Resource Sciences and Asset Management and Environmental Services teams work collaboratively to guaranty that the planning and execution of the BRH Project's grouting work is completed in a manner consistent with PSE's environmental obligations related to migratory fish pathways and other environmental and wildlife-related concerns. PSE has contracted with an expert environmental and engineering firm to confirm compliance with all project regulated activities.
Licensing & Permitting	The Licensing and Permitting group will obtain and maintain all necessary permits for the project period and the period of the BRH Project's continued operations after grouting and modernization are completed. PSE is working with two external firms to make sure PSE complies with all permit conditions.

1
2 **Q. Please describe how PSE plans to manage the BRH Project in the planning,**
3 **execution, and commissioning phases of work.**

4 A. PSE has designated a full-time senior project manager and senior construction
5 manager to oversee this project. As of Q3 2021, the planning phase is complete
6 and the project has moved into execution. To assist PSE during the execution
7 phase, PSE has hired a construction management firm, HDR, Inc., with extensive
8 experience in complex and high-risk hydroelectric projects. The firm will provide
9 industry experts to conduct the following services: assist in managing day-to-day
10 construction activities, inspect on-site activities to conform with project plans and
11 specifications, monitor conformance with environmental permits/conditions,
12 oversee administrative process (i.e. document management), evaluate contractor's
13 schedule (including critical-path items), and perform cost evaluations and
14 contractual validity assessment for all proposed change orders.

15 PSE has also retained the services of the design Engineer of Record, Shannon &
16 Wilson, Inc., to be onsite during all drilling and grouting operations. Their role
17 will be to oversee construction activities so they conform with the project design
18 documents.

19 **Q. What mechanisms does PSE have in place to prudently manage the BRH**
20 **Project throughout its planning and implementation?**

21 A. PSE's Project Practices Center of Excellence ("COE") organization will require
22 monthly reporting for the BRH Project. PSE's senior project manager assigned to

1 this project will develop these reports. Items captured in each report include:
2 status (progress), budget (anticipated versus actual costs), schedule (anticipated
3 versus actual durations), and on-going risk identification and assessment. The
4 COE will evaluate each report and share with PSE executives.

5 **V. PROJECT MILESTONES COMPLETED AND EXPECTED DURING**
6 **THE RATE PLAN**

7 **Q. What major milestones have been completed to date?**

8 A. Initiation and planning phases have been completed. Permitting is underway and
9 on schedule. The contract with the major execution team is signed and ready for
10 the execution phase. FERC is currently reviewing the required project
11 documentation.

12 **Q. What are the key milestones for the BRH Project from 2021 through 2025?**

13 A. Early contractor involvement occurred from Q4 of 2020 into Q4 of 2021, and the
14 contract and pricing negotiations were finalized in Q4 2021. Submittals and pre-
15 construction started in Q4 of 2021 and will continue into Q1 of 2022.

16 Mobilization and site preparation will follow in Q1 and Q2 of 2022. Vertical
17 tiedown anchors and temporary platform construction will begin in Q2 of 2022
18 and continue through Q3 of 2023, at which point drilling and grouting will
19 commence. Drilling and grouting will then be the longest phase, extending from
20 Q3 2023 through Q4 2024. Deconstruction, demobilization, and final inspection

1 will take place through 2025, and the project is expected to be finalized by July
2 2025. The total project construction is expected to take approximately 44 months.

3 **VI. CONCLUSION**

4 **Q. What plans does PSE have in place to brief the Washington Utilities and**
5 **Transportation Commission and its Staff apprised of the BRH Project's**
6 **modernization and grouting progress?**

7 A. At a minimum, PSE project staff will provide updated project reports at
8 significant project milestones. In addition to project updates, Commission staff
9 will be invited to visit the site at those same project milestones.

10 **Q. Does this conclude your prefiled direct testimony?**

11 A. Yes, it does.