EXH. CJP-11 DOCKETS UE-240004/UG-240005 2024 PSE GENERAL RATE CASE WITNESS: CRAIG J. POSPISIL

BEFORE THE WASHINGTON UTILITIES AND TRANSPORTATION COMMISSION

WASHINGTON UTILITIES AND TRANSPORTATION COMMISSION,

Complainant,

v.

PUGET SOUND ENERGY,

Respondent.

Docket UE-240004 Docket UG-240005

TENTH EXHIBIT (NONCONFIDENTIAL) TO THE PREFILED DIRECT TESTIMONY OF

CRAIG J. POSPISIL

ON BEHALF OF PUGET SOUND ENERGY



Queued Up:

Characteristics of Power Plants
Seeking Transmission Interconnection
As of the End of 2022

Joseph Rand, Rose Strauss, Will Gorman, Joachim Seel, Julie Mulvaney Kemp, Seongeun Jeong, Dana Robson, Ryan Wiser

Lawrence Berkeley National Laboratory

April 2023

This work was funded by the U.S. Department of Energy under Contract No. DE-AC02-05CH11231. The views and opinions of the authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof, or The Regents of the University of California.

Image source: Licensed from Shutterstock



Contents

- High-Level Findings
- Methods, Data Sources, and Background
- Active Queue Projects Summary
 - Active queue volume & time trends
 - Regional trends
 - Expected online year and current study status
 - Hybrid projects in the queues
- Completed and Withdrawn Projects Summary
 - Volume of completed and withdrawn projects
 - Completion percentages
- Duration Trends Time in Queues
- Conclusions

What are interconnection queues?


Utilities and regional grid operators (a.k.a., ISOs or RTOs) require projects seeking to connect to the grid to undergo a series of studies before they can be built. This process establishes what new grid system upgrades may be needed before a project can connect to the system and then estimates and assigns the costs of that equipment. The lists of projects that have applied to connect to the grid and initiated this study process are known as "interconnection queues".

Visit https://emp.lbl.gov/queues to download the data used for this analysis and to access an interactive data visualization tool




High-Level Findings





Completion rates are generally low; wait times are increasing


 Only ~21% of projects (14% of capacity) requesting interconnection from 2000-2017 reached commercial operations by the end of 2022



- Completion rates are even lower for wind (20%) and solar (14%)
- The average time projects spent in queues before being built has increased markedly. The typical project built in 2022 took 5 years from the interconnection request to commercial operations¹, compared to 3 years in 2015 and <2 years in 2008.

Proposed capacity is widely distributed across the U.S.


- Substantial proposed solar capacity exists in most regions of the U.S.; 947 GW of solar active in queues
- Wind capacity is highest in NYISO, the non-ISO West, PJM, and SPP, with increasing share of offshore projects
- Storage is primarily in the West and CAISO, but also strong in ERCOT, MISO, and PJM; much in hybrid configurations
- Only 82 GW of gas capacity active in the queues, less than 10% of active solar capacity





Methods and Data Sources


- Data collected from interconnection queues for 7 ISOs / RTOs and 35 utilities, which collectively represent >85% of U.S. electricity load
 - Projects that connect to the bulk power system, not behindthe-meter
 - Includes projects in queues through the end of 2022
 - The full sample includes:
 - 3,846 "operational" projects
 - 10,262 "active" projects
 - 374 "suspended" projects
 - 15,672 "withdrawn" projects
- Hybrid / co-located projects were identified and categorized
 - Storage capacity in hybrids (separate from generator capacity)
 was estimated based on available data for some projects
- Note that being in an interconnection queue does not guarantee ultimate construction





Typical Interconnection Study Process and Timeline


- A project developer initiates a new interconnection request (IR) and thereby enters the queue
- A series of interconnection studies
 establish what new transmission equipment
 or upgrades may be needed and assigns the
 costs of that equipment
- The studies culminate in an interconnection agreement (IA): a contract between the ISO or utility and the generation owner that stipulates operational terms and cost responsibilities
- Most proposed projects are withdrawn,
 which may occur at any point in the process
- After executing an IA, some projects are built and reach commercial operation







There has been a substantial increase in annual interconnection requests (both in terms of number and capacity) since 2013; over 700 GW added in 2022 alone



Decrease in new requests in 2022 likely driven by "pauses" on new requests in CAISO and PJM (see slide 9).






Active Projects in Interconnection Queues: Volume, Regional Trends, Hybrids, and Timelines

Region	n (Active)
CAISO	495
ERCOT	902
ISO-NE	350
MISO	1,734
NYISO	459
PJM	3,042
SPP	571
Southeast (non-ISO)	830
West (non-ISO)	1,879



Over 2,000 GW (2 TW) of generation & storage capacity active in queues; Especially strong developer interest in solar (~947 GW) and storage (~680 GW), including hybrids




- Hydropower
- Geothermal
- Biomass/biofuel
- Landfill gas
- Solar thermal
- Oil/diesel

See https://emp.lbl.gov/queues to access an interactive data visualization tool.



Notes: (1) *Hybrid storage capacity is estimated for some projects using storage:generator ratios from projects that provide separate capacity data, and that value is only included starting in 2020. Storage duration is not provided in interconnection queue data. (2) Wind capacity includes onshore and offshore for all years, but offshore is only broken out starting in 2020. (3) Hybrid generation capacity is included in all applicable generator categories. (4) Not all of this capacity will be built.


Active queue capacity highest in the non-ISO West (598 GW), followed by MISO (339 GW) and PJM (298 GW). Solar and storage requests are booming in most regions.






Active capacity in queues (~2,040 GW) exceeds installed capacity of entire U.S. power plant fleet (~1,250 GW), as well as peak load and installed capacity in most ISO/RTOs

Entire U.S. Installed Capacity vs. Active Queues






Comparisons aueue capacity to installed capacity or peak load should also consider generators' contributions to resource adequacy, for example their "effective load carrying capability" (ELCC). As variable resources, solar and wind contribute a smaller percentage of their nameplate capacity to resource adequacy compared to dispatchable generation like natural gas.

Decarbonizing electric therefore requires higher levels of installed solar and wind capacity to achieve the same resource adequacy contributions. High levels of storage can offset this need to some degree. Electrification of buildings and transport will also result in load growth.




Proposed solar is widespread, with less in SPP and Northeast; Most wind in the West and offshore East Coast; Most storage in the West and CAISO, but expanding; Gas is primarily in the Southeast and West







Most proposed solar TX, AZ, IN, CA; proposed wind is mainly offshore, TX, and Great Plains; storage is predominantly in CA, TX, AZ; Proposed gas in TX and Southeast





62% (1,262 GW) of total capacity in queues has proposed online date by end of 2025; 13% (257 GW) already has an executed interconnection agreement (IA)









Notes: (1) *Hybrid storage capacity is estimated for some projects. (2) Proposed online dates are included in the developer's original interconnection request, and may differ from actual online date. (3) Not all of this capacity will be built. (4) Study status categories are simplified, not all queues identify projects under construction

Interest in hybrid plants has increased over time: Hybrids comprise 52% of active storage capacity (358 GW), 48% of solar (457 GW), and 8% of wind (24 GW)





- Solar Hybrids include: Solar+Storage (431 GW), Solar+Wind (3 GW), Solar+Wind+Storage (8 GW)
- Wind Hybrids include: Wind+Storage (19 GW), Wind+Solar (1 GW), Wind+Solar+Storage (4 GW)
- Storage Hybrids may be paired with any generator type; most are paired with solar
- **Gas Hybrids** include: Gas+Solar+Storage (13 GW), Gas+Storage (0.4 GW), Gas+Solar (0.3 GW) [not shown above]



Hybrids comprise a sizable fraction of all proposed solar plants in multiple regions; wind hybrids are less common overall but still a large proportion in CAISO

Region	% of Proposed Capacity Hybridizing in Each Region			
	Solar	Wind	Gas	Storage
CAISO	97%	45%	15%	53%
ERCOT	42%	4%	3%	42%
ISO-NE	33%	0%	0%	8%
MISO	34%	12%	0%	n/a
NYISO	19%	0%	0%	n/a
PJM	24%	1%	0%	21%
SPP	18%	1%	0%	n/a
Southeast (non-ISO)	21%	0%	0%	n/a
West (non-ISO)	81%	17%	74%	n/a
TOTAL	48%	8%	17%	n/a





Commercially Operational & Withdrawn Projects: Volume and Completion Rates

Withdrawn project data were collected from 7 ISO/RTOs, and 31 non-ISO utilities, totaling 15,672 projects.


Region	n (Operational)		
CAISO	199		
ERCOT	314		
ISO-NE	305		
MISO	452		
NYISO	88		
PJM	1,061		
SPP	261		
Southeast (non-ISO)	303		
West (non-ISO)	863		

Region	n (Withdrawn)
CAISO	1,580
ERCOT	736
ISO-NE	600
MISO	1,885
NYISO	713
PJM	3,558
SPP	1,135
Southeast (non-ISO)	1,777
West (non-ISO)	3,687

Notes: (1) The number of operational and withdrawn projects with available data may be fewer than the total number of operational or withdrawn projects for each entity. (2) Data were sought from 7 ISO/RTOs and 35 utilities; operational and withdrawn project data are not always available.




Volume (number and capacity) of operational and withdrawn projects are increasing year-over-year, but with a marked decrease in projects coming online in 2022






Only 21% of all projects proposed from 2000-2017¹ had reached commercial operations by the end of 2022 – 72% had withdrawn from queues






There is considerable variation in completion rates across regions and types; solar (14%) has a lower completion rate from 2000-2017 than other types




Completion percentage by generator type:






Note: (1) Completion rate shown here is calculated by <u>number</u> of projects online by end of 2022, not capacity-weighted. (2) Calculated as number of projects operational as of EOY 2022 divided by the total number of requests per year. (3) Includes data from 7 ISO/RTOs and 26 utilities.

Capacity-weighted completion rates are even lower: Only 14% of all capacity requesting interconnection from 2000-2017 is online; 16% of wind capacity, 10% of solar capacity




Percentage of capacity online by generator type:





Notes: (1) Completion rate shown here is capacity-weighted, calculated as the capacity that is online by end of 2022 divided by the total capacity requesting interconnection each year. (2) Includes data from 7 ISO/RTOs and 26 utilities.


The share of projects requesting interconnection from 2000-2017 that have reached COD is relatively low across regions: Only ISO-NE and ERCOT exceed 30% completion



- Capacity-weighted completion rates are even lower; shown in brackets [%]
 - ERCOT is the only region with >20% of capacity reaching commercial operation date (COD)
- For interconnection requests from 2000-2017, ISO-NE (37%) and ERCOT (31%) had the highest project completion percentages, with CAISO (13%) and NYISO (15%), and the Southeast (15%) lower on average
- These rates are variable by year, and trends may be shifting as queue volumes and reforms evolve
- The difference between regions, temporal trends, and the implications of these low rates on electric-sector decarbonization, are important areas for future research



More recently proposed projects are taking longer to make the decision to withdraw as study durations lengthen; later-stage withdrawals are becoming more common



Interconnection Study Phase Upon Withdrawal 80% Withdrawn Year 70% 2003-2006 2007-2010 2011-2014 ■ 2015-2018 **2019-2022** p 30% Percentage 6 10% 0% Feasibility System Impact Facility Pending/Executed


Final outcome (i.e., withdrawn or operational) for many projects entering the queues in recent years may not yet be determined (i.e., they are still "active"); cumulative percent withdrawn will increase over time.

Late-stage withdrawals can be more costly for developers (sunk costs, deposits) and can trigger re-studies for other projects in the queue, increasing delays.






Duration Trends: How Long Do Projects Spend In the Queues?




The median duration from request to withdrawn date ticked up in 2022; wind projects typically spend more time in queues than gas or solar prior to withdrawing






Although median withdrawal duration has been relatively consistent over time, the *mean* withdrawal duration and distributions have edged higher in recent years



- This trend implies that some recentlywithdrawn projects are waiting longer in the queues before making the determination to withdraw
- This corroborates the findings on cumulative withdrawal rates and latestage withdrawals illustrated on Slide 22
- Later stage withdrawals can be costly for developers and can disrupt assumptions built into other projects' interconnection studies, necessitating re-studies in some cases and lengthening study durations




After falling from a 2012 peak, the typical duration from interconnection request (IR) to interconnection agreement (IA) increased sharply since 2015, reaching 35 months in 2022






Study duration is increasing in many regions, exceeding 3 years in PJM, SPP, NYISO, and MISO for IAs executed from 2018-2022; ERCOT and Southeast are notably faster






Wind projects typically face longer interconnection study timelines; recent battery projects are processed much more quickly





Notes: (1) Data are only shown where sample size is >2 for each type and year. (2) Not all data used in this analysis are publicly available.


There is a clear step change in IR to IA duration between "small" (<20 MW) and "large" (>20 MW) generator interconnection procedures



- On average, projects with rated capacity <20 MW complete studies and execute interconnection agreements much faster than larger projects
 - Median is 11 months for projects <5 MW</p>
 - 15 months for projects 5 <20 MW
- The median duration for projects 20 MW or larger hovers around 30 months across the four larger project groups analyzed
- 20 MW is the threshold between the FERC "large" and "small" generator interconnection procedures (LGIP / SGIP)
 - The median LGIP duration is twice the median SGIP duration for projects in our sample




Typical duration from IA to commercial operations date (COD) has increased modestly since 2007, except in CAISO where recently built solar projects took 4-6 years *after* securing an IA






The median duration from interconnection request (IR) to commercial operations date (COD) continues to rise, reaching ~5 years for projects completed in 2022






IR to COD timelines are longest in CAISO, NYISO, and SPP; solar and wind projects typically take longer than other types, with standalone battery projects moving fastest to completion






Larger projects have longer development timelines: Typical IR to COD duration increases monotonically by project size (MW)





Notes: (1) Box-plot includes projects reaching commercial operations from 2010-2022. (2) Includes data from 6 ISOs and 5 utilities. (2) Duration is calculated as the number of months from the queue entry date to the in-service date.

Solar and wind developers' proposed timelines (from IR to <u>proposed</u> online date) have trended upward since 2010, accounting for lengthening development times





Conclusions

- Solar (947 GW) accounts for >70% of all active generator capacity in the queues, though substantial wind (300 GW) and gas (82 GW) capacity is also in development. 113 GW of offshore wind is currently active in the queues.
- □ Considerable standalone (325 GW) and hybrid (~358 GW¹) storage capacity has also requested interconnection.
- □ The combined capacity of solar and wind now active in the queues (~1,250 GW) approximately equals the total installed U.S. power plant fleet capacity, and is greater than the estimated 1,100 GW needed to approach a zero-carbon electricity target².
- Capacity in queues is widespread across U.S. but some states dominate: Texas has 13% of proposed solar, storage, and gas, and
 7% of proposed wind; New York has 23% of all proposed wind (mostly offshore); California has 14% of proposed storage.
- □ Hybrids now comprise a large and increasing share of proposed projects, particularly in CAISO and the West. 457 GW of solar hybrids (primarily solar+battery) and 24 GW of wind hybrids are in the queues.
- The majority (62%) of capacity in the queues is proposed to come online before 2025, and some (13%) already has an executed interconnection agreement (IA).
- The time projects spend in queues before reaching COD is increasing. For the regions with available data³, the median duration from IR to COD has doubled from <2 years for projects built in 2000-2007 to nearly 4 years for those built in 2018-2022.
 - The typical full interconnection study duration (from IR to IA) has also increased sharply, exceeding 3 years in many regions.
 - Larger projects have longer development timelines; interconnection study duration increases notably for projects >20 MW.
- Ultimately, much of this proposed capacity will not be built. Historically only ~21% of projects (and only 14% of capacity) requesting interconnection from 2000-2017 have reached commercial operations. As well, late-stage withdrawals may be on the rise.





Contact:

Joseph Rand (<u>irand@lbl.gov</u>)

More Information:

- Visit https://emp.lbl.gov/queues to download the data used for this analysis and access an interactive data visualization tool
- Visit https://emp.lbl.gov/interconnection costs for related research on generator interconnection costs

Acknowledgements:

This work was funded by the U.S. Department of Energy's Office of Energy Efficiency and Renewable Energy, in particular the Solar Energy Technologies Office and the Wind Energy Technologies, in part via the Interconnection Innovation eXchange (i2X). We thank Ammar Qusaibaty, Michele Boyd, Juan Botero, Cynthia Bothwell, Jian Fu, Patrick Gilman, Gage Reber, and Paul Spitsen for supporting this project.

Disclaimer

This document was prepared as an account of work sponsored by the United States Government. While this document is believed to contain correct information, neither the United States Government nor any agency thereof, nor The Regents of the University of California, nor any of their employees, makes any warranty, express or implied, or assumes any legal responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by its trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof, or The Regents of the University of California. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof, or The Regents of the University of California.

Ernest Orlando Lawrence Berkelev National Laboratory is an equal opportunity employer.

Copyright Notice

This manuscript has been authored by an author at Lawrence Berkeley National Laboratory under Contract No. DE-AC02-05CH11231 with the U.S. Department of Energy. The U.S. Government retains, and the publisher, by accepting the article for publication, acknowledges, that the U.S. Government retains a non-exclusive, paid-up, irrevocable, worldwide license to publish or reproduce the published form of this manuscript, or allow others to do so, for U.S. Government purposes






Appendix




Active solar capacity in queues: by county






Active <u>standalone</u>¹ storage capacity in queues: by county






Active wind capacity in queues: by county





Active gas capacity in queues: by county





Balancing Areas Included In Data:

IS	O/RTOs	Other (non-ISO) Transmission Operators				
	РЈМ	Southern Company	Associated Electric Coop.	LG&E & KU Energy	Portland General Electric	Public Service Co. of NM
	MISO	Tennessee Valley Authority	PSCO	Salt River Projects	Idaho Power	Avista
E	ERCOT	Duke/Progress	Santee Cooper	NV Energy	Florida Municipal Power Pool	El Paso Electric
	SPP	WAPA	Georgia Transmission Corp.	Navajo-Crystal	Tri-State G&T	Imperial Irrigation District
	NYISO	Florida Power & Light	Arizona Public Service	Dominion	Jacksonville Electric Authority	Platte River Power Authority
	CAISO	Bonneville Power Admin.	LADWP	Puget Sound Energy	Tucson Electric Power	Black Hills Colorado
ı	ISO-NE	PacifiCorp	Seminole Electric Coop.	Tampa Electric Co.	NorthWestern	Cheyenne Light Fuel & Power

