MATCHLINE STA. 21+50
SEE DRAWING C3

EXST. CURB AND GUTTER
SIDEWALK
RAISE EXST SSMH TO FINAL GRADE
CONSTRUCT NEW SIDEWALK PER CITY OF RICHLAND STANDARDS
EXST. 8" PVC SS
RAISE EXST SSMH TO FINAL GRADE
EXISTING RETENTION POND
USP
STA. 26+80, 48'L END SIDEWALK
NEW CURB, RAMP, AND LANDING
PAVING LIMIT
EXST SIDEWALK
22+00
23+00
24+00
25+00
26+00
27+00
70' R/O.W.
48'
N01°50'14"E
656.92'
R=20'
L=27.18'
RAISE EXST VALVE BOX TO FINAL GRADE
RAISE EXST VALVE BOX TO FINAL GRADE
RAISE EXST VALVE BOX TO FINAL GRADE
EXISTING PROPERTY LINE

NOTE:
REMOVE EXISTING ASPHALT RAMPS AT DRIVEWAY LOCATIONS AND AT STA 26+70 PRIOR TO ANY ASPHALT OVERLAY WORK.

STA. 26+60
START NEW CURB, RAMP, SIDEWALK AND CONCRETE LANDING

CALL 2 WORKING DAYS BEFORE YOU DIG
1-800-424-5555

ALL UTILITIES & STRUCTURES ARE NOT SHOWN. THE LOCATION OF THOSE SHOWN ARE APPROXIMATE. THE CONTRACTOR IS RESPONSIBLE TO FIELD VERIFY BOTH UNDERGROUND AND ABOVEGROUND EXISTING CONDITIONS. NOTIFY A/E FOR RESOLUTION AND MAKE MINOR CHANGES TO NEW CONSTRUCTION AT NO COST TO THE OWNER.

0' 20' 40'

SITE PLAN
STA. 21+50 TO END OF PROJECT
SCALE: 1" = 20'

EXST 12" SD @ 5.7%
EXST SDCB-1
STA. 21+57, RIGHT
N. INV. OUT: 434.00
EXST SDCB-2
STA. 22+10, RIGHT
S. INV. IN: 432.00
EXST 8" WATERLINE
EXISTING ROAD GRADE
EXST SDCB-4
STA. 24+45, LEFT
E. INV. IN: 418.03
N. INV. OUT: 418.03
EXST 8" SANITARY SEWER
EXST 12" SD @ 5.7%
EXST 12" SD @ 1%
EXST SDMH-OIL/WATER SEPARATOR
STA. 26+50, LEFT
RIM: 409.65
S. INV. IN: 405.20
N. INV. IN: 405.00
W. INV. OUT: 405.00
EXST SDCB-6
STA. 26+77, LEFT
E. INV. IN: 405.32
SW. INV. IN: 405.32

450
440
430
420
410
400
395

22+00	23+00	23+50	24+00	25+00	26+00	27+00
439.0 / 438.70	436.6 / 435.80	433.7 / 432.96	430.7 / 430.00	427.7 / 427.10	424.7 / 424.20	421.7 / 421.30	418.7 / 418.40	415.5 / 415.50	412.6 / 412.60	410.0 / 409.78	409.2 / 409.29	409.4

PROFILE
STA. 16+50 TO STA. 21+50
HORIZONTAL SCALE: 1" = 20'
VERTICAL SCALE: 1" = 5'

Exhibit 4

2 PRELIMINARY
PLOT DATE: 05/6/03 MER
H:\AG\5854.010\DWG\5854BASE.DWG 03/20/03 12:31:27 PM

REGION NUMBER	STATE	FEDERAL AID PROJECT NUMBER
??	??	??

12:31 15.06a (LMS Tech) 03/20/03 DATE OF ISSUE

NO	DATE	BY	DESCRIPTION	APPROVED

© 2003 SCM Consultants, Inc.

DRAWN MER
CHECKED
DESIGN GM
DESIGN A/E
SCM APPROVAL

CITY OF KENNEWICK
N. CENTER PARKWAY EXTENSION

SCM Consultants, Inc. Architects & Engineers Kennewick, WA. 99336

PLAN AND PROFILE
STA. 21+50 TO END

PROJECT NUMBER: 5854.010
CAD FILE: 5854BASE.DWG

DRAWING NUMBER C4
REV 0