Exh. PCD-1T Docket UG-21____ Witness: Patrick C. Darras

BEFORE THE WASHINGTON UTILITIES AND TRANSPORTATION COMMISSION

WASHINGTON UTILITIES AND TRANSPORTATION COMMISSION,

Complainant,

v.

CASCADE NATURAL GAS CORPORATION,

Respondent.

DOCKET UG-21____

CASCADE NATURAL GAS CORPORATION

DIRECT TESTIMONY OF PATRICK C. DARRAS

September 30, 2021

TABLE OF CONTENTS

I.	INTRODUCTION		
II.	SCOPE AND SUMMARY OF TESTIMONY		
III.	OVE	RVIEW OF PROJECT SELECTION AND BUDGETING PROCESS	4
IV.	MAJ	OR CAPITAL PROJECTS	12
	A.	Wallula Gate Project	16
	B.	Othello Gate Project	24
	C.	Walla Walla Gate Project	27
	D.	Arlington Gate Project	32
	E.	Bellingham 8" HP Project	37
	F.	Moses Lake 4" PE Project	39
	G.	Walla Walla 6" Distribution Project	43
	H.	Bremerton Reg Station Project	48
	I.	Kennewick Odorizer Project	50
	J.	Bremerton Office Project	52
V.	OTHER MAJOR CAPITAL PROJECTS		
VI.	BLA	NKET FUNDING PROJECTS	56
VII.	CUSTOMER CARE AND BILLING SYSTEM UPGRADE		

LIST OF EXHIBITS

1. Exh. PCD-2 Summary of 2020 Capital Projects

I. INTRODUCTION

1	Q.	Please state your name, business address, and position.
2	A.	My name is Patrick C. Darras and my business address is 400 North Fourth Street,
3		Bismarck, North Dakota 58501. I am the Vice President – Engineering & Operations
4		Services for Cascade Natural Gas Corporation ("Cascade" or "Company"), a wholly-
5		owned subsidiary company of MDU Resources Group, Inc. ("MDU Resources"). I am
6		also the Vice President – Engineering & Operations Services for Intermountain Gas
7		Company ("Intermountain"), Montana-Dakota Utilities Co. ("Montana-Dakota"), and
8		Great Plains Natural Gas Co. ("Great Plains"), subsidiaries of MDU Resources.
9	Q.	Please describe your duties and responsibilities with Cascade.
10	A.	I have executive responsibility for the development, coordination, and implementation of
11		Company strategies and policies related to engineering and operations, including design,
12		construction, compliance, and pipeline integrity and safety.
13	Q.	Please outline your educational and professional background.
14	A.	I am a graduate of North Dakota State University with a Bachelor of Science Degree in
15		Construction Engineering. I also hold a Master of Business Administration and a
16		Master's Degree in Management, both from the University of Mary. In June 2014 I
17		attended the Utility Executive Course at the University of Idaho.
18		I began my career in 2002 as a gas engineer with Montana-Dakota in Bismarck,
19		North Dakota. I held that position for four years, primarily working with the construction
20		and service group in day to day operations. In 2006, I was promoted to the role of Region
21		Gas Superintendent in which I was responsible for the overall gas engineering,

1	construction, and service of the Dakota Heartland Region of Montana-Dakota. I worked
2	in that capacity for two years and was then promoted to Region Director for Montana-
3	Dakota's Dakota Heartland Region and Great Plains. In this role, I was responsible for
4	oversight of all gas and electric operations for the Region. In January 2015, I accepted the
5	promotion to Vice President of Operations for Montana-Dakota and Great Plains. My
6	responsibilities in this role included gas and electric distribution operations and
7	engineering across the five states of North Dakota, South Dakota, Montana, Wyoming,
8	and Minnesota. In June 2018, I accepted my current role of Vice President – Engineering
9	and Operations Services.

10Prior to joining Montana-Dakota, I worked for a local industrial contractor11specializing in refinery and power plant maintenance along with turn-key construction of12industrial facilities such as refineries and food processing plants. I spent seven years with13this group in various capacities in engineering, construction, and project management.

II. SCOPE AND SUMMARY OF TESTIMONY

14 Q. Wh

What is the purpose of your testimony?

15 A. The purpose of my testimony is to:

16	(1)	provide an overview of the Company's project selection and budgeting
17		process;

- 18 (2) provide an overview of the Company's major capital projects that have
 19 been completed since the test year in the last rate case, which include:
- Wallula Gate Station and 12" High Pressure ("HP")
 Reinforcement,

1		• Othello Gate Station Reinforcement and Northwest Pipeline
2		("NWP") Lateral Upgrade project,
3		• Walla Walla Gate Station and 6" HP Line Reinforcement,
4		• Arlington Gate Station and 6" HP Reinforcement project,
5		• Bellingham 8" HP Relocation project,
6		• Moses Lake 4" Polyethylene (PE ¹) Reinforcement project,
7		• Walla Walla 6" Steel and PE Distribution Reinforcement project,
8		• Bremerton Regulator Station Replacement project,
9		• Kennewick and Richland Odorizer Replacement projects, and
10		• Bremerton District Office Remodel.
11		(3) describe the Company's blanket funding projects; and
12		(4) provide an update to the Company's Customer Care and Billing System
13		Upgrade.
14		As I explain in detail in my testimony, the Company has carefully evaluated its system
15		needs and potential alternatives and selected the proposed capital projects that will
16		benefit the system and its customers.
17	Q.	Are you sponsoring any exhibits in this proceeding?
18	A.	Yes, I sponsor the following exhibit:
19		Exh. PCD-2 Summary of 2020 Capital Projects

¹ PE is polyethylene (plastic) pipe only used for distribution pressure, operating less than 60 psig.

III. OVERVIEW OF PROJECT SELECTION AND BUDGETING PROCESS

1	Q.	Please describe how the Company selects and budgets for capital projects.
2	A.	The Company prioritizes capital projects that improve safety and reliability. The bulk of
3		Cascade's major capital projects are either pipeline replacement projects that have been
4		identified for safety reasons and to reduce risk on Cascade's system, or system
5		reinforcements or system expansions that are needed to ensure system reliability and to
6		accommodate growth on the Company's system. A reinforcement is an upgrade to
7		existing infrastructure or a new system addition, which increases system capacity,
8		reliability, and safety. An expansion is a new system addition to accommodate an
9		increase in demand. Collectively, reinforcements and expansions are known as
10		distribution system enhancements. Distribution system enhancements do not reduce
11		demand, nor do they create additional supply. Instead, enhancements can increase the
12		overall capacity of a distribution pipeline system while utilizing existing gate station
13		supply points. The two broad categories of distribution enhancement solutions are
14		pipelines and regulators.
15	Q.	How does the Company identify safety-related projects?
16	A.	The Company uses the Distribution Integrity Management Program ("DIMP") and the
17		expertise of its own engineers and district managers to identify areas of risk on its system
18		and to develop the safety projects required to remediate risk. The DIMP informs
19		Cascade's understanding of the system and its material characteristics and is used to
20		identify, assess, and prioritize integrity risks to Company-owned and operated
21		infrastructure. The Company reviews and analyzes the DIMP risk model outputs after

Direct Testimony of Patrick C. Darras Docket UG-21____

each model run to identify areas of highest risk and those areas where risk increased from
 the last model run.

Additionally, because the DIMP model does not perfectly capture all risk factors, the Company also considers input from its system engineers, district managers, and other subject matter experts ("SMEs") who have intimate knowledge of specific portions of Cascade's system to identify other areas of potential concern.

7 The Company then considers and analyzes existing and proposed measures to 8 address identified threats to Cascade's pipeline system. The prioritization and selection of 9 appropriate remediation actions depends on (i) the type of threat being addressed, (ii) 10 whether the threat is current or potential, and (iii) the viability of the remedial action in 11 managing the relevant risk factors.

12 Q. What types of projects are typically performed to address safety-related concerns?

A. Pipeline replacement is typically the most viable option to remediate risks associated with
 corrosion, natural forces, material, weld, joint, and/or equipment. If Cascade determines
 that replacement is an appropriate action to reduce the risk, the Company establishes a
 replacement project.

17 Q. How does the Company prioritize and select safety-related projects?

- 18 A. Once pipe segments requiring replacement have been identified via the DIMP, the
- 19 Company plans and prioritizes specific projects within these segments based on risk. This
- 20 process ensures that higher risk threats are mitigated in a timely manner.

1

2

Q. Please provide an overview of Cascade's identification and selection process for distribution enhancement projects.

3 Three primary inputs contribute to the Company's identification and selection of A. 4 distribution enhancement projects. First, Cascade assesses new development in the 5 district, which typically increases capacity needs. The engineering department regularly 6 works closely with energy services representatives and district management to ensure the 7 system is safe and reliable. As towns develop and add new homes and businesses, the 8 need for pipeline expansions and reinforcements increases. Indeed, historically, system 9 expansion projects have been driven by new city developments or new housing plats. 10 Before expansions and installation can be constructed to serve these new customers, the 11 Company performs engineering analysis using system modeling software, Synergi², to 12 represent cold weather scenarios, and to predict the necessary capacity of the system. As 13 new groups of customers seek natural gas service, the Synergi models provide feedback 14 on how best to serve them reliably. 15 Second, Cascade analyzes gate capacity and forecasts constraints. Over time, each 16 gate station will take on more and more demand, and it is Cascade's goal to stay ahead of

- 17 potential reliability issues by predicting and identifying constraints on its system. The
- 18 Company's Integrated Resource Plan ("IRP") growth data, along with design day
- 19

modeling in Synergi, allows Cascade to forecast necessary gate upgrades. Supervisory

² Synergi® is used in conjunction with the GasWorks models that were built years ago and have been upgraded as needed. Synergi® is more advanced than GasWorks and is much more user-friendly. Synergi® is also the modeling software of choice for many other local distribution companies (LDCs).

1	Control and Data Acquisition ("SCADA") technology utilized by Cascade allows		
2	verification of models with real time and historic gate flow and pressure data.		
3	Third, the Company performs demand studies, modeling multiple demand		
4	forecasting scenarios to identify constraints and the corresponding optimum		
5	combinations of pipe-modification and pressure-modification solutions to maintain		
6	adequate pressures throughout the network. After developing a working demand study,		
7	the Company analyzes every system at design day conditions to identify areas where		
8	potential outages may occur. These constraint areas are then risk-ranked against each		
9	other to ensure the highest risk areas are corrected first and that others are properly		
10	addressed. Within a given area of constraint, projects/reinforcements are selected using		
11	the following criteria:		
12 13	• The shortest segment(s) of pipe that improves the deficient part of the distribution system.		
14 15 16 17	• The segment of pipe with the most favorable construction conditions, such as ease of access or rights or traffic issues, and minimal to no impacts to water, railroad, major highway crossings, etc.		
18 19 20	• The segment of pipe that minimizes environmental concerns, including minimal to no impacts to wetlands, and minimizes impacts to local communities and neighborhoods.		
21 22	• The segment of pipe that provides opportunity to add additional customers.		
23	• Total construction costs including restoration.		
24	Once a project/reinforcement is identified, the design engineer or energy services		
25	representative begins a more thorough investigation by surveying the route and filing for		
26	permits. This process may uncover additional impacts such as moratoriums on road		

excavation, underground hazards, discontent among landowners, etc., resulting in another
 iteration of review of the above project/reinforcement selection criteria. Figure 1, below,
 provides a schematic representation of the distribution project process flow.



District Info: **Design Day** IRP Growth Data -City Developments Models -New Housing Plats System Limitation **Computer Model Pressure** Concerns BENEFIT FEASIBILITY ID Potential Projects and **Enhancement Types** (Individually) COST Rank Projects Based On BENEFIT Priority FEASIBILITY соѕт Schedule Into Budget

Figure 1. Distribution Planning Project Process Flowchart

1	Q.	Does the Company also consider demand side management alternatives?		
2	A.	Yes. The Company also reviews the impacts of proposed conservation resources on		
3		anticipated distribution constraints. Although Cascade provides utility-sponsored		
4		conservation programs throughout its Washington service territory, there may be		
5		instances where a more targeted approach could reduce or delay the estimated need for		
6		reinforcement of a specific area. While Cascade attempts to influence these decisions		
7		through its conservation programs, the consumer is still the ultimate decisionmaker		
8		regarding the purchase and use of a conservation measure. Therefore, in the short term,		
9		Cascade does not anticipate that the peak day load reductions resulting from incremental		
10		conservation will be adequate to eliminate distribution system constraint areas. However,		
11		over the longer term, the Company plans to continue to explore opportunities for targeted		
12		conservation programs to provide a cumulative benefit that offsets potential constraint		
13		areas.		
14	Q.	How does the Company's IRP process inform project selection?		
15	A.	Cascade's IRP process helps identify priority projects to ensure adequate upstream		
16		pipeline and downstream distribution capacity to support the existing customer base and		
17		any growth. The IRP analyzes resource needs and evaluates projects based on factors		

15 A. Cascade's IKP process helps identify profits to ensure adequate upstream 16 pipeline and downstream distribution capacity to support the existing customer base and 17 any growth. The IRP analyzes resource needs and evaluates projects based on factors 18 such as safety, economics, and reliability to ensure full-path delivery of natural gas from 19 basin to the customer meter. Analyzing resource needs in the IRP ensures adequate 20 upstream capacity is available to the city gates, especially during a peak event. Securing 21 adequate natural gas supply and ensuring sufficient pipeline transportation capacity to 22 Cascade's city gates are necessary elements for providing gas to the customer.

1		The other essential element that informs project selection is ensuring the
2		distribution system growth behind the city gates is not constrained. Distribution planning
3		focuses on determining if adequate pressure will be available during a peak hour. Given
4		this nuance, distribution planning addresses many of the same goals, objectives, risks,
5		and solutions as resource planning. For example, important parts of the distribution
6		planning process include forecasting local demand growth, determining potential
7		distribution system constraints, analyzing possible solutions, and estimating costs for
8		distribution system enhancements. Individual distribution system projects are then
9		developed and evaluated by Engineering Services with input from local field personnel.
10	Q.	Are all major projects identified in the Company's IRP?
11	A.	No. Generally, the projects that are included in the IRP are distribution enhancement
12		projects, which address system capacity and growth. Safety-related projects are not
13		typically included in the IRP, as they are not driven by system capacity or growth, but
14		rather are required by Federal and State Pipeline Safety regulations and to ensure
15		Cascade is operating its gas system in the safest means possible.
16	Q.	Please provide an overview of Cascade's process for budgeting, planning, and
17		managing capital investments.
18	A.	Capital additions and changes are planned through the annual budget process using
19		PowerPlan ("PP"). The budget process begins with an individual (originator) creating
20		specific funding projects in PP for all new projects to be included in the five-year capital
21		budget. Originators are generally managers at the district level or engineering staff at the
22		corporate level. Sources of information for capital projects include the IRP, DIMP, TIMP
23		("Transmission Integrity Management Program"), state and local government agencies,

1	and internal Cascade personnel. Funding projects are used to hold the capital budget
2	estimates and will be linked to the capital work orders to be created when actual costs
3	commence. A Fixed Asset Financial Analyst reviews the funding projects for proper
4	setup. If the project as submitted is not considered a capital expenditure, it is rejected and
5	sent back to the originator for revision, cancellation, or a move to Operations and
6	Maintenance ("O&M") Expense. After the review has been completed, the Fixed Asset
7	Financial Analyst will add appropriate overheads and approve the funding project.
8	Once all the funding projects have been updated with expenditures, various
9	Company operating managers generate reports to show estimated expenditures and
10	justification for each project. The managers review funding projects and ensure that any
11	necessary changes are made to the estimate and that the project is supported. Reports are
12	then generated by the budgeting personnel for review and approval by the Directors and
13	Vice Presidents of the Utility Group. Any final budget changes are made, and the budgets
14	are then presented to the Utility Group's President for review and approval. The final
15	Utility Group budget is then presented to the MDU Resources Chief Executive Officer
16	("CEO") for review and approval. If the budget is approved by the MDU Resources
17	CEO, the final review and approval occurs with the Board of Directors. At each stage of
18	the review and approval process, a project (or projects) can be challenged for
19	appropriateness and removed from the capital budget or moved to another year within the
20	five-year budget. The addition or removal of projects can also be impacted by other
21	factors such as available capital and/or borrowing capacity.
22	After final approval, an approved budget version is created in PP and locked for
23	entry, and the funding projects and estimated amounts in the approved budget version are

copied back to the working budget version. Project managers are notified that the budget
 has been approved, and the funding projects are opened for work order creation. Projects
 are monitored and updated throughout the year as part of the review process and to
 ensure, as best as possible, that projects are completed on time and within the approved
 budget.

6 Q. Have there been any changes to these processes in the past few years?

7 A. Yes. Beginning in January 2019, the Company's parent, MDU Resources, moved toward 8 a "one utility" model. As a result, the engineering department was reorganized, and more 9 consistent tasks and processes were defined. Within this effort there is a new internal 10 requirement to develop a more robust analysis for any project with a cost estimate over 11 \$1 million. As part of that analysis, the Company develops documentation supporting the 12 project, including a substantial executive summary, Synergi model snapshots, alternatives 13 considered, and timing and justification. The engineering managers and directors 14 collaboratively review all projects and determine which are the most important from a 15 risk standpoint and what the timing of the projects should be to best mitigate risks.

IV. MAJOR CAPITAL PROJECTS

Q. Does the Company propose to include any pro forma capital additions in this case? A. No. In its 2020 general rate case, Docket UG-200568, Cascade proposed recovery for

several pro forma plant additions, and the Commission approved certain investments and
rejected others because they were not yet "used and useful". The major capital

20 investments included in this proceeding were all in service during the test year. I will first

1		provide an ov	verview of the major projects completed in 2020 that are included in this		
2		proceeding and then discuss each project in detail.			
3	Q.	Please provi	Please provide a brief overview of the major capital projects that are included for		
4		recovery in t	his case.		
5	А.	The Company	y is requesting recovery for the following major capital projects that were		
6		completed in	2020:		
7		1.	Wallula Gate Station and 12" HP Reinforcement ("Wallula Gate		
8			Project"). The Wallula Gate Project involved installing a new gate station		
9			at the southernmost point of the Company's Attalia pipeline. The feed to		
10			the Attalia line was to the far north and was undersized to handle the		
11			largest load on the line at the southern end. This new gate station and HP		
12			pipeline has brought a new feed and HP pipe closer to the large loads in		
13			the southern system. Design and construction started in 2019, and the		
14			project was placed in service in December 2020.		
15		2.	Othello Gate Station Reinforcement and Northwest Pipeline ("NWP")		
16			Lateral Upgrade ("Othello Gate Project"). The Othello Gate Project		
17			upgraded the gate station equipment to accommodate the increase in the		
18			NWP Othello lateral pipe and pressure. These upgrades were required due		
19			to insufficient capacity in the lateral and at the gate station to		
20			accommodate increased industrial load and overall historical flows. The		
21			project was completed and fully placed in service in September 2020.		
22		3.	Walla Walla Gate Station and 6" HP Reinforcement ("Walla Walla		
23			Gate Project"). The Walla Walla Gate Project is a reinforcement project		

1		designed to eliminate the need for the district to bypass during cold
2		weather events and to address the supply issues presented by the ongoing
3		growth in the southern area of Walla Walla. The Walla Walla Gate Project
4		was completed and placed in service in December 2020.
5	4.	Arlington Gate Station and 6" HP Reinforcement ("Arlington Gate
6		Project"). The Arlington Gate Project upgrades the existing Arlington
7		Gate station, takes over regulation from NWP, and upgrades the outlet
8		pipe from the station to meet current winter capacities and to
9		accommodate increased gas load in the Arlington system. The Arlington
10		Gate Project was fully placed in service in September 2020.
11	5.	Bellingham 8" HP Relocation ("Bellingham 8" HP Project"). The
12		Bellingham 8" HP Project involved relocating the existing 10" HP main
13		attached to the Bellingham State Street Bridge due to the City of
14		Bellingham rebuilding the State Street Bridge. The project was started in
15		early 2019, and the project was completed and placed in service in January
16		2020.
17	6.	Moses Lake 4" PE Reinforcement ("Moses Lake 4" PE Project"). The
18		Moses Lake 4" PE project included installing approximately 1,800 feet of
19		new 4" PE pipe to loop the northwestern Moses Lake system and
20		improving the pressures to be above design criteria during peak usage.
21		This system reinforcement also improves capacity to allow for ongoing
22		growth in this area of Moses Lake. The project was completed and placed
23		in service in April 2020.

1	7.	Walla Walla 6" Distribution Steel and PE Reinforcement ("Walla
2		Walla 6" Distribution Project"). The Walla Walla 6" Distribution
3		Project was needed to reinforce the existing 4" gas main that has reached
4		maximum capacity based on current models and historic gas usage. The
5		project was completed and placed in service in October 2020.
6	8.	Bremerton Regulator Station Replacement ("Bremerton Reg Station
7		Project"). The Bremerton Reg Station Project included installing one new
8		regulator station to eliminate five smaller regulator stations that were
9		difficult to access and maintain and had a history of leaks. The project was
10		placed in service in November 2020.
11	9.	Kennewick Odorizer Replacement ("Kennewick Odorizer Project").
12		The Kennewick Odorizer Project involved replacing a vintage odorizer
13		with obsolete parts with a new odorizer that performs correctly and can be
14		safely maintained. The project was placed in service in November 2020.
15	10.	Bremerton District Office Remodel ("Bremerton Office Project"). The
16		Bremerton Office Project included remodeling the existing district office
17		located at 6313 Kitsap Way, Bremerton, Washington, 98312. The office
18		remodel was necessary to accommodate added district staff and to
19		reconfigure the outdated space to better meet the current needs of the
20		district operations. This project was completed and placed in service in
21		December 2020.

Table 1, below, is a summary of the projects in a table format.

	TABLE	1		
Line				
No.	Description / Project Name	Actual In Service Date	Act	ual Cost
	Α	В		С
	Major Capital Projects			
1	Wallula Gate Project	12/29/2020	\$	16,969,017
2	Othello Gate Project	9/28/2020	\$	5,314,207
3	Walla Walla Gate Project	12/10/2020	\$	7,551,516
4	Arlington Gate Project	9/3/2020	\$	6,058,267
5	Bellingham 8" HP Project	1/23/2020	\$	1,568,956
6	Moses Lake 4" PE Project	4/23/2020	\$	213,958
7	Walla Walla 6" Distribution Project	10/26/2020	\$	402,969
8	Bremerton Reg Station Project	11/12/2020	\$	134,782
9	Kennewick Odorizer Project	11/20/2020	\$	156,796
10	Bremerton Office Project	12/21/2020	\$	781,146
11	Total Major Capital Projects		¢ 20.1	51 (1)
11 12	Total Major Capital Projects		\$ 39,1	51,014

2 A. <u>Wallula Gate Project</u>

1

3 Q. Please describe the Wallula Gate Project.

- 4 A. This project included installation of a new gate station and 12" HP pipeline connecting to
- 5 the south end of the Attalia pipeline. The Wallula gate station is fed from
- 6 GTN/TransCanada, and the pipeline connecting to the southernmost part of the existing
- 7 Attalia line is roughly 5.5 miles of 12" and 0.5 miles of 8" high-pressure steel pipeline.

Direct Testimony of Patrick C. Darras Docket UG-21____

The overall project area is shown on the map below in Figure 2.

2

1

Figure 2. Wallula Gate Project



4	Q.	Why did the Company undertake the Wallula Gate Project?
5	A.	The Attalia pipeline, in the Kennewick District, was an 8" HP pipeline that was installed
6		in 1958. The pipeline begins at the gate station north of Pasco, Washington, and ends at
7		the Boise Cascade facility along Highway 12 north of the Wallula Junction, covering
8		approximately 17 miles and serving east Pasco and Burbank. The Attalia pipeline
9		provides service to several industrial and large commercial customers. The pipeline
10		operates at an assumed maximum allowable operating pressure ("MAOP") ³ of 300 psig.
11		However, since this pipe is considered "pre-code," this MAOP had not yet been validated

³ MAOP means the maximum pressure at which a pipeline or segment of a pipeline may be operated under 49 CFR Part 192.

1		and this pipeline is part of Cascade's MAOP validation plan. Cascade discovered coating
2		damages to the Attalia pipeline, which led the Company to review the remediation
3		measures in the MAOP validation plan to determine if there was a better way to address
4		MAOP validation. Other issues related to the Attalia pipeline included concerns with
5		shallow bury depth, under-rated fittings, recent damages, material concerns as noted in
6		Cascade's DIMP model, reliability for industrial and commercial customers at the end of
7		the pipeline, the ability to provide for growth in the area, and the possibility that there
8		may be other issues with the aging pipeline that may be unknown. Due to so many
9		unknown variables related to validating the Attalia pipeline MAOP, Cascade determined
10		that the Wallula Gate project best addressed these unknowns and resolved the other
11		system capacity and system integrity issues of the Attalia pipeline.
12	Q.	How do Cascade's customers benefit from the Wallula Gate Project?
12 13	Q. A.	How do Cascade's customers benefit from the Wallula Gate Project? The new gate station, HP pipeline, and regulator station reinforce the Attalia line that had
13		The new gate station, HP pipeline, and regulator station reinforce the Attalia line that had
13 14		The new gate station, HP pipeline, and regulator station reinforce the Attalia line that had low pressures during peak usage at the south end of the line. This project relieves the
13 14 15		The new gate station, HP pipeline, and regulator station reinforce the Attalia line that had low pressures during peak usage at the south end of the line. This project relieves the Burbank Heights gate station that was running over capacity and required manual bypass
13 14 15 16		The new gate station, HP pipeline, and regulator station reinforce the Attalia line that had low pressures during peak usage at the south end of the line. This project relieves the Burbank Heights gate station that was running over capacity and required manual bypass during cold weather events. This project allows Cascade to reduce the MAOP of the
13 14 15 16 17		The new gate station, HP pipeline, and regulator station reinforce the Attalia line that had low pressures during peak usage at the south end of the line. This project relieves the Burbank Heights gate station that was running over capacity and required manual bypass during cold weather events. This project allows Cascade to reduce the MAOP of the existing Attalia line to under 20 percent of the specified minimum yield strength
 13 14 15 16 17 18 		The new gate station, HP pipeline, and regulator station reinforce the Attalia line that had low pressures during peak usage at the south end of the line. This project relieves the Burbank Heights gate station that was running over capacity and required manual bypass during cold weather events. This project allows Cascade to reduce the MAOP of the existing Attalia line to under 20 percent of the specified minimum yield strength ("SMYS") ⁴ and allow for future testing of the line without any interruption of service if

⁴ SMYS is the minimum yield strength, expressed in pounds per square inch, prescribed by the specification under which the material is purchased from the manufacturer.

provides also allows for new growth opportunities including the expanded demand for new and existing industrial customers.⁵ The Synergi diagrams below in Figures 3 and 4, below, illustrate the improvements to the Pasco/Burbank/Wallula system resulting from the Wallula Gate project.



4

1

2

3





Figure 3. Synergi Model: Pasco/Burbank/Wallula – Current Model

⁵ There is a developing industrial park at the southernmost section of the Attalia line, which the new pipeline is running through and will be able to serve. This is also the alignment for the new Highway 12, which will parallel the new pipeline and further attract new customers to this area.

Figure 4. Synergi Model: Pasco/Burbank/Wallula – Improved Model Upon Project Completion



3

4

5

The area in red at the end of the high-pressure pipeline in Figure 3 indicates insufficient pressure to support the existing loads on the system. After the reinforcement

1		in Figure 4, the model shows sufficient pressure to maintain existing customers and
2		provide adequate pressure for new customers.
3	Q.	Did the Company consider alternative ways to meet the need for system
4		reinforcement in the Pasco/Burbank/Wallula system?
5	A.	Yes. In addition to the Wallula Gate Project described above, the Company considered
6		the following alternatives to address the system reinforcement needs:
7		1. <u>Replace the Attalia pipeline</u> : Under this alternative, the Company would
8		replace the Attalia pipeline in its entirety with a 12" HP steel pipeline
9		operating at 500 psig. Replacing the pipeline would eliminate all the
10		MAOP and integrity concerns and increasing the diameter and pressure
11		would allow for future growth. It is likely that the existing right-of-way
12		("ROW") and easements would be able to be utilized, and any issues with
13		the ROW or easements could be corrected during the replacement project.
14		2. <u>Dodd Rd installation with new gate station</u> : Under this alternative,
15		Cascade would install the new proposed gate station and pipeline in a
16		different location and route.
17		3. <u>Replace the Burbank Heights gate and validate the Attalia Line</u> : Under
18		this alternative, Cascade would address the capacity issues of the existing
19		gate station by replacing the existing gate and would perform the MAOP
20		validation of the Attalia line.
21	Q.	Why did the Company reject these alternatives and select the Wallula Gate Project?
22	A.	None of the alternatives that the Company considered would adequately meet the
23		Company's need to provide reliable service in the Pasco/Burbank/Wallula area, resolve

the MAOP validation and integrity issues of the existing Attalia line, and accommodate
 future load growth.

3 The Company determined that it could not pursue the first alternative (replace the 4 Attalia pipeline) because the crossings that would be required presented significant 5 challenges. Surveying, permitting, and planning would be needed for crossing the Snake 6 River, McNary Wildlife Refuge, Casey Pond, Hood Park, and Highways 12 and 395. 7 Permits for some of these crossings could take up to two years to acquire, therefore 8 doubling the length of the project, which would extend the project beyond the MAOP 9 validation commitment. Constructing a pipeline through the populated areas of Burbank 10 and tying over existing regulator stations to the new pipeline would also present 11 challenges.

12 The Company determined that it could not pursue the second alternative (Dodd 13 Rd installation with new gate station) because the alignment would have extended the 14 pipeline distance by over two miles as compared to the Wallula Gate Project and would 15 have had much greater restoration costs because it is located at or near a concrete road 16 with greater elevation challenges.

17 The Company determined that it could not pursue the third alternative (replace 18 Burbank Heights gate and validate the Attalia line) because this option would have 19 addressed only the capacity issues of the gate station and the validation of the Attalia line, 20 and the Company would still have the major concerns of maintaining adequate pressures 21 to serve the existing customer base and allowing new growth. The MAOP validation plan

Direct Testimony of Patrick C. Darras Docket UG-21____

Exh. PCD-1T Page 22 of 58

1		called for <i>in situ</i> testing ⁶ for pipe grade in 2017 and pressure testing in 2019 at an
2		estimated cost of \$784,000 and \$2,000,000, respectively. Thus, Cascade would likely
3		have needed to spend close to \$3,000,000 on testing alone, without performing the
4		needed upgrades.
5		As a result, the Company determined that the Wallula Gate Project was the best
6		option to meet the Company's need for reinforcement in the area, resolve the MAOP
7		validation issues and integrity concerns with the existing Attalia line, and accommodate
8		future growth.
9	Q.	Was the Wallula Gate Project included in the Company's IRP analysis?
10	A.	Yes. The analysis of the Wallula Gate Project (Attalia Pipeline) in the 2018 IRP was
11		completed in 2017 and the cost estimates and timing of the Wallula Gate project
12		described in the 2018 IRP were revised due to minor scope changes and increases in costs
13		for materials and construction.
14	Q.	What was the timing of the project?
15	A.	Design, drafting, permitting and easement acquisitions for the pipeline were completed
16		by February 2019. Construction of the project began in mid-2019, but final completion
17		was delayed due to unexpectedly difficult drilling conditions. The unanticipated drilling
18		conditions resulted in two failed bores while attempting to cross a private rail spur. The
19		failed bore attempts resulted in increased costs associated with additional materials,
20		change orders, and re-mobilizing crews, equipment, and materials. Construction was

⁶ In situ testing refers to pipe wall thickness and grade tests performed on installed piping in the field. Such testing is considered a direct means of establishing existing steel grade of the pipe to inform pipe strength calculations.

- completed in December 2020, and the project was placed in service on December 29,
 2020.
- **3 Q.** What was the cost for the project?
- 4 A. The total actual cost was \$16,969,017, as detailed in Exh. PCD-2.

5 B. <u>Othello Gate Project</u>

- 6 Q. Please describe the Othello Gate Project.
- 7 A. This project includes upgrading and taking over pressure regulation from NWP at the
- 8 existing Othello Gate Station. The project also includes NWP upgrading their Othello
- 9 lateral pipeline to accommodate the increased capacity in the Othello system. The project
- 10 is located in Adams County, Washington, approximately one mile north of the
- 11 intersection of W Herman Rd and Lucy Rd. The project area is shown on the map below
- 12 in Figure 5.
- 13

Figure 5. Othello Gate Project



1

Q.

Why did the Company undertake the Othello Gate Project?

2 A. This project increases the Othello Gate Station's capacity and, combined with the 3 upgrade to NWP's Othello lateral, increases the system capacity of the Othello 4 distribution system. The Othello area has experienced overall customer growth and 5 increased large volume customer demand, which has surpassed the physical design and 6 contract capacities of the Othello Gate Station. Given NWP's planned upgrade to 7 increase capacity and pressure in the Othello lateral pipeline, this upgrade will ensure 8 Cascade's Othello Gate facilities continue to operate below 20 percent SMYS and are 9 rated for the new inlet MAOP. By operating facilities below 20 percent SMYS, these 10 facilities do not become designated as gas transmission facilities per state and federal 11 pipeline safety regulations, which would require additional maintenance and other 12 programs applicable to transmission facilities.

13

Q. How will Cascade's customers benefit from the Othello Gate Project?

A. This project will improve the physical capacity of the Othello system to meet the design
 day demands of Cascade's core customers and contract demands of Cascade's large
 volume customers. In addition, ensuring Cascade's Othello Gate facilities will continue
 to operate below 20 percent SMYS and are rated for the new inlet MAOP reduces the

- 18 operating costs associated with operating and maintaining gas transmission facilities and
- 19 ensures continued compliance with state and federal pipeline safety regulations.
- 20 Q. Did the Company consider alternative ways to meet the need for the system
- 21 reinforcement in Othello?
- A. Yes. In addition to the Othello Gate Project as described above, the Company considered
 the following alternatives to address the system reinforcement needs:

1		1. <u>No reinforcement</u> : Under this alternative, the Company would not perform
2		any reinforcement.
3		2. <u>Postponing reinforcement</u> : Under this alternative, Cascade would postpone
4		reinforcement for two years.
5	Q.	Why did the Company reject these alternatives and select the Othello Gate Project?
6	A.	None of the alternatives that the Company considered would adequately meet the
7		Company's need to provide reliable service in the Othello distribution system and
8		accommodate future load growth.
9		The Company determined that it could not pursue the first alternative (no
10		reinforcement) because it would result in operating the Othello Gate Station below
11		capacity, reducing the ability to keep the gas pressure deliverable to existing customers.
12		Operating the station and the lateral below capacity could also result in damaging NWP's
13		meter equipment at the station and a loss of metering the inlet gas to the station.
14		The Company determined that it could not pursue the second alternative
15		(postponement) because it would also result in the possibility of loss of service to core
16		and large volume customers due to operating the Othello gate station and pipeline lateral
17		below capacity.
18		As a result, the Company determined that the Othello Gate Project was the best
19		option to meet the Company's need for reinforcement in the area and accommodate
20		future growth.
21	Q.	Was the Othello Gate Project included in the Company's 2020 IRP?
22	A.	Yes, the analysis supporting this project was included in the Company's 2020 IRP, which
23		was submitted to the Commission in February 2021.

1	Q.	What was the timing of the Othello Gate Project?
2	A.	Construction began in early summer 2020 and the project was placed in service on
3		September 28, 2020.
4	Q.	What was the cost of the Othello Gate Project?
5	A.	The total actual cost was \$5,314,207, as detailed in Exh. PCD-2.
6	C.	<u>Walla Walla Gate Project</u>
7	Q.	Please describe the Walla Walla Gate Project.
8	A.	The Walla Walla Gate Project is a system reinforcement project that included installing a
9		new gate station located at NWP's interstate pipeline, approximately 2 miles of new 6"
10		HP steel pipe, 2 new regulator stations, and approximately 2 miles of 6" distribution PE
11		pipe. The project site starts at Pranger Road and heads north to Old Milton Highway then
12		goes east and west along Old Milton Highway to connect to the existing Walla Walla
13		distribution system.
14	Q.	Why did the Company undertake the Walla Walla Gate Project?
15	A.	The pressure in the southern Walla Walla distribution system during peak usage was
16		below design criteria, which required the district to bypass during cold weather events.
17		This area is the outer edge of the Walla Walla distribution system, farthest from existing
18		high-pressure pipelines and regulation. The customers in the southern Walla Walla
19		system are a mix of residential and commercial, and most are large homes or wineries
20		with higher gas demand. In addition, the existing distribution system does not allow for
21		ongoing growth in the southern Walla Walla area.

1 Q. How do Cascade's customers benefit from the Walla Walla Gate Project?

A. The new HP pipeline and regulator station bring the southern Walla Walla distribution
system above design criteria during peak usage and cold weather events, eliminating the
need for bypass operations. Additionally, this project allows Cascade to bring high
pressure gas closer to the areas of Walla Walla with larger residential and commercial gas
load and allows gas service to be offered to new growth occurring in this area of
development. The Synergi diagrams below in Figures 6 and 7 illustrate the improvements
to the Walla Walla system resulting from this project.



)

Figure 6. Synergi Model: Walla Walla – Current Model





Figure 7. Synergi Model: Walla Walla – Improved Model Upon Project Completion

1

2



3 As indicated in the legends for both diagrams, the areas of the map in red and 4 orange indicate pressures below 20 psig. Operating at pressures below 20 psig can result 5 in outages, especially during cold weather events. The improved model after the 6 reinforcement is completed (Figure 7) shows these areas now operating at pressures 7 above 20 psig (as shown by the yellow and green colors), therefore removing the need for 8 remedial action during cold weather events and also providing adequate pressure for new 9 gas load. 10 Q. Did the Company consider alternative ways to meet the need for system

- 11 reinforcement in the southern Walla Walla area?
- A. Yes. In addition to the Walla Walla Gate Project as described above, the Company
 considered the following alternatives to address the system reinforcement needs:

Direct Testimony of Patrick C. Darras Docket UG-21____

1		1. <u>No reinforcement</u> : Under this alternative, the Company would not perform
2		any reinforcement.
3		2. <u>Postponing reinforcement</u> : Under this alternative, Cascade would postpone
4		reinforcement for five years.
5		3. <u>Shorter reinforcement</u> : Under this alternative, Cascade would install only
6		high- pressure pipeline and regulator stations, which would put the high-
7		pressure pipeline and new regulator stations farther away from the existing
8		and new load.
9	Q.	Why did the Company reject these alternatives and select the Walla Walla Gate
10		Project?
11	A.	None of the alternatives that the Company considered would adequately meet the
12		Company's need to provide reliable service in the southern Walla Walla area and
13		accommodate future load growth.
14		The Company determined that it could not pursue the first alternative (no
15		reinforcement) because it would not address the Company's need to bypass during cold
16		weather events to keep system pressures in the southern Walla Walla system deliverable
17		to customers. There are many factors that affect the decision to bypass regulation, and
18		some of these factors are dependent on current temperatures, inlet pressure from the
19		transmission company, time of day, and flow rates. Due to these fluctuating variables, it
20		is difficult to make a concrete rule for when bypass needs to occur, and it instead requires
21		close on-site system observation, often occurring in extreme weather conditions. There
22		are risks involved with bypass operations with personnel required to manually bypass
23		regulation and closely monitor system pressures to prevent over pressuring the

downstream pipeline systems and customer services and meters. Other risks include not
 performing bypass operations soon enough and potentially losing gas service to
 thousands of customers.

4 The Company determined that it could not pursue the second alternative 5 (postponement) because it would require Walla Walla District personnel to continue to 6 bypass during cold weather events until a reinforcement is in place. Additionally, 7 Cascade needs to bring higher pressure and regulation closer to the load to provide 8 service to new residential and commercial customers in the southern Walla Walla area. 9 There are efficiencies and cost savings that can be achieved by installing gas mains while 10 developments and construction are in progress, and it can be more difficult and expensive 11 to install main and services at a later date when the system capacity is increased and new 12 neighborhoods are built out with finished infrastructure (roads, sidewalks, storm, sewer, 13 water, phone, cable, and power).

14 The Company determined that it could not pursue the third alternative (shorter 15 reinforcement) because this option would not adequately meet the Company's needs for 16 reliability. While the Company's modeling showed that a shorter reinforcement option 17 would provide some improvements in the southern Walla Walla distribution system, there 18 still would be customers in the southern Walla Walla distribution system that would 19 experience pressures below design criteria, which would result in a continuing need to 20 bypass during peak usage and cold weather events.

As a result, the Company determined that the Walla Walla Gate Project was the best option to meet the Company's need for reinforcement in the area and to

23 accommodate future growth.


1	Q.	Was the Walla Walla Gate Project included in the Company IRP analysis?
2	A.	Yes. The analysis and timing of the Walla Walla Gate project in Cascade's 2018 IRP
3		remains consistent with the current project as described in this section.
4	Q.	What was the timing of the project?
5	A.	Construction began in July 2020 and was completed in December 2020. The actual in-
6		service date was December 10, 2020.
7	Q.	What was the cost of the project?
8	A.	The total actual cost was \$7,551,516, as detailed in Exh. PCD-2.
9	D.	Arlington Gate Project
10	Q.	Please describe the Arlington Gate Project.
11	A.	This project includes upgrading the existing Arlington Gate Station, taking over pressure
12		regulation at the station from NWP, and replacing 1.15 miles of existing 4" HP outlet
13		pipeline with a 6" HP pipeline in Arlington, Washington. The gate station upgrade
14		includes the installation of a heater, odorizer, and regulation equipment. The overall

15 replacement project area is shown on the map below in Figure 8, below.

Figure 8. Arlington Gate Project



2




- 1 diagrams below in Figures 9 and 10 illustrate the anticipated improvements to the
- 2 Arlington system resulting from this project.
 - 'le l' Node - Anington 4" HP End Point × + 3. + . Facilities Color By Untilate Not Applicable (7) Arington 4" HP End Name: < 1.4500 (411) Descript 4500 - 2.3730 (1395) Control 3730-3.8000 (154) 3.8000 · 4.6261 (91) 261 - 5.1420 (0 o^{238.00} psig 5.1420 (28) Color By Annotation Syn See. 8 Deplay Fa DefaultSt 187.89 psig 197.95 olor by 15 Facility Ppe ht Doternal <Unassigned> · 10 15 Controling E Display Settings... Symbology Settings... Q Astr OK Groat
- Figure 9. Synergi Model: Arlington Current Model

5

3

Figure 10. Synergi Model: Arlington – Improved Model Upon Project Completion





9

As shown in the improved model (Figure 10), the improved pressure and capacity in the pipeline removed the need for remedial action during cold weather events and provide adequate pressure for new gas load.

1	Q.	Did the Company consider alternative ways to meet the need for system			
2		reinforcement in the Arlington area?			
3	A.	Yes, in addition to the Arlington Gate Project as described above, the Company			
4		considered the following alternatives:			
5		1. <u>No reinforcement</u> : Under this alternative, the Company would not perform			
6		any reinforcement.			
7		2. <u>Postponing reinforcement</u> : Under this alternative, Cascade would postpone			
8		reinforcement for 2 years.			
9		3. <u>Gate station upgrade only</u> : Under this alternative, Cascade would upgrade			
10		the gate station but would not replace the HP pipe, which would not			
11		improve the capacity of the Arlington distribution system.			
12	Q.	Why did the Company reject these alternatives and select the Arlington Gate			
13		Project?			
14	A.	None of the alternatives that the Company considered would adequately meet the			
15		Company's need to provide reliable service in the Arlington area and accommodate			
16		future growth.			
17		The Company determined that it could not pursue the first alternative (no			
18		reinforcement) because the Arlington distribution system would continue to experience			
19		low pressures during peak usage and cold weather events, and without installing a			
20		reinforcement, Cascade would be unable to provide gas service to new residential and			
21		commercial customers in the Arlington distribution system.			
22		The Company determined that it could not pursue the second alternative			
23		(postponement) because the Arlington distribution system would continue to experience			


1		low pressures during peak usage until the project is completed. In addition, residential			
2		and commercial growth is occurring in the City of Arlington currently and is anticipated			
3		to continue to increase. By not increasing the capacity of the higher-pressure pipeline,			
4		Cascade would not have the ability to provide service to new residential and commercial			
5		customers in the Arlington distribution system.			
6		The Company determined that it could not pursue the third alternative (gate			
7		station upgrade only) because the Synergi modeling for this option showed some			
8		improvements in the Arlington distribution system, but did demonstrate adequate			
9		reinforcement for the remaining areas experiencing low pressure and did not provide			
10		adequate reinforcement to accommodate requests for additional load.			
11		As a result, the Company determined that the Arlington Gate Project was the best			
12		option to meet the Company's need for reinforcement in the area and to accommodate			
13		future growth.			
14	Q.	Was the Arlington Gate Project included in the Company's IRP analysis?			
15	A.	Yes. The analysis of the Arlington Gate Project was included in the Company's 2018			
16		IRP, which was completed in 2017. The cost estimates and timing of the Arlington Gate			
17		project described in the 2018 IRP were revised due to minor scope changes and increases			
18		in costs for materials and construction.			
19	Q.	What was the timing of the Arlington Gate Project?			
20	A.	Construction started in late 2019 and was completed in September 2020. The actual in-			
21		service date was September 3, 2020.			
22	Q.	What was the cost of the project?			
23	А.	The total actual cost was \$6,058,267, as detailed in Exh. PCD-2.			


1 E. <u>Bellingham 8" HP Project</u>

2 Q. Please describe the Bellingham 8" HP Project.

A. This project involved installing 1,200 ft of 8" HP steel pipe via horizontal directional drill
("HDD") and retiring the existing 10" HP steel pipe attached to the State Street Bridge in
Bellingham, Washington. The overall replacement project area is shown on the map
below in Figure 11, below.







1	Q.	Why did the Company undertake the Bellingham 8" HP Project?
2	А.	The City of Bellingham rebuilt the Whatcom Creek crossing bridge ("State Street
3		Bridge") in Bellingham. Cascade has 10" HP steel pipe attached to this bridge that
4		required relocation due to the City's efforts to rebuild the bridge.
5	Q.	How will this project benefit customers?
6	A.	This project safely relocated the pipeline prior to the bridge reconstruction and upgraded
7		the Bellingham HP line. Specifically, the project established a higher design pressure,
8		allowing for a future uprate of the Bellingham HP system to improve the Bellingham
9		distribution system capacity.
10	Q.	Did the Company consider alternative ways to meet the need for this project?
11	A.	Yes. The original proposed reroute location was identified to avoid having to bore under
12		Whatcom Creek by relocating the pipeline along a route running to the east, allowing for
13		a tie-in to the existing 4" HP line.
14	Q.	Why did Cascade reject this alternative and select the Bellingham 8" HP Project as
15		the best way to meet the Company's needs in the Bellingham area?
16	A.	Upon analysis of the Bellingham system models, this line was shown to have inadequate
17		pressure to provide reliable service south of tie-in location. This alternative route would
18		also have required an additional 1,900 ft of 8" HP pipe to ensure reliable system
19		operation, thereby doubling the cost of the project. The reroute alternative considered was
20		more costly and overall less beneficial to the Bellingham distribution system than the
21		chosen route via HDD under Whatcom Creek.

1 Q. What was the timing of the Bellingham 8" HP Project?

- 2 A. Design for this project began in February 2019, construction began in December 2019,
- 3 and the project was completed and in service in January 23, 2020.

4 Q. What was the cost of the Bellingham 8" HP Project?


5 A. The actual, completed cost of the project was \$1,568,956, as detailed in Exh. PCD-2.

6 F. <u>Moses Lake 4" PE Project</u>

7 Q. Please describe the Moses Lake 4" PE Project.

- 8 A. This project installed approximately 1,800 ft of 4" PE main along Block Rd in Moses
- 9 Lake, Washington, to loop the existing Moses Lake northwest distribution system. The
- 10 overall project area is shown on the map below in Figure 12.
- 11

Figure 12. Moses Lake 4" PE Project




Q. Why did the Company undertake the Moses Lake 4" PE Project?


2 A. The Company's Synergi modelling showed that design day pressures for the northwest 3 Moses Lake distribution pressure system were below design criteria. The reinforcement 4 brought the pressures in the northwestern system above design criteria, which will allow 5 Cascade to better serve the existing core and commercial customers and provide capacity 6 to accept further growth.

7 Q. How will this project benefit customers?


8 The new 4" PE pipeline brought the Moses Lake northwestern distribution system above A. 9 design criteria during peak usage and cold weather events. Additionally, this project 10 allows for new commercial and residential growth occurring in the area. The Synergi 11 diagrams below in Figures 13 and 14 illustrate the anticipated improvements to the 12 Moses Lake system resulting from this project.








1 Figure 14. Synergi Model: Moses Lake – Improved Model Upon Project Completion



As indicated in the legends for both diagrams, the areas of the map in red and orange indicate pressures below 20 psig. Operating at pressures below 20 psig can result in outages, especially during cold weather events. The improved model after the reinforcement is completed (Figure 14) shows these areas now operating at pressures above 20 psig (as shown by the gray, yellow and green colors), therefore removing the need for remedial action during cold weather events and providing adequate pressure for new gas load.

10 Q. Did the Company consider alternative ways to meet the need for this project?

A. Yes, in addition to the Moses Lake 4" PE Project described above, the Company
considered the following alternatives:



2

Exh. PCD-1T Page 41 of 58

1		2. <u>Postponing reinforcement</u> : Under this alternative, Cascade would postpone			
2		reinforcement for 2 years.			
3		3. <u>Pipe replacement</u> : Under this alternative, Cascade would replace existing			
4		pipe with larger pipe.			
5	Q.	Why did Cascade reject these alternatives and select the Moses Lake 4" PE Project			
6		as the best way to meet the Company's needs in the Moses Lake area?			
7	A.	None of the alternatives that the Company considered would adequately meet the			
8		Company's need to provide reliable service in the Moses Lake area.			
9		The Company determined that it could not pursue the first alternative (no			
10		reinforcement) because the northwestern Moses Lake distribution system would continue			
11		to experience low pressures during peak usage and cold weather events, and Cascade			
12		would be unable to provide gas service to new residential and commercial customers and			
13		existing customers wanting to increase their commercial gas load in the northwestern			
14		Moses Lake distribution system without installing a reinforcement.			
15		The Company determined that it could not pursue the second alternative			
16		(postponement) because the northwestern Moses Lake distribution system would			
17		continue to experience low pressures during peak usage. In addition, residential and			
18		commercial growth is occurring in the City of Moses Lake currently and growth is			
19		anticipated to continue to increase. By not looping the Moses Lake system and thus			
20		improving capacity, Cascade would not have the ability to provide service to new			
21		residential and commercial customers and existing customers wanting to increase their			
22		commercial gas load in the northwestern Moses Lake distribution system.			

Direct Testimony of Patrick C. Darras Docket UG-21____

Exh. PCD-1T Page 42 of 58

1		The Company determined that it could not pursue the third alternative (pipe		
2		replacement) because the Synergi modeling for this option showed some improvements		
3	in the northwestern Moses Lake distribution system, but did demonstrate adequate			
4	reinforcement for the remaining areas experiencing low pressure and did not provide			
5		adequate reinforcement to accommodate requests for additional load.		
6		As a result, the Company determined that the Moses Lake 4" PE Project was the		
7		best option to meet the Company's need for reinforcement in the area and accommodate		
8		future growth.		
9	Q.	Was the Moses Lake 4" PE Project included in the Company's IRP?		
10	A.	Yes, the analysis supporting this project was included in the Company's 2020 IRP, which		
11		was submitted to the Commission in February 2021.		
12	Q.	What was the timing of the Moses Lake 4" PE Project?		
12 13	Q. A.	What was the timing of the Moses Lake 4" PE Project? The project was estimated for completion in July 2020, and it was placed in service on		
13		The project was estimated for completion in July 2020, and it was placed in service on		
13 14	А.	The project was estimated for completion in July 2020, and it was placed in service on April 23, 2020.		
13 14 15	А. Q.	The project was estimated for completion in July 2020, and it was placed in service on April 23, 2020. What was the cost of the Moses Lake 4" PE Project?		
13 14 15 16	А. Q. А.	The project was estimated for completion in July 2020, and it was placed in service on April 23, 2020. What was the cost of the Moses Lake 4'' PE Project? The total actual cost was \$213,958, as detailed in Exh. PCD-2.		
 13 14 15 16 17 	А. Q. А. G.	The project was estimated for completion in July 2020, and it was placed in service on April 23, 2020. What was the cost of the Moses Lake 4" PE Project? The total actual cost was \$213,958, as detailed in Exh. PCD-2. Walla Walla 6" Distribution Project		
 13 14 15 16 17 18 	А. Q. А. G. Q.	The project was estimated for completion in July 2020, and it was placed in service on April 23, 2020. What was the cost of the Moses Lake 4" PE Project? The total actual cost was \$213,958, as detailed in Exh. PCD-2. Walla Walla 6" Distribution Project Please describe the Walla Walla 6" Distribution Project.		
 13 14 15 16 17 18 19 	А. Q. А. G. Q.	The project was estimated for completion in July 2020, and it was placed in service on April 23, 2020. What was the cost of the Moses Lake 4" PE Project? The total actual cost was \$213,958, as detailed in Exh. PCD-2. Walla Walla 6" Distribution Project Please describe the Walla Walla 6" Distribution Project. This project consisted of installing approximately 1,800 ft of 6" PE distribution pressure		

Direct Testimony of Patrick C. Darras Docket UG-21____



1

Q. Why did the Company undertake the Walla Walla 6" Distribution Project?

A. Prior to installing this project, the route had 4" steel and 4" PE installed, and it was the
largest pipe bottleneck in the Walla Walla/College Place gas system, leading to
substantial pressure loss on a design day. The new 6" PE pipe was installed parallel to the
existing 4" gas main. Leaving the existing pipe in place eliminates the potential for
isolated steel pipe, which could lead to cathodic protection issues.

1 Q. How will this project benefit customers?

A. This project increases the system capacity in the northeast Walla Walla distribution
system, bringing the system above design criteria during peak usage and cold weather
events. The R-3 regulator station will take full advantage of the added capacity of the 6"
pipe, resulting in an increased maximum demand of almost 20%. Synergi diagrams below
in Figures 16 and 17 illustrate the anticipated improvements to the Walla Walla system
resulting from this project.

8





Figure 16. Synergi Model: Walla Walla – Current Model

Figure 17. Synergi Model: Walla Walla – Improved Model Upon Project Completion

1

2




As indicated in the legends for both diagrams, the areas of the map in red and orange indicate pressures below 20 psig. Operating at pressures below 20 psig can result in outages, especially during cold weather events. he improved model after the reinforcement is completed (Figure 17) shows some⁷ of these areas now operating at pressures above 20 psig (as shown by the gray, yellow and green colors), therefore providing adequate pressure for new gas load and removing needs for remedial action during cold weather events.

⁷ The southeastern system still in red and orange are resolved with the Walla Gate Station project described in section 3 of this testimony.

1	Q.	Did the Company consider alternative ways to meet the need for this project?		
2	А.	Yes. In addition to the Walla Walla 6" Distribution Project as described above, the		
3		Company considered the following alternatives to address the system reinforcement		
4		needs:		
5		1. <u>No reinforcement</u> : Under this alternative, the Company would not perform		
6		any reinforcement.		
7		2. <u>Replacement</u> : Under this alternative, Cascade considered retiring the		
8		existing pipe and installing new pipe.		
9	Q.	Why did Cascade reject these alternatives and select the Walla Walla 6"		
10		Distribution Project as the best way to meet the Company's needs in the Walla		
11		Walla area?		
12	А.	None of the alternatives that the Company considered would have adequately met the		
13		Company's need to provide reliable service in the northeastern Walla Walla area.		
14		The Company determined that it could not pursue the first alternative (no		
15		reinforcement) because the northeastern Walla Walla distribution system would continue		
16		to experience low pressures during peak usage and cold weather events, and Cascade		
17		could lose service to the existing customers in this area unless it installs a reinforcement.		
18		The Company determined that it could not pursue the second alternative (retire		
19		the existing pipe and replace with 6" PE) because if the existing pipe is retired, new steel		
20		pipe would be required for a portion of the route to ensure continuity with the cathodic		
21		protection system. This alternative is more expensive and results in decreased capacity		
22		when compared to the current proposal, due to the capacity difference between a single		

1		6" pipeline and a dual-fed system consisting of a new 6" pipeline and an existing 4"			
2		pipeline.			
3		As a result, the Company determined that the Walla Walla 6" Distribution Project			
4		was the best option to meet the Company's need for reinforcement in the area and to			
5		accommodate future growth.			
6	Q.	Was the Walla Walla 6" Distribution Project included in the Company's 2020 IRP?			
7	А.	Yes, the analysis supporting this project was included in the Company's 2020 IRP, which			
8		was submitted to the Commission in February 2021.			
9	Q.	What was the timing of the Walla Walla 6" Distribution Project?			
10	А.	The project was estimated for completion on November 2020 and was completed a			
11		month earlier than expected. The project was placed in service on October 26, 2020, as			
12		shown in Exh. PCD-2.			
13	Q.	What was the cost of the Walla Walla 6" Distribution Project?			
14	А.	The total cost of the project was \$402,969, as detailed in Exh. PCD-2.			
15	H.	Bremerton Reg Station Project			
16	Q.	Please describe the Bremerton Reg Station Project.			
17	А.	The gas distribution system along Werner Road in Bremerton, Washington had several			
18		regulator stations of various sizes. Some of these stations were located in vaults, and			
19		some had a leak history. The stations in question also did not operate at the same			
20		pressure, which prevented these systems from being looped or further reinforced. This			
21		project installed a single large regulator station in the area of the existing R-038. The			
22		project location is shown on the map below in Figure 18.			





3 Q. Why did the Company undertake the Bremerton Reg Station Project?

A. The new station was sized to accommodate the loads currently spread out through the
following stations: R-021, R-019, R-119, R-038, and R-027. Installing one largercapacity regulator station and eliminating multiple small regulator stations reduces
maintenance costs and improves overall system reliability.

8

Q.

1


2

How will this project benefit customers?

9 A. This new station replaces five smaller stations, thereby increasing the safety and 10 reliability of the gas distribution system in this area. Additionally, migrating the 11 distribution system to a single operating pressure will allow for other pipeline 12 reinforcement opportunities in the future. While all these smaller stations operate at 13 different pressures, these systems cannot be looped or supplied by other nearby pipelines, 14 providing the necessary back feed to ensure reliability of the system. The new above-15 ground station will also increase system capacity, allowing for gas service to be offered 16 to new growth occurring in this area.

Exh. PCD-1T Page 49 of 58

1	Q.	Did the Company consider alternative ways to meet the need for this project?			
2	A.	The Company determined that no alternatives adequately addressed the maintenance			
3		difficulties with the regulator stations in vaults and leak hazards or continued to provide			
4		the capacity needs for the City of Bremerton that this one regulator station provides. In			
5		addition, it is more cost effective to install one larger regulator station than to replace five			
6		smaller regulator stations.			
7	Q.	What was the timing of the Bremerton Reg Station Project?			
8	A.	The Bremerton Reg Station Project was placed in service on November 12, 2020.			
9	Q.	What was the cost of the Bremerton Reg Station Project?			
10	A.	The total actual costs was \$134,782, as detailed in Exh. PCD-2.			
11	I.	Kennewick Odorizer Project			
12	Q.	Please describe the Kennewick Odorizer Project.			
13	A.	This project included replacing the existing vintage odorizer with an updated injection			
14		odorizer. The existing pad, inlet, and injection points can be reused. The overall project			
15		area is shown on the map below.			



3

1

Q. Why did the Company undertake the Kennewick Odorizer Project?

A. The existing odorizer located at the Kennewick gate station was an old Wilroy injectionstyle odorizer. This style of odorizer is no longer supported because the manufacturer no
longer exists, and became increasingly difficult to find replacement parts. The site gauge
for the existing odorizer no longer worked, and therefore it was hard to determine how
much odorant has been used or was in the tank for fill-ups.

9 Q. How will this project benefit customers?

A. This project mitigates the risk of Cascade being unable to repair or maintain the aging,
unsupported odorizer to the gate station. Installing a new odorizer at this station that has a
working site gauge enables Cascade to accurately track odorant usage, will help safely fill
the odorant tank without overfilling or underfilling, and will prevent the risk of running
the tank dry and leaving the pipeline unodorized.

1	Q.	Did the Company consider alternative ways to meet the need for this project?			
2	A.	The Company determined that no alternatives adequately addressed the pipeline-safety			
3		risk or met the odorizing needs for the Kennewick distribution system as the new			
4		odorizer does.			
5	Q.	What was the timing of the Kennewick Odorizer Project?			
6	A.	The project was placed in service on November 20, 2020.			
7	Q.	What was the cost of the Kennewick Odorizer Project?			
8	A.	The total actual cost was \$156,796.			
9	J.	Bremerton Office Project			
10	Q.	Please describe the Bremerton Office Project.			
11	А.	This project involved remodeling the existing Bremerton District office. The address of			
12		the Bremerton District office is 6313 Kitsap Way, Bremerton, Washington. The overall			
13		project area is shown on the map below in Figure 20.			



3 Why did the Company undertake the Bremerton Office Project? Q.

4 Before the project, there was not enough space or offices to accommodate the number of А. 5 Bremerton District employees on staff. The office space also needed to be reconfigured to 6 improve space usage and efficiency for the Bremerton District Operations.

7

How will this project benefit customers? Q.

- 8 The remodeled office space provides a safer work environment for Cascade's Bremerton A.
- 9 Employees and increases the efficiency of the office staff with an updated design and
- 10 larger workspace.


1	Q.	Did the Company consider alternative ways to meet the need for this project?		
2	A.	The Company determined that no alternatives adequately addressed the office needs for		
3		the Bremerton District employees that this minor remodel provides. Relocating or		
4		purchasing new property were less cost-effective means of improving the current office		
5		conditions.		
6	Q.	What was the timing of the Bremerton Office Project?		
7	A.	The Bremerton Office Project was placed in service on December 21, 2020.		
8	Q.	What was the cost of the Bremerton Office Project?		

9 A. The total actual cost was \$781,146.

V. OTHER MAJOR CAPITAL PROJECTS

10 Q. Please provide a brief update of the major capital projects that were discussed in the 2020 GRC, but that are not included for recovery in this case?

A. In its 2020 general rate case, Docket UG-200568, Cascade proposed recovery for three
major capital investments that were expected to be placed in service by 2020. However,
due to delays, two were not in service in 2020, and one has been cancelled. Therefore,
Cascade is not including them for recovery in this case. The status of these projects are
discussed in more detail below.



1		Port. This is a multi-year project that was started in 2018 and was initially
2		expected to be in service by July 2020. In its 2020 rate proceeding, UG-
3		200568, Cascade updated the Commission on the timing of this project,
4		explaining that the Company was delaying completion until 2021 to
5		reduce the 2020 capital budget considering the ongoing COVID-19
6		pandemic. The project is estimated for completion in September 2022. The
7		estimated cost of the project is still \$4,257,740.
8	2.	Mount Vernon Regulator Station Relocation ("Mount Vernon Reg
9		Station Project"). The Mount Vernon Reg Station Project includes
10		replacement and relocation of two existing pressure regulation stations and
11		metering equipment in Anacortes, Washington. The replacement of these
12		stations is necessary due to equipment maintenance issues, accessibility of
13		the stations, and the existing facilities being undersized for the increased
14		load in the area. Design for the project is underway, and construction was
15		expected to begin in late summer 2020 with the project complete in late
16		fall 2020. The project was delayed until 2021, however, because the
17		Company was unable to secure the necessary easements. The project is
18		estimated for completion in November 2021. The total estimated cost of
19		the project is still \$352,513.
20	3.	Richland Odorizer Replacement ("Richland Odorizer Project"). The
21		Richland Odorizer Project anticipated replacing a vintage odorizer with
22		obsolete parts with a new odorizer that performs correctly and can be

1	safely maintained. This funding project has been cancelled; instead a
2	subsequent project is replacing this funding project within its scope.

VI. BLANKET FUNDING PROJECTS

3 Q. Please describe the Company's use of "blanket" funding for capital projects.

4 A. Blanket funding is used for certain types of capital work that historically occurs every 5 year but is not specifically known at the time of budgeting. Examples of blanket funding 6 projects include: 1) replacement of regulator stations due to location, damage or capacity; 7 2) new regulator stations due to growth; and 3) distribution pipe replacement projects in 8 city, state or county roadways due to road widening projects. Replacement of pipe in 9 roadways is heavily dependent upon funding from various state and federal agencies, and 10 it is not known what projects may be required or how much funding will be available 11 from these agencies at the time the Company creates its capital budget.

For blanket funding, work orders that are estimated at less than \$100,000 are
created within a Funding Project. Work orders greater than \$100,000 require their own
Funding Project number.

15 Q. How does the Company budget for blanket funding?

16 A. The Company reviews certain types of capital work that historically occur each year in 17 each state and also communicates with local governing agencies to help determine what 18 projects are planned and/or scheduled locally. The Company then estimates a reasonable 19 budget cost for each state based on current known or scheduled work and historical average 20 annual costs.

1	Q.	In total, how much of the Company's Washington capital budget is attributable to
2		blanket funding projects?
3	A.	Out of the Company's Washington capital budget of \$96.2 million, approximately \$33.1
4		million is attributable to blanket funding projects.
5	Q.	What is the total amount the Company spent on blanket funding projects during the
6		test year?
7	A.	The Company spent \$33,067,806 on gas meters, regulator station, services, and mains that
8		represent growth, replacement, and reinforce blanket funding projects.

VII. CUSTOMER CARE AND BILLING SYSTEM UPGRADE

9 Q. Please describe the Company's Customer Care and Billing System Upgrade 10 ("CC&B Upgrade").

11 A. The MDU Resources Utility Group was running Oracle's Customer Care & Billing

- 12 ("CC&B") version 2.4 as its Customer Information and Billing System. This project
- 13 involved upgrading the CC&B to a newer version, v2.6. This was primarily a technical

14 upgrade to the base architecture of CC&B.

15 Q. Why did the Company perform the CC&B Upgrade?

16 A. Cascade's prior version of CC&B was written in COBOL, which is an outdated

17 application development language. The majority of our custom modules were also written

- 18 in COBOL when CC&B was implemented. We converted these modules into Java, which
- is a modern high-level programming language that is primarily used for creating web-
- 20 based applications. The newer version of CC&B will only support Java modifications,
- and therefore the Company needed to convert its COBOL custom modifications to the

1 Java platform. This was accomplished as an "In-place upgrade," which means Cascade 2 deployed the new code into the existing environment while testing it in both v2.4 and 3 v2.6 environments, thus greatly reducing the time it took to do the actual CC&B version 4 changes. In addition to the code changes, the Company re-configured all the billing rates 5 in the system since v2.6 introduced a new rate engine methodology. 6 Q. Did the Company consider alternatives to the CC&B Upgrade? 7 A. The Company determined that there were no other options available unless it no longer 8 wished to stay current with the vendor's upgrade cycle. As a result, Cascade decided to 9 pursue the upgrade to keep current with the vendor's version releases in order to take 10 advantage of new features and functions, continued vendor technical support, and, more 11 importantly, vendor security patch management. 12 **Q**. How will customers benefit from the CC&B Upgrade? 13 A. Customer benefits will include continual access to future enhancements, improved 14 performance, continual vendor support and security patches that protect their personally 15 identifiable information data.

- 16 Q. What is the total cost for the CC&B Upgrade?
- 17 A. On a Washington-allocated basis, the total cost of the CC&B Upgrade was \$730,309.
- 18 Q. What was the timing for the CC&B Upgrade?
- 19 A. The upgrade went into production on December 31, 2020.
- 20 Q. Does this conclude your direct testimony?
- A. Yes, it does.