

**EXH. CAK-3
DOCKETS UE-19 ___/UG-19 ___
2019 PSE GENERAL RATE CASE
WITNESS: CATHERINE A. KOCH**

**BEFORE THE
WASHINGTON UTILITIES AND TRANSPORTATION COMMISSION**

**WASHINGTON UTILITIES AND
TRANSPORTATION COMMISSION,**

Complainant,

v.

PUGET SOUND ENERGY,

Respondent.

**Docket UE-19 ___
Docket UG-19 ___**

**SECOND EXHIBIT (NONCONFIDENTIAL) TO THE
PREFILED DIRECT TESTIMONY OF**

CATHERINE A. KOCH

ON BEHALF OF PUGET SOUND ENERGY

JUNE 20, 2019

PUGET SOUND ENERGY

**SECOND EXHIBIT (NONCONFIDENTIAL) TO THE
PREFILED DIRECT TESTIMONY OF
CATHERINE A. KOCH**

CONTENTS

I. MAJOR PROJECTS GREATER THAN \$10 MILLION OVERVIEW 1

II. PIERCE COUNTY 230 kV TRANSMISSION AND SUBSTATION..... 2

III. SPURGEON CREEK SUBSTATION 7

IV. LAKESIDE SUBSTATION..... 11

V. TALBOT HILL SUBSTATION 16

VI. WHITE RIVER-ELECTRON HEIGHTS 115 kV TRANSMISSION LINE 22

VII. BELLINGHAM-SEDRO #4 115 kV RECONDUCTOR
TRANSMISSION LINE 26

VIII. CONCLUSION 32

PUGET SOUND ENERGY

**SECOND EXHIBIT (NONCONFIDENTIAL) TO THE
PREFILED DIRECT TESTIMONY OF
CATHERINE A. KOCH**

LIST OF APPENDICES

- | | |
|------------|--|
| Appendix A | Pierce County 230 kV Transmission and Substation Project Implementation Plan |
| Appendix B | Spurgeon Creek Substation Project Implementation Plan |
| Appendix C | Lakeside Substation Project Implementation Plan |
| Appendix D | Talbot Hill Substation Project Implementation Plan |
| Appendix E | White River-Electron Heights 115 kV Project Implementation Plan |
| Appendix F | Bellingham-Sedro #4 115 kV Project Implementation Plan |

1 **PUGET SOUND ENERGY**

2 **SECOND EXHIBIT (NONCONFIDENTIAL) TO THE**
3 **PREFILED DIRECT TESTIMONY OF**
4 **CATHERINE A. KOCH**

5 **I. MAJOR PROJECTS GREATER THAN \$10 MILLION**
6 **OVERVIEW**

7 **Q. Please describe the major projects with capital costs greater than \$10 million.**

8 A. There are six major projects with capital costs greater than \$10 million: i) Pierce
9 County 230 kV Transmission and Substation, ii) Spurgeon Creek Substation, iii)
10 Lakeside Substation, iv) Talbot Hill Substation, v) White River-Electron Heights
11 115 kV Transmission Line, and vi) Bellingham-Sedro #4 115 kV Reconductor
12 Transmission Line. For each project, my testimony describes the need,
13 alternatives considered, how management was informed, and any major changes
14 during the project lifecycle. PSE’s project management process follows industry
15 best practices and is based on our Infrastructure Project Lifecycle Phase/Gate
16 Model, which includes five phases: Initiation, Planning, Design, Execution and
17 Close-out. Each phase includes deliverables and activities that ensure risks are
18 managed, costs are controlled, and benefits will be realized as the project
19 progresses through each phase by way of phase gate approvals. Each project is
20 accompanied by a budget approval document in the form of a Project Change
21 Request or a Corporate Spending Authorization.

1 placed in service December 2017 with final site restoration completed in June
2 2018.

3 **Q. What was the final cost of Pierce 230?**

4 A. The final cost of the project was \$53.1 million without AFUDC. The costs
5 associated with the Alderton substation work were recovered in the 2017 general
6 rate case. PSE seeks recovery of the remainder of the project cost of \$41,957,946
7 associated with the 230 kV transmission line.

8 **Q. Describe the system need for Pierce 230.**

9 A. The primary need for the project was capacity in the bulk power delivery
10 transmission system in Pierce County, which was approaching limits whereby
11 meeting NERC reliability standards would no longer be assured and customer
12 reliability was at risk. The bulk power 230-115 kV transformers at White River
13 and certain 115 kV transmission lines could exceed or were near operating limits
14 for single and multiple element contingencies.

15 **Q. Describe the alternatives evaluated and how this solution was chosen.**

16 A. Four alternatives, including the selected alternative, were evaluated. PSE's
17 solution required all identified needs be addressed and eliminated. In evaluating
18 the alternatives, PSE prioritized the following key decision components: (i)
19 availability of durable operating rights; (ii) minimizing environmental impacts;
20 (iii) using existing corridors where possible; and (iv) minimizing impacts on the

1 public such as schools and constructability. Additionally, PSE established a
2 community advisory committee that evaluated alternatives.

- 3 1) Build a new 230 kV transmission line between White River and Alderton
4 substations – This alternative was selected because it had no negative
5 impacts to the Bonneville Power Administration (“BPA”) transmission
6 system and it met PSE’s long range 230 kV plan, which was to extend a
7 230 kV backbone south of PSE’s White River substation to Pierce and
8 Thurston Counties. The proposed solution was then reviewed for route
9 selection with the assistance of the community advisory committee and
10 ultimately, the West Corridor route was selected. In 2012, PSE re-
11 evaluated alternatives and based on cost and the other factors, the selected
12 alternative remained the best alternative.
- 13 2) Expand Alderton substation to include a 230 kV yard, and loop in the
14 existing White River-BPA South Tacoma transmission line – This
15 alternative was rejected because of negative impacts on the BPA
16 transmission system, and it did not fully meet PSE’s long range 230 kV
17 plan for Pierce and Thurston Counties.
- 18 3) Expand the White River substation and install a third 230-115 kV
19 transformer – This alternative was rejected because of the lack of diverse
20 supply as White River would remain as the only bulk power source for
21 Pierce County. Also, it did not fully meet PSE’s long range 230 kV plan
22 for Pierce and Thurston Counties.

1 4) Operate stand-by peaking generation units at Frederickson as an interim
2 step in the event of system load exceeding 5,200 MW – This alternative
3 was rejected because it provided only a short term, interim solution, and in
4 2012, studies showed that in the absence of the White River substation, if
5 a failure of an aging transformer or a bus contingency occurred, the
6 minimum voltage requirements for Pierce County would barely be met
7 with the Frederickson generator. Additionally, these units may not be
8 available at the time of requirement for planned or emergency outage
9 support.

10 **Q. What benefits does Pierce 230 provide for customers?**

11 A. This project improved reliability and capacity for over 100,000 Pierce County
12 customers, improved bulk power supply reliability, and resolved capacity
13 limitations of the existing bulk power supply to meet NERC reliability standards
14 for bulk electric system performance. The new 230 kV transmission feed to the
15 Alderton substation removed capacity constraints on the 115 kV lines and added
16 operating flexibility for scheduling outages, and improved reliability by providing
17 major support to the Alderton substation for forced outages during storms.

18 **Q. Describe how PSE kept management informed during this project.**

19 A. Using PSE's Project Lifecycle Model, management provided review and
20 approvals for the project. This project was reviewed by management in 2011 as
21 project planning began relative to establishing route selection and community
22 involvement, in February 2013 by the executive level Energy Management

1 Committee to proceed to the project planning phase, and in January 2017 to
2 proceed to the execution phase. Pierce 230 was tracked within PSE's Strategic
3 Project Portfolio throughout the execution phase of the project.

4 **Q. Were there any material changes that impacted the project scope, schedule**
5 **or budget? If so, describe.**

6 A. Yes. In February 2013, this project was estimated at \$40-\$60 million. At the
7 execution approval, the estimate was \$45.7 million without AFUDC. The major
8 changes to this project that increased the cost from \$45.7 million to the actual
9 expenditure of \$53.1 million are as follows:

10 1) Although PSE commenced a competitive bid process for the transmission
11 line contract, PSE did not have recent historic cost data to use in setting its
12 cost estimates due to the fact that PSE does not regularly construct 230 kV
13 infrastructure. The final contract exceeded PSE's estimate by
14 approximately \$2.5 million.

15 2) Between the design and execution phases of this project, PSE updated its
16 financial system and accounting principles to achieve greater financial
17 transparency and more accurate and refined allocation of direct and
18 overhead costs to specific projects. This resulted in an increase of roughly
19 \$2.6 million from the original estimate due to additional direct charges and
20 associated overhead costs that were previously spread across the entire
21 project portfolio and are now calculated and spread according to the direct
22 projects they support (electric, gas, generation, etc.).

1 **Q. Is Spurgeon operating and providing service to customers?**

2 A. Yes.

3 **Q. What was the timeline for Spurgeon?**

4 A. This project was initiated in 2004 with an anticipated need date of 2009. The
5 project was delayed due to: (i) a change in growth projections in 2007 caused by
6 the economic downturn and (ii) the need to focus on another capacity project. The
7 project resumed with public meetings in 2011 but slower growth projections again
8 delayed the project until 2015. Spurgeon was completed and placed in service
9 June 2017.

10 **Q. What was the final cost of Spurgeon?**

11 A. The final cost of the project was \$16,176,316.

12 **Q. Describe the system need for Spurgeon.**

13 A. There were several needs for this project. First, the distribution substation and
14 feeder capacity serving the area required additional distribution capacity. Second,
15 there was the need to improve reliability for customers as more than a third of the
16 120,000 customers in Thurston County were served by two transmission lines
17 between the Olympia and St. Clair substations. Third, with Spurgeon constructed,
18 PSE can initiate future transmission projects to limit outage exposure to
19 customers in the Olympia/Lacey area and establish a more redundant power
20 supply transmission network for the county. Finally, Spurgeon also secures a

1 presence for future 230 kV expansion and bulk power capacity addition to meet
2 long term growth in Thurston County.

3 **Q. Describe the alternatives evaluated and how this solution was chosen.**

4 A. Three alternatives, including the selected alternative, were evaluated. PSE's
5 solution criteria required all identified needs be addressed and eliminated.

6 1) Build a new Spurgeon Creek transmission and distribution substation with
7 provisions for 230 kV in the future – This alternative was selected because
8 it fully met the project needs, including PSE's long-range plan to
9 accommodate customer growth and improved reliability in the area, and
10 the location was close to existing 230 kV transmission. The selected
11 alternative provided greater distribution feeder capacity and operating
12 flexibility than the other two alternatives, which would add station
13 capacity at existing sites.

14 2) Defer the transmission switching portion of the station – This alternative
15 was rejected because it delayed the transmission reliability benefits and
16 was complicated by potential difficulties in acquiring future transmission
17 easements and higher costs associated with the acquisition of these
18 easements in the future.

19 3) Build a new 230 kV transmission substation, at a separate undetermined
20 location, in the future when needed – This alternative was rejected because
21 of the uncertainty of finding an acceptable property in the future.

1 **Q. What benefits does Spurgeon provide for customers?**

2 A. This project improved Olympia area capacity and reduced customer interruptions
3 due to having additional circuit and substation capacity in the area, which
4 improves system redundancy and flexibility. Spurgeon also set the stage for future
5 transmission reliability improvement projects such as sectionalizing the Olympia-
6 St. Clair #1 115 kV line by looping the existing line through Spurgeon, as well as
7 extending a second transmission feed to the Airport substation, which will benefit
8 approximately 30,000 customers. Finally, a new 115 kV interconnection of
9 Spurgeon to BPA Olympia (via Airport substation) will help meet NERC
10 reliability requirements. Spurgeon also secures presence for future 230 kV bulk
11 power capacity addition to serve long term capacity needs of Thurston County.

12 **Q. Describe how PSE kept management informed during this project.**

13 A. Using PSE's Project Lifecycle Model, management provided review and approval
14 of the project. This project was reviewed by management in June 2014 to proceed
15 to the design phase.

16 **Q. Were there any material changes during execution that impacted the project
17 scope, schedule or budget? If so, describe.**

18 A. No. In June 2014, this project was estimated at \$16.4 million without AFUDC and
19 was completed under this estimate.

1 **Q. Have the benefits from this project been realized?**

2 A. Yes. Additional station and feeder capacity added by this project reduced feeder
3 loading on all circuits in the substation group area to below 400 amps. Having a
4 circuit below 400 amps makes it possible to pick up half of the customers on an
5 adjacent circuit during an outage. This reduces customer interruptions by allowing
6 faster restoration times. This project also reduced loading on one of the
7 substations in the study group (Lacey) by 35 percent. This additional capacity
8 now allows this station to pick up some adjacent station load where it was unable
9 to before the project.

10 **IV. LAKESIDE SUBSTATION**

11 **Q. Please describe the Lakeside substation project.**

12 A. The Lakeside substation project (“Lakeside”) is located in the Bellevue area of
13 King County serving customers in the Bellevue, Issaquah, Kirkland and the
14 Newcastle area. Lakeside consisted of rebuilding the existing 115 kV switching
15 station to a breaker-and-a-half bus configuration and included construction of a
16 new station control house. Appendix C contains the Project Implementation Plan
17 for Lakeside.

18 **Q. Is Lakeside operating and providing service to customers?**

19 A. Yes.

1 **Q. What was the timeline for Lakeside?**

2 A. This project was initiated in 2012 with an anticipated need date of 2015. The
3 project was delayed due to other system priorities. Lakeside was completed and
4 placed in service October 2017.

5 **Q. What was the final cost of the project?**

6 A. The final cost of the project was \$17,046,461.

7 **Q. Describe the system need for Lakeside.**

8 A. The primary need for this project was to improve reliability. First, due to aging
9 infrastructure, the structures, foundations and twelve circuit breakers required
10 replacement and had experienced a significant number of faults. Also, multiple
11 electromechanical relay packages needed replacement in the existing control
12 house and the bus work had aging structures and failing foundations. Second, the
13 layout created reliability concerns, all of which would be improved while
14 addressing the aging relays and breakers. Third, the single bus section breaker at
15 Lakeside would put all of the eleven 115 kV transmission lines at risk of opening
16 in the event of a bus section breaker failure, which would drop service to
17 thousands of customers.

18 **Q. Describe the alternatives evaluated and how this solution was chosen.**

19 A. Six alternatives, including the selected alternative, were evaluated. PSE's solution
20 criteria required all identified needs be addressed and eliminated while

1 maximizing construction efficiency to accommodate future transmission
2 expansion in the area.

3 1) Rebuild bus to breaker-and-a-half configuration prior to other planned
4 transmission expansion in the area – This alternative was selected because
5 it addressed all of the aging and outdated equipment and infrastructure
6 while providing a more reliable substation configuration and utilizing the
7 existing substation footprint. It also allowed for the security and drainage
8 systems to be updated to current standards. Transmission lines needed to
9 be temporarily re-routed to maintain a safe and reliable system during
10 construction. There was considerable congestion of transmission lines
11 running in and out of the station on the north and south sides, and this
12 alternative provided the necessary flexibility and space to construct safely
13 while maintaining reliability for customers.

14 2) Rebuild bus to a breaker-and-a-half configuration; construct the first half
15 of the bus by 2017 and the second half after 2020 in a phased approach to
16 allow for future transmission expansion in the area – This alternative was
17 rejected because it was not as efficient as rebuilding the entire substation
18 before other transmission system improvements. Phasing the project by
19 several years created multiple challenges such as working around the
20 existing transmission congestion and partially upgraded site drainage. It
21 required extending the life of already aged infrastructure and did not
22 realize the full benefits of a station rebuild with only rebuilding half of the
23 station.

1 3) Rebuild bus to a breaker-and-a-half configuration after future transmission
2 expansion in the area – This alternative was rejected because it was not as
3 efficient as rebuilding the substation before the future transmission
4 expansion, and it did not address the aging infrastructure within the station
5 in a timely manner.

6 4) Use existing bus configuration, proceed with upgrades – This alternative
7 was rejected because of the low benefit versus cost as the aging
8 infrastructure within the Lakeside substation required several retrofits and
9 equipment upgrades which included circuit breaker replacements,
10 installation of a second bus section breaker, replacement of all of the
11 remaining electromechanical relays, extension of the substation fence to
12 the north, installation of a breaker off the north bus for capacitors,
13 replacement of the south dead-end structures and foundations, and other
14 site improvements, all of which did not bring the benefits gained by the
15 selected alternative.

16 5) Rebuild the 115 kV switchyard located at the pole yard property to the
17 south of the existing Lakeside substation – This alternative was rejected
18 because of transmission line congestion and unacceptable schedule
19 durations.

20 **Q. What benefits does Lakeside provide for customers?**

21 A. This project improved transmission reliability to approximately 114,000
22 customers in the Eastside area by reduced failure exposure from eleven 115 kV

1 transmission lines down to two lines in the event of a bus section breaker failure.
2 The replacement of eleven aging circuit breakers also reduced the likelihood of a
3 breaker failure. The new Lakeside layout accommodated future transmission
4 expansion by adding additional line bays and space for capacitors.

5 **Q. Describe how PSE kept management informed during this project.**

6 A. Using PSE's Project Lifecycle Model, management provided review and approval
7 of the project. This project was reviewed by management to proceed to the project
8 planning phase in June 2014, in January 2015 to proceed to the design phase, and
9 in April 2016 to proceed to the execution phase.

10 **Q. Were there any material changes during execution that impacted the project**
11 **scope, schedule or budget? If so, describe.**

12 A. No. In April 2016, this project was estimated at \$19.1 million without AFUDC
13 and was completed under the estimate.

14 **Q. Have the benefits from this project been realized?**

15 A. Yes. This project is providing improved operational flexibility and transmission
16 reliability to approximately 114,000 customers in the Eastside area. The
17 replacement of twelve at-risk aged 115 kV oil breakers has greatly reduced the
18 likelihood of a breaker failure at Lakeside, impacting thousands of customers
19 radially fed.

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22

V. TALBOT HILL SUBSTATION

Q. Please describe the Talbot Hill Substation project.

A. The Talbot Hill Substation project (“Talbot”) is located in Renton and serves south and central King County. Talbot consisted of rebuilding the 230 kV side of the substation into a double bus, double breaker configuration and included construction of a new station control house and upgrades to the protection systems. Due to system constraints for when a planned outage can occur, Talbot was required to be built in phases: Phase I was the north half of the bus, the new control house, and site improvements and Phase II was the south half of the bus. Phase III was not included in the original scope of work. The need for Phase III was identified by BPA towards the end of Phase I in 2017 and added to the project in 2018. An issue was identified by BPA that showed a potential for fault current to have the ability to bypass the existing current limiting reactors within the BPA substation once PSE’s breakers were energized on the newly configured double bus, double breaker. The solution was to add six current limiting reactors on the Talbot Hill-Maple Valley #1 and #2 230 kV transmission lines that interconnect PSE’s substation with BPA’s Maple Valley substation. This work is currently estimated to increase the total project cost by \$5.5 million and is scheduled to be complete in 2020. Appendix D contains the Project Implementation Plan for Talbot.

Q. Is Talbot operating and providing service to customers?

A. Yes. Phase III discussed above is expected to be in service in 2020.

1 **Q. What was the timeline for Talbot?**

2 A. This project was initiated in 2015. Phase I was completed and placed in service
3 November 2017 and Phase II was completed and placed in service December
4 2018. Phase III is planned for 2020.

5 **Q. What was the final cost of Talbot?**

6 A. The final cost was \$22,634,159. The estimated total cost including the remaining
7 Phase III work is \$28.2 million.

8 **Q. Describe the system need for Talbot.**

9 A. There are several needs for this project. First, the existing 230 kV bus at Talbot
10 that was divided into a north and south bus and separated by a normal open switch
11 could not be operated unless both buses were de-energized. This limited the
12 operational capability and flexibility of the substation. Second, the existing 230
13 kV intertie lines between Talbot and BPA Maple Valley had no breakers on the
14 PSE end of the line at Talbot which required that the Talbot bus differential
15 protection scheme¹ sense for faults all the way to the breaker on the Maple Valley
16 end of the line. A line outage for either of the two intertie lines would take out the
17 entire Talbot north or south 230 kV bus, which occurred three times in the past.
18 The differential protection scheme was an old system with copper control wires

¹ The purpose of a differential protection scheme is to protect equipment from damage or overloads caused by a fault. It operates by monitoring measuring points along a line to determine where a fault may have occurred and then instructing the breakers or other types of equipment to open to isolate customers or equipment.

1 run over public streets and under the Seattle water lines between Talbot and
2 Maple Valley. Third, taking a 230 kV line breaker out of service for maintenance
3 resulted in that line being out of service due to the lack of an auxiliary bus.

4 **Q. Describe the alternatives evaluated and how this solution was chosen.**

5 A. Three alternatives, including the selected alternative, were evaluated. PSE's
6 solution criteria required all identified needs be addressed and eliminated with
7 consideration of cost benefit for maximum flexibility and reliability in the
8 operation of the Talbot substation and related infrastructure along with
9 minimizing the risk to project completion and cost effectiveness.

10 1) Rebuild to a double bus double breaker configuration – This alternative
11 was selected because it provided the most efficient electrical solution,
12 could be built within the existing station footprint, eliminated 230 kV line
13 crossings, reduced bus outage duration during construction, and allowed
14 for phased construction. It also eliminated the bus section switch, retired
15 the old differential scheme, and allowed for maintenance of breakers
16 without taking a line outage. The double bus, double breaker rebuild was
17 the least cost alternative with the most operability.

18 2) Rebuild the existing main and auxiliary bus configuration to current
19 standards and add back-to-back bus section breakers – This alternative
20 provided an acceptable electrical solution but was rejected because of
21 several unacceptable contingencies. Construction required an outage on
22 the entire 230 kV side of the station, which would likely not be feasible

1 due to system outage constraints. It required expansion of the south fence
2 line of the station and multiple transmission line getaway crossings.

3 3) Rebuild to breaker and a half configuration – This alternative provided an
4 acceptable electrical solution but was rejected because (i) it required
5 significant expansion of the east fence line, impacting Seattle Public
6 Utilities water lines and BPA; (ii) presented increased complexity of
7 needing to cross multiple transmission line getaways leaving the
8 substation; and (iii) triggered additional permitting requirements,
9 increasing the risks to the project timeline.

10 **Q. What benefits does Talbot provide for customers?**

11 A. This project provided additional flexibility in the operation of the substation and
12 reduced exposure during outage conditions. Breaker failures no longer result in
13 complete bus outages and a 230 kV bus outage no longer cause outages to the
14 transmission lines.

15 Additionally, as part of the rebuild, breakers were added to two BPA Maple
16 Valley 230 kV intertie transmission lines. This allowed for a fault on the interties
17 to no longer result in a bus outage, only effecting the intertie line. The protection
18 changes associated with the addition of the breakers brought the relays and
19 protection to current industry standards and best practices, and the replaced aging
20 infrastructure improved reliability to the substation operation and overall
21 connected system.

1 **Q. Describe how PSE kept management informed during this project.**

2 A. Using PSE's Project Lifecycle Model, management provided review and approval
3 of the project. This project was reviewed by management in January 2015 to
4 proceed to the design phase, in June 2016 for Phase I to proceed to execution
5 phase, in April 2018 for Phase II to proceed to execution phase, and again in
6 November 2018 to add the Phase III scope of work to the project.

7 **Q. Were there any material changes during execution that impacted the project**
8 **scope, schedule or budget of Phase I and II? If so, describe.**

9 A. Yes. In August 2016, Talbot was estimated at \$16.5 million without AFUDC.
10 There were four material changes during Phase I and Phase II that increased the
11 project cost to \$22.6 million as follows:

12 1) The City of Renton initially stated that a building permit was not needed
13 for the new station control house structure. After construction was started,
14 the City later determined that a permit was required, which stopped
15 construction and delayed the project several months resulting in the need
16 to accelerate the work, as well as triggering additional jurisdictional fees.
17 This resulted in over \$2 million of added labor and overtime, as well as a
18 frontage improvement fee.

19 2) Unforeseen circumstances arose during construction which resulted in
20 additional scope and contractor costs. These changes included
21 contaminated soils, additional drainage and foundation work, additional
22 transmission line relocation, and around the clock site security guard

1 during construction due to vandalism and NERC requirements. These
2 changes resulted in an increase of over \$1.7 million.

3 3) Between the design and execution phases of this project, PSE updated its
4 financial system and accounting principles to achieve greater financial
5 transparency and more accurate and refined allocation of direct and
6 overhead costs to specific projects. This resulted in an increase of roughly
7 \$2 million from the original estimate due to additional direct charges and
8 associated overhead costs that were previously spread across the entire
9 project portfolio and are now calculated and spread according to the direct
10 projects they support (electric, gas, generation, etc.).

11 4) When the double bus, double breaker configuration was chosen for the
12 substation rebuild, coordination with BPA resulted in identification of an
13 issue where BPA's fault protection equipment would be bypassed due to
14 the configuration. PSE entered into an agreement in May 2017
15 (Agreement #16TP-11033) to cost share with BPA in the amount of
16 approximately \$60,000 for scoping the mitigation needed to protect BPA
17 equipment at their Maple Valley substation. In 2018, BPA commenced
18 planning for the line and bus relay upgrades that would be needed at the
19 Maple Valley substation due to the Talbot Hill substation upgrades. PSE
20 entered into a cost share agreement (Agreement # 18TP-11496) and paid
21 \$253,800 to upgrade the interconnected relays between the substations and
22 maintain dedicated positions on the BPA auxiliary bus in case of line
23 outages. Neither of these costs paid to BPA were included in the project

1 cost estimate. This resulted in a total of \$313,800 of added cost to the
2 project.

3 **Q. Have the benefits from Talbot been realized?**

4 A. Some benefits have been realized to date. The updated relays and protection
5 schemes are in service in the upgraded control house, as are the breakers on the
6 230 kV intertie transmission lines between the Talbot substation and BPA's
7 Maple Valley substation. Now, an outage or fault on the Talbot – BPA Maple
8 Valley lines will no longer result in a bus outage. The full benefit will not be
9 realized until all of the breakers are closed in, which requires completion of Phase
10 III, which consists of installing the current limiting reactors on the intertie lines.

11 **VI. WHITE RIVER-ELECTRON HEIGHTS 115 kV**
12 **TRANSMISSION LINE**

13 **Q. Please describe the White River-Electron Heights transmission project.**

14 A. The White River-Electron Heights transmission project (“White River-Electron”)
15 is located in the Alderton and Bonney Lake areas of Pierce County and serves
16 customers in the Bonney Lake, Lake Tapps and Enumclaw areas. White River-
17 Electron consisted of rebuilding the White River-Electron Heights-Krain Corner
18 115 kV transmission system such that it split the three-terminal line into two
19 separate lines. Phase I of the project added a new four-mile 115 kV line from the
20 Rhodes Lake substation to the Alderton substation, which split the three-terminal
21 line into two lines. Phase II of the project split and re-routed 3.2 miles of one of
22 these lines into two separate line segments, White River-Alderton #1 115 kV and

1 Alderton-Krain Corner 115 kV. Appendix E contains the Project Implementation
2 Plan for White River-Electron.

3 **Q. Is White River-Electron operating and providing service to customers?**

4 A. Yes.

5 **Q. What was the timeline for the completion of White River-Electron?**

6 A. This project was initiated in 2002. Phase I was completed and placed in service
7 October 2014. Phase II was completed and placed in service October 2018. The
8 final activities of this project, which includes mitigation planting, permit closeout,
9 and customer reimbursement for crop loss during construction, will be completed
10 in the fall 2019.

11 **Q. What was the final cost of White River-Electron?**

12 A. The final project cost of Phase I and Phase II was \$20 million. The costs
13 associated with Phase I of the project were included in the 2017 general rate case.
14 The final cost of Phase II of the project was \$8,755,773 as of December 31, 2018,
15 with final mitigation and closeout costs expected in late 2019 to be an additional
16 \$140,000.

17 **Q. Describe the system need for White River-Electron.**

18 A. There were several needs for this project. First, the White River-Electron Heights-
19 Krain Corner 115 kV line was vulnerable to storm-related outages due to its
20 combined 37 miles of exposure and three terminal configuration, and a reliability

1 improvement was needed for the approximately 25,000 customers served by this
2 line. Second, load growth in the Bonney Lake and Lake Tapps area of Pierce
3 County required capacity improvements.

4 **Q. Describe the alternatives evaluated and how this solution was chosen.**

5 A. Three alternatives, including the selected alternative, were evaluated. PSE's
6 solution criteria required all identified needs be addressed and eliminated,
7 specifically the customer reliability objectives and PSE's long-term transmission
8 reliability objectives in Pierce County.

9 1) Sectionalize the three-terminal line and route three-line sections to

10 Alderton – This alternative was selected because it fully met the project
11 needs of transmission reliability and capacity. This segmented the
12 customer load from one line servicing 25,000 customers to three lines
13 serving 15,000, 6,000, and 4,000 customers, respectively. This also
14 supported the long-term planning efforts for the Pierce County electric
15 system.

16 2) Sectionalize the three-terminal line and route one new line section to

17 Alderton – This alternative was rejected because it only partially met
18 customer reliability objectives of the project and about 10,000 customers
19 could continue to experience three to four outages per year.

20 3) Install 115 kV breakers at Bonney Lake, Rhodes Lake and Osceola – This

21 alternative was rejected because it did not meet the near and long-term
22 goals of the project or meet the system needs in the area. It leaves the

1 three-terminal connection in place without interconnection to a second
2 230kV bulk power source at Alderton.

3 **Q. What benefits does White River-Electron provide for customers?**

4 A. This project improved transmission reliability for approximately 25,000
5 customers served from five distribution substations in central Pierce County. The
6 project better integrated the Alderton bulk power source to the Pierce County 115
7 kV transmission system and two of the three new lines out of Alderton are
8 directed to the Bonney Lake/Lake Tapps area to provide new transmission
9 capacity to support future area load growth.

10 **Q. Describe how PSE kept management informed during this project.**

11 A. Using PSE's Project Lifecycle Model, management provided review and approval
12 of the project. Phase I of the project was reviewed by management to proceed to
13 the execution phase in February 2014, in December 2014 to proceed to the close
14 out phase for Phase I and for continuation of Phase II, and in May 2018 for Phase
15 II to proceed to the execution phase.

16 **Q. Were there any material changes that impacted the project scope, schedule
17 or budget of Phase II? If so, describe.**

18 A. No. In May 2018, the total lifetime project cost of Phase II was estimated at \$8.2
19 million without AFUDC. The final project cost at the end of 2018 was \$8.4
20 million without AFUDC and was completed within a reasonable variance.

1 **Q. Have the benefits from this project been realized?**

2 A. Yes. With the project in-service, transmission reliability has improved for the five
3 distribution substations in Bonney Lake/Orting Valley area of central Pierce
4 County. Transmission outage exposure was reduced for the Bonney Lake
5 substation (~6,000 customers) from 17 miles to five miles, the Osceola substation
6 (~4,000 customers) from 17 miles to eight miles, and the Orting Valley
7 substations of Rhodes Lake, Knoble and Orting (~14,000 customers) from 17
8 miles to four miles. The project provides interconnection to a second 230 kV bulk
9 power source at Alderton, thereby increasing the redundancy of the transmission
10 network serving Pierce County.

11 **VII. BELLINGHAM-SEDRO #4 115 kV RECONDUCTOR**
12 **TRANSMISSION LINE**

13 **Q. Please describe the Bellingham-Sedro #4 Reconductor Transmission Line**
14 **project.**

15 A. The Bellingham-Sedro #4 Reconductor Transmission Line project (“Sedro #4”) is
16 located in western Whatcom and Skagit Counties serving Burlington and Sedro
17 Woolley. Sedro #4 consisted of rebuilding and reconductoring the existing 24-
18 mile-long Sedro Woolley-Bellingham #4 115 kV line. The line helps connect the
19 Skagit County and Whatcom County 115 kV systems together and directly feeds
20 two distribution substations, Alger and Norlum. To coordinate concurrent
21 distribution system upgrades, this project was constructed in five phases: Phase A
22 includes approximately four miles of the line in Skagit County; Phase B includes
23 approximately seven and a half miles of the line in Skagit County; Phase C

1 includes approximately six miles of the line in Skagit and Whatcom Counties;
2 Phase D includes approximately six miles of the line in Whatcom County; and
3 Phase E includes rebuilding the final a half mile of the line in Skagit County.
4 Appendix F contains the Project Implementation Plan for Sedro #4.

5 **Q. Is Sedro #4 operating and providing service to customers?**

6 A. Partially. Phases A and B are operating and providing service to customers.
7 Phases C, D and E are not.

8 **Q. What was the timeline for the completion of Sedro #4?**

9 A. This project was initiated in 2010. Phase A was completed and placed in service
10 February 2018, and Phase B was completed and placed in service December
11 2018. Phase C is planned for 2020, and Phases D and E are planned for 2021.

12 **Q. What was the final cost of Sedro #4?**

13 A. The final cost of Phases A and B of this project was \$10 million without AFUDC.
14 PSE is seeking recovery of \$8,079,838 in this rate case, as lagging contractor
15 invoices and control zone mitigation costs have been incurred in 2019. The
16 estimated total cost of the project, including all five phases, is \$23 million without
17 AFUDC.

18 **Q. Describe the system need for Sedro #4.**

19 A. There were several needs for this project. First, the low capacity line ratings
20 would cause the line to exceed its allowable capacity ratings for several
21 contingencies and would limit generation capacity in Whatcom and Skagit

1 Counties. The small copper wires also would cause high line losses and the aging
2 infrastructure would lead to extended outages.

3 Second, the low capacity of the Bellingham-Sedro Woolley #4 line caused
4 constraints on regional power flows for over twenty years due to the parallel
5 higher-voltage transmission line, which required PSE to protect the line from
6 loading above its allowable limits by automatically opening the Sedro Woolley
7 substation circuit breaker. Opening the breaker and subsequently the line reduced
8 system reliability in both Whatcom and Skagit Counties, including the Norlum
9 and Alger substations. Additionally, the 6,240 customers served from the Norlum
10 and Alger substations were at an increased risk of outage during this time as each
11 substation has only one transmission source.

12 Third, the aged equipment of the line contributed to outages as there were 27
13 momentary outages and four sustained outages in the five years prior.

14 **Q. Describe the alternatives evaluated and how this solution was chosen.**

15 A. Three alternatives, including the selected alternative, were evaluated. PSE's
16 solution criteria required all identified needs to be addressed and eliminated
17 including the existing line's low capacity, upgrading the aging infrastructure of
18 the line, and addressing the thermal line loading limitation.

- 19 1) Rebuild the 115 kV transmission line – This alternative was selected
20 because it addressed both the capacity deficiency and the reliability
21 problems related to the aging infrastructure for the most economical cost.
22 It included replacing all of the aging wood poles and upgrading the

1 conductor size, which addressed the line loading and reliability issues of
2 the line.

3 2) Maintain existing transmission line, replace bad order poles and keep
4 Corrective Action Plan (“CAP”) – This alternative was rejected because it
5 (a) did not decrease the number of line outages; (b) increased maintenance
6 activities and costs; (c) reduced reliability to both counties due to the line
7 having the potential to being forced out of service from the CAP which is
8 an over-current protection scheme that would automatically open the line
9 at Sedro Woolley substation to prevent it from overloading; (d) lowered
10 reliability to the Alger and Norlum substations; and (e) did not eliminate
11 the line overloads or the existing aging infrastructure.

12 3) Build a new 115 kV transmission line – This alternative was rejected
13 because of its high cost from purchasing land and easements for a new
14 right-of-way (“ROW”), the associated permitting challenges with a new
15 ROW, and it did not address the aging infrastructure of the existing
16 transmission line.

17 **Q. What benefits does Sedro #4 provide for customers?**

18 A. This project improved capacity, and reliability, and reduced operating costs
19 through replacement of deteriorating infrastructure. Replacement of the aging
20 infrastructure reduced the likelihood of unplanned customer outages. With the
21 increased line capacity, PSE will be able to remove an automatic tripping scheme
22 that opens the south end of the line when system events cause the line to overload,

1 which decreases exposure of the customers of Norlum and Alger substations to
2 subsequent line outages, and also strengthens the transmission system between
3 Whatcom and Skagit Counties.

4 **Q. Describe how PSE kept management informed during Sedro #4.**

5 A. Using PSE's Project Lifecycle Model, management provided review and approval
6 of the project. This project was reviewed by management in February 2011 for the
7 substation work to proceed to the design phase, in June 2014 for the transmission
8 line work to proceed to the design phase, in June 2015 to update budget and again
9 in October 2018 to update budget and scope.

10 **Q. Were there any material changes that impacted the project scope, schedule
11 or budget of Phases A and B? If so, describe.**

12 A. Yes. In November 2016, Phase A and Phase B of the project was estimated at
13 \$8.8 million without AFUDC. There were two material changes during Phases A
14 and B that increased the project cost to \$10 million without AFUDC, as described
15 below. PSE is seeking recovery of \$8.1 million in this rate case, as lagging
16 contractor invoices and control zone mitigation costs have been incurred in 2019.

- 17 • Skagit County enacted a Control Zone policy, which is intended to
18 improve safety on county roads, and typically requires poles to be moved
19 further away from the fog line. However, to avoid county farmland zoning
20 restrictions, poles could not be moved out of the right of way, and PSE

1 had to mitigate with added guardrail to meet control zone requirements.

2 This resulted in over \$450,000 in added costs.

- 3 • The project cost also increased due to various construction related issues,
4 including poor soil conditions which added casings and anchors,
5 additional vegetation removal and trimming, as well as added scope
6 including additional disconnect switches and voltage regulators to improve
7 reliability. These changes resulted in a project cost increase of
8 approximately \$750,000.

9 **Q. Have the benefits from Sedro #4 been realized and how does PSE know this?**

10 A. Reliability improvements have been realized for Phase A and Phase B, as these
11 line segments have been rebuilt with new poles, wires, cross-arms and insulators
12 which are not as susceptible to damage. During the 2018-2019 storm season, there
13 were two storm related outages of the Sedro Woolley-Bellingham #4 transmission
14 line, both of which saw customers restored by automatic switching prior to the
15 line being repaired. On December 20, 2018, a tree contacted the rebuilt section of
16 line. The upgraded infrastructure was not damaged, and the outage was restored
17 by simply removing the tree. On January 3, 2019, a tree contacted the line in a
18 section that had not yet been rebuilt; an aged pole was broken and required
19 replacing, which occurred several days later. The line remained fed from only one
20 direction until the repair was complete, which meant that the customers of the two
21 substations were at risk of outage if another storm-related or transmission line
22 fault had occurred prior to the repair. The full benefits of the project will be

1 realized once the project is complete, as the entire line will be rebuilt with
2 upgraded infrastructure and the capacity of the line will increase allowing the
3 automatic tripping scheme, which was previously discussed, to be removed.

4 **VIII. CONCLUSION**

5 **Q. Does this conclude your testimony?**

6 **A.** Yes, it does.